

APPENDIX 13.1

ARCHAEOLOGICAL INVENTORY DESCRIPTIONS OF SITES WITHIN 2 KM OF PROPOSED DEVELOPMENT

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
CO093-113----	18th/19th century house	630m	Small rectangular house or cabin which has been partially built into the base of a south facing slope. It is orientated NE-SW with internal measurements of 4.6m L by 2.45m W with a maximum height of 1.7m at the W gable. The rear (N) wall is almost completely dug into the slope with just a single course of stones at ground level. The front wall is built up to a H of c.1m with a 0.8m wide door opening in it. It is sheltered to the west by a large boulder and faces a small stream to the south. Though probably only constructed in the 19th Century this building is of interest as it appears to be an example of a type of cabin the very poorest in society would have built, possibly for temporary farm labourers.
CO093-027002-	Anomalous stone group	760m	In pasture on W-facing slope to E of standing stone (CO093-02701-). Two low stones at right angles to each other. Southernmost stone; rectangular plan with long axis E-W (H 0.46m; 0.59 x 0.3m). Second stone set at right angles to first with long axis N-S (H 0.39m; 0.8m x 0.3m). Prostrate third stone to E of first.
CO093-054001-	Anomalous stone group	1,130m	In level pasture. Described in OS Name Book (1842) as 'a circle of gallauns' three of which are still standing and one lying prostrate and is commonly called a stone circle in other parts of the country'. No visible surface trace.
CO093-081----	Bullaun stone	155m	In rough hill grazing, on bog, on an E-W terrace on the S side of Shehy Beg. A roughly square stone (0.6m x 0.6m; H 0.16m above ground level), which protrudes above the surface of the bog, has a smooth-surfaced oval bowl (0.36m x 0.27m; D 0.1m) in its upper surface.
CO093-004----	Burial ground	1,795m	Named 'Killeen Burial Ground' on 1842 OS 6-inch map. In pasture, on N-facing slope. Triangular area defined by two field fences forming S apex of triangle; N edge defined by low rise (H 1m). Interior partially overgrown. Burials marked by low rectangular mound of stones, aligned N-S.
CO093-011001-	Burial ground	1,470m	In pasture. Irregular area (32m N-S; 30m E-W) defined by holly growth and numerous grave markers.
CO093-104----	Burnt spread	525m	This monument was reported by archaeologist Tony Miller. He describes it as follows: "In an area of young forestry near the top of a ridge and just to the west of Carrigmount. The butter path which crosses neighbouring Shehy Beg passes just south of the site. A track for machines to access the forestry has been scraped out up into the hill here and in the process has exposed a section of burnt spread roughly 4m in length. It is not possible to see its full extent and there is no mound visible on either side of the track."
CO092-061001-	Enclosure	1,910m	In rough hill grazing on a bog-covered terrace, on a N-facing slope overlooking the valleys of the Gortloughra and Owvane Rivers. A roughly circular area (8m E-W; 7m N-S) is defined by the partially collapsed lower courses of a roughly built drystone wall (T 0.5m; H 0.45m), which protrudes above the surface of the shallow bog. Many of the stones are leaning against each other and are set at right angles to the line of the wall. A low mainly sod-covered mound (H 0.35m) of stones of varying sizes occupies most of the interior. Its function is unclear. A hut site (CO092-061002-) abuts the enclosure at W.

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
CO092-075002-	Enclosure	430m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains. A level circular area (9m N-S; 8.5m E-W) is defined by the remains of a stone wall which protrudes above the surface of the bog. The wall displays traces of a double row of contiguous upright slabs (T 1m; H 0.5m). Three hut sites (CO092-075003-, CO092-075004-, CO092-075005-) abut the interior of the enclosing element along the W arc. This enclosure lies within a complex of field boundaries (CO092-075001-).
CO093-010----	Enclosure	940m	On break in N-facing slope of Shehy mountains; commanding view to N and E. Circular area (diam. 18m N-S; 16m E-W) enclosed by ruinous stone wall best preserved to W (int.H 0.95m; ext. H 0.5m; Wth 1.80m); partially revetted inside and outside with upright slabs. Entrance to SE (Wth 1m) marked by two upright stones (H c. 0.65m). Interior overgrown; to W, dense scatter of stones, possibly indicates internal structure.
CO093-025----	Enclosure	600m	On lower SE-facing slope of Shehy mountains. Roughly circular area (diam. c.24m) defined by stone bank (ext. H 0.8m; Wth 3.5m) SSW->NNE; overgrown scarp NNE->SSW (possibly quarried in places). Interior heavily overgrown with briars and ferns.
CO093-080002-	Enclosure	75m	In rough hill grazing on bog, with occasional outcropping rock, on a large terrace on the upper S-facing slopes of Shehy Beg. A D-shaped area (9m N-S), with the straight side at N (L 14m), is defined by the linear face of outcropping rock at N and elsewhere by the remains of a stone wall (T 0.4m; H 1m). The stone wall consists mainly of contiguous stone slabs protruding above the surface of the bog. Rushes obscure the interior. There is a hut site (CO093-080001-) c. 60m to the E. A length of field wall (L c. 14m) emerges from the bog c.11m out from the western side of the enclosure. It consists of mostly flat stones set on edge contiguously (H. 0.8m). It forms a partial outer element to the enclosure.
CO093-088----	Enclosure	425m	In rough hill grazing, on bog, in a sheltered hollow on the N-facing slopes of Shehy More. A roughly rectangular area (7.6m N-S; 4m E-W) is enclosed by a roughly built, partially collapsed, drystone wall (T 0.8m; max. H 1.1m). The entrance is unclear due to collapse. Rushes obscure the level interior. A hut site (CO093-089----) lies c. 100m to the NW.
CO093-099----	Enclosure	90m	This enclosure was reported to the Archaeological Survey of Ireland by Tony Miller on 28th January 2013. He describes it as follows: "This enclosure is c. 25m southwest of the hut site already described (CO093-098----) and lies to the south of the same large rock outcrop. It is sub-circular in shape measuring c. 11m east-west and c. 9m north-south internally. The containing walls survive to a height of c. 1m and are in a collapsed state apart from the southern section, which is constructed of contiguous upright slabs of rock. It is sited in an area of rough mountain grazing and looks out over the boggy uplands to the east. The interior of this enclosure appears slightly domed, possibly created either by a drainage feature inside the walls or by a feature in the centre of the enclosure. In the south west quadrant of the enclosure there is a rough line of partially buried stones indicating another possible feature."
CO093-101----	Enclosure	105m	This enclosure was reported to the Archaeological Survey of Ireland by Tony Miller on 28th January 2013. He describes it as follows: "This enclosure is c. 40m to the south-west of the previous enclosure recorded (CO093-099----). It has a similar aspect but is sited in poorer,

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
			boggier land and is also just south of the same rock outcrop. It is a sub-circular enclosure measuring c. 11m east-west and c. 9m north-south. The perimeter wall was constructed mainly out of contiguous slabs set on edge which are all collapsed. To the south one slab is set radially and probably marks the entrance. No internal features visible."
CO093-110----	Enclosure	1,910m	Partial remains of a large enclosure in rough grazing just to the east of cleared fields and to the west of semi mature forestry. It is situated on a level area on a north facing slope with a stream running to the east at its base. The valley rises to the west and the summit of Shehy Mountain. The enclosure would have been roughly circular in plan but the eastern half has been cleared probably during the making of the field adjacent to it. It has a N-S D of 24m. The enclosing wall is made of single stones with a maximum H of 0.9m
CO092-064----	Field boundary	1,620m	In rough hill grazing on bog, on a N-facing slope overlooking the valleys of the Gortloughra and Owvane Rivers. A network of relict stone field boundaries (T 0.6m; H 0.4m) occur along the hillside in this roughly rectangular area (c. 350m E-W; c. 150m N-S). In general the walls are curvilinear and discontinuous. The walls are visible in the areas of cutaway bog and elsewhere, in uncut bog, where they protrude intermittently above the surface. An enclosure (CO092-062001-) and a hut site (CO092-062002-) are within the E half of the field boundary network.
CO092-075001-	Field boundary	430m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains. A network of both linear and curvilinear, relict, stone field boundaries (T 0.5m; max. H 0.6m) occur in a roughly rectangular area (c. 150m E-W; c 110m N-S). The boundaries protrude intermittently above the surface of the bog and consist mainly of a mixture of upright, leaning and fallen slab-type stones. An enclosure (CO092-075002-) and six hut sites (CO092-075003-, CO092-075004-, CO092-075005-, CO092-075006-, CO092-075007-, CO092-075008-) occur within the field boundary network.
CO092-090----	Field boundary	1,765m	This is a boundary formed of field stones surviving to a maximum height of 0.5m. It is c.90m in length and runs uphill (south – north) from the better land to the south before swinging to the northeast and finishing around a drier patch of grazing. There is a 2m wide gap in the boundary c two thirds of the way uphill. It would also appear to extend further to the south into an area of partially improved grazing.
CO092-095----	Field boundary	1,765m	This relict field boundary survives to a length of c.90m and runs partly up a south facing ridge of rough, mountain grazing. Close to the northern limit it turns to the northeast and finishes partly enclosing an area of drier ground. Built from random field stones it survives to a maximum height of c.05m.
CO093-097----	Field boundary	60m	This relict field wall was reported to the Archaeological Survey of Ireland by Tony Miller on 28th January 2013. He describes it as follows: "A section of ancient field walling which is in a collapsed state and partially buried by the turf and bog. An 18m linear section is visible running from the southwest, where it abuts a rock outcrop, to the northeast, where it runs down hill and out into the bog."
CO093-102----	Field boundary	175m	This possible enclosure was reported to the Archaeological Survey of Ireland by Tony Miller on 28th January 2013. He describes it as follows: "This site is immediately south of a

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
			high rock outcrop, on a small plateau of rough grazing and bog overlooking open ground to the east. It consists of a curved section of wall built of contiguous slabs with a maximum height of c. 0.8m and a length of c. 10m. This wall could either be an unfinished or partially destroyed length of field boundary or enclosure wall. I would favour the latter as it has a similar look to the two previous enclosures described (CO093-099---- & CO093-101----)"
CO093-103----	Field boundary	150m	This relict field boundary was reported to the Archaeological Survey of Ireland by Tony Miller on 28th January 2013. He describes it as follows: "This is a long, curvilinear section of ancient field wall running roughly in a northwest to east direction. At least 50m of this wall is visible built of roughly grouped field stones now in a collapsed state and overgrown by bog. To the west of it the ground is a drier rough grazing while to the east of it the ground is much boggy. It does appear to be on the eastern boundary of the better land of all the sites described above (CO093-097---- to CO093-102----).
CO093-106----	Field boundary	80m	This relict field boundary was reported to the Archaeological Survey of Ireland by Tony Miller on the 10th of December 2014. He describes it as follows: "A relict field boundary running roughly north-south in an area of rough mountain grazing and bog. It is c. 200m in length and skirts the bottom of a rounded hill of drier ground rising to the east while it is wetter and boggy to the west. A single line of field stones protrude from the turf and a single stone standing upright and higher than the rest possibly marks a gap in the boundary."
CO093-107----	Field boundary	335m	This relict field boundary was reported to the Archaeological Survey of Ireland by Tony Miller on the 10th of December 2014. He describes it as follows: "A relict field boundary running north- south for c. 30m across a level terrace of ground c. 100m west of a stream. It is in a drier area of otherwise boggy, rough grazing. It is c. 0.5m wide with a maximum height of 0.6m with the single line of stones rising from beneath the turf. To the north it abuts a rock face and to the south it ends at the edge of a drop down to another level area."
CO093-029----	Fulacht fia	1,540m	Burnt material visible in section in recently cut-through field fence. Spring to NE.
CO093-054002-	Fulacht fia	1,130m	Roughly horseshoe-shaped grass-covered mound (L 19.8m; Wth 16.5m; H 0.9m), on level pasture. Opening to W (Wth 4m).
CO093-090----	Fulacht fia	575m	In level pasture, c. 10m E of a stream. A low grass-covered horseshoe-shaped mound (c. 20m E-W; c. 14m N-S; H 0.8m) of heat-shattered stones and charcoal-enriched soil with a W-facing opening (Wth 4m). Patches of burnt material are exposed on the SW side and on the E arm of the mound.
CO093-094----	Fulacht fia	1,045m	No entry
CO093-108----	Fulacht fia	660m	This possible fulacht fia was reported to the Archaeological Survey of Ireland by Tony Miller on the 10th of December 2014. He describes it as follows: "During recent cleaning of a drain in this field a large quantity of burnt stone and charcoal rich soil was brought up to the surface. It is not possible to see exactly where the burnt spread is but it is somewhere immediately south of the causeway over the drain, connecting two fields. A large fulacht (CO093-090--) is sited c 150m to the north west and a stream runs c10m to the south. It is a level area of improved grassland, close to the base of Shehy Mountain. The stream is a tributary of the Bandon River."

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
CO093-109----	Fulacht fia	640m	This fulacht fia was reported to the Archaeological Survey of Ireland by Tony Miller on the 10th of December 2014. He describes it as follows: "Horse shaped mound, partially levelled, in NW corner of a large reclaimed field of pasture, next to a stream. It is about 20m north of site one [CO093-108----] and adjacent to the same open drainage ditch. The mound has its open side facing the drain c. 3m to the west. Its total size is c. 10m N-S, 6m E-W, 0.5m in height with the opening of the trough c. 3m in width. It is under the spreading branches of an old oak tree."
CO092-061002-	Hut site	1,910m	In rough hill grazing, on a bog-covered terrace, on a N-facing slope overlooking the valleys of the Gortloughra and Owvane Rivers. The remains of a roughly rectangular hut site (2.1m N-S; 1.3m E-W) defined by a stone wall (T 0.55; H 0.3m) which protrudes from the shallow bog. The entrance (Wth 0.4m) is at the N. An enclosure (CO092-061001-) abuts this hut site at the E.
CO092-062001-	Hut site	1,620m	In rough hill grazing, on shallow bog in a heather-covered terrace, on a N-facing slope. The remains of a D-shaped hut site (6.7m E-W) defined by a partially collapsed, curving, drystone wall (T 0.7m; H 0.6m) with a straight E side (L 5.8m). The lower courses of the wall protrude from the shallow bog. The interior is slightly uneven and contains a scattering of rubble. There is an entrance (Wth 0.55m) at the SE. Field boundaries (CO092-064----) abut the hut site at the S, W and N. There is another hut site (CO092-062002-) c. 30m to the NE.
CO092-062002-	Hut site	1,635m	In rough hill grazing, on a N-facing heather-covered slope, overlooking the valleys of the Gortloughra and Owvane Rivers and within the E half of a network of relict field boundaries (CO092-062001-). The remains of a D-shaped hut site (4m E-W) defined by the collapsed lower courses of a curving stone wall (T 0.65m; H 0.6m) with a straight W side (L 4m). The stone wall protrudes above the surface of the bog. Rubble is scattered in the interior. A nearby rocky ridge at the S provides shelter for the hut site. Another hut site (CO092-062001-) is c. 30m to the SW.
CO092-063001-	Hut site	1,305m	In rough hill grazing, on a heather and rush-covered terrace on a N-facing slope. The remains of a D-shaped hut site (3.1m N-S) defined by a partially collapsed, curving, drystone wall (T 0.65m; H 1.1m) with a straight N side (L 4.3m). The wall is best preserved SW-N. The entrance (Wth 0.6m) is at the S. Rubble is scattered on the level interior. Another hut site (CO092-063002-) is c. 25m to the S.
CO092-063002-	Hut site	1,225m	In rough hill grazing, on a heather and rush-covered terrace on a N-facing slope. The remains of a rectangular hut site (2.8m N-S; 2.3m E-W) defined by a largely collapsed, roughly built, stone wall (T 0.6m; H 0.8m). The entrance (Wth 0.5m) is at S. The level interior, which is obscured by moss-covered rubble, is cut (D 1m) into the upslope at S. Another hut site (CO092-063001-) is c. 25m to the N. A subsequent inspection of this hut site in June 2007 reported that the area has been planted in forestry and that this hut site has been partly demolished.
CO092-063003-	Hut site	1,195m	In rough hill grazing, on a N-facing heather-covered slope overlooking the valleys of the Gortloughra and Owvane Rivers. The remains of a rectangular hut site (3.2m N-S; 2m E-W) defined by the collapsed lower courses of a roughly built drystone wall, some of which protrude from shallow bog. Rubble partially obscures the interior of the hut site. The collapsed entrance (Wth c. 0.4m) is at N.

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
CO092-074----	Hut site	415m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains. The remains of a circular hut site (diam. 3m) defined by traces of a wall (T 0.6m; H 0.3m) which consist of a double row of contiguous upright slabs that protrude above the surface of the bog. The level interior is raised (H 0.15m) at the S and cut (D 0.2m) into the upslope at the N to compensate for the slope.
CO092-075003-	Hut site	430m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains and within an enclosure (CO092-075002-). The remains of a D-shaped hut site (1.4m N-S) defined by the jumbled lower courses of a curving stone wall (T 0.4m; H 0.3m) with a straight S side (L 2m) which abuts the inner face of the enclosure at the WSW and another hut site (CO092-075004-) at N. The stone wall protrudes above the surface of the bog. The hut site lies within a network of relict field boundaries (CO092-075001-).
CO092-075004-	Hut site	430m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains and within an enclosure (CO092-075002-). The remains of a circular hut site (diam. 2m) defined by the collapsed lower course of a stone wall (T 0.5m; H 0.4m) which protrudes above the surface of the bog. The hut site abuts the inner face of the enclosure at the W, a hut site (CO092-075003-) at the S and another hut site (CO092-075005-) at the N. The hut site lies within a network of relict field boundaries (CO092-075001-).
CO092-075005-	Hut site	430m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains and within an enclosure (CO092-075002-). The remains of a circular hut site (diam. 1.9m) defined by the jumbled lower course of a stone wall (T 0.5m; H 0.6m) which protrudes above the surface of the bog. The hut site abuts the inner face of the enclosure at the WNW and another hut site (CO092-075004-) at the S. The hut site lies within a network of relict field boundaries (CO092-075001-).
CO092-075006-	Hut site	400m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains and within a network of relict field boundaries (CO092-075001-). The remains of a circular hut site (diam. 2.3m) defined by the jumbled lower course of a stone wall (T 0.6m; H 0.4m) which protrudes above the surface of the bog. There is an enclosure (CO092-075002-) c. 20m to the W.
CO092-075007-	Hut site	400m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains and within a network of relict field boundaries (CO092-075001-). The remains of a rectangular hut site (3m E-W; 1.5m N-S) defined by the collapsed lower course of a stone wall (T 0.45m; H up to 0.6m) which protrudes above the surface of the bog.
CO092-075008-	Hut site	430m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains and within a network of relict field boundaries (CO092-075001-). The remains of a D-shaped hut site (5m E-W) defined by the jumbled lower courses of a curving stone wall (T 0.6m; H 0.7m) with a straight W side (L 5m). The stone wall protrudes above the surface of the bog. Another hut site (CO092-075009-) abuts the enclosing element of this hut site externally at the W.
CO092-075009-	Hut site	430m	In rough hill grazing, on a terrace on the S-facing slopes of the Shehy Mountains and within a network of relict field boundaries (CO092-075001-). The remains of a D-shaped hut site (1.8m E-W) defined by the jumbled lower courses of a curving stone wall (T 0.5m; H 0.5m) with a straight E side (L 2.2m). The stone wall protrudes above the surface

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
			of the bog. Another hut site (CO092-075008-) abuts the enclosing element of this hut site externally at the E.
CO092-076----	Hut site	480m	In rough grazing, on the N side of a sheltered E-W hollow. The remains of a D-shaped hut site (4m N-S) defined by the roughly built, mainly collapsed, lower courses of a curving stone wall (T 0.5m; H 0.4m) with a straight S side (L 5m). The interior of the hut site is obscured by rubble.
CO092-079----	Hut site	1,910m	No entry
CO092-097----	Hut site	1,970m	In open pasture. A sub-circular hut site consisting of collapsed dry-stone walling 0.6m W and max H of 0.6m measuring externally 3m E-W and 3.5m N-S. The western side is slightly flattened and forms the northern terminus of a 12m length of N-S relict field boundary. There is no obvious entrance to the hut site.
CO093-077001-	Hut site	145m	In rough hill grazing, on bog, on a terrace on the upper S-facing slopes of Shehy Beg. The remains of a D-shaped hut site (6.5m N-S) defined by a curving stone wall (T 0.7m; H 0.65m) with a straight N side (L 6m). The stone wall protrudes above the surface of the bog. Another hut site (CO093-077002-) is c. 60m to the W.
CO093-077002-	Hut site	100m	In rough hill grazing, on bog, on a terrace on the upper S-facing slopes of Shehy Beg. The remains of an oval hut site (3m N-S; 2m E-W) defined by a jumbled stone wall (T 0.7m; H 0.5m), the lower courses of which protrude above the surface of shallow bog. Another hut site (CO093-077005-) adjoins this one at the S and a second hut site (CO093-077001-) is c. 70m to the E.
CO093-077003-	Hut site	90m	In rough hill grazing, on bog, on a terrace on the upper S-facing slopes of Shehy Beg. The remains of a circular hut site (2m N-S; 1.8m E-W) defined by a jumbled stone wall (T 0.6m; H 0.4m) which protrudes from traces of a low peaty bank (H 0.05m). Another hut site (CO093-077004-) is c. 10m to the E and a second hut site (CO093-077005-) is c. 30m to the N.
CO093-077004-	Hut site	90m	In rough hill grazing, on bog, on a terrace on the upper S-facing slopes of Shehy Beg. The remains of a circular hut site (diam. 2m) defined by a scatter of stones (T 0.5m; H 0.6m) which protrude above the surface of shallow bog. A break at the SE may indicate the entrance location. Another hut site (CO093-077003-) is c. 10m to the W.
CO093-077005-	Hut site	100m	In rough hill grazing, on bog, on a terrace on the upper S-facing slopes of Shehy Beg. The remains of a circular hut site (4.8m E-W; 4.6m N-S) defined by a jumbled stone wall (T 0.6m; H 0.5m) which protrudes SW-SE above the surface of shallow bog and by traces of the stone wall SE-SW. Another hut site (CO093-077002-) adjoins this hut site at the N and a second hut site (CO093-077003-) is c. 30m to the S.
CO093-079001-	Hut site	80m	In rough hill grazing, on bog, on the N side of a terrace on the upper S-facing slopes of Shehy Beg. The remains of a circular hut site (diam. 2.3m) defined by a wall (T 0.6m; H 0.5m) which consists mainly of large slabs, some of which are set at right angles to the perimeter. The level interior, which in pasture, is raised (H 0.1m) at the S and cut (D 0.2m) into the upslope at the N. The entrance (Wth 0.6m) is at the SE. Another hut site (CO093-079002-) is c. 70m to the SW.
CO093-079002-	Hut site	125m	In rough hill grazing, on bog, on a terrace on the upper S-facing slopes of Shehy Beg. The remains of a circular hut site (3.8m E-W; 3.6m N-S) defined by the lower courses of a collapsing drystone wall (T 0.7m; H 0.5m) which protrudes above the surface of the bog. The level interior,

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
			which is covered with heather, is raised (H 0.3m) at the S. Another hut site (CO093-079001-) is c. 70m to the NE.
CO093-080001-	Hut site	25m	In rough hill grazing, on bog, on a terrace on the upper S-facing slopes of Shehy Beg. The remains of a circular hut site (diam. 4.3m N-S) defined by a fern-covered stone wall (T 0.65m; H 0.6m) NW-S and elsewhere by intermittent traces of the wall. The entrance (Wth 0.8m) is at the E. The level interior is in pasture. An enclosure (CO093-080002-) is c. 60m to the W.
CO093-082----	Hut site	175m	In rough hill grazing, on bog, on the S edge of an E-W terrace on the S side of Shehy Beg. The remains of an oval hut site (5.2m E-W; 3m N-S) defined by an intermittent stone wall (T 0.75m; H 0.4m) which protrudes above the surface of the bog. The level interior is in pasture and a break at S may be the location of the entrance.
CO093-083----	Hut site	145m	In rough hill grazing, on a SE-facing slope. The largely denuded remains of a circular hut site (diam. 2.9m) defined by a stone wall (T 0.4m; H 0.3m) which protrudes intermittently above the surface of shallow bog. A bullaun stone (CO093-081----) lies c. 2m to the N.
CO093-089----	Hut site	505m	In rough hill grazing, on bog, on a terrace on the N-facing slopes of Shehy More. The remains of a D-shaped hut site (2.5m N-S) with a straight S side (L 2.6m) are defined by the jumbled lower courses of a drystone wall (T 0.6m; H 0.8m). The stone wall protrudes above the surface of the bog. The straight S side is cut (D 0.7m) into the upslope at the S. Loose stones are scattered in the E-sloping interior. There is an entrance (Wth 0.6m) at the E. An enclosure (CO093-088----) lies c. 100m to the SE.
CO093-093001-	Hut site	1,045m	No entry
CO093-093002-	Hut site	1,045m	No entry
CO093-098----	Hut site	80m	This hut site was reported to the Archaeological Survey of Ireland by Tony Miller on 28th January 2013. He describes it as follows: "This sub-circular hut site is immediately south of an extensive rocky ridge and c. 25m south of site 1 (CO093-097----) and is in an area of rough mountain grazing. It measures, internally, c. 4m east-west and c. 4.5m north-south and only a single ruinous course of the walls is visible, c. 0.7m in width. The entrance is to the west and is marked by two radially set upright slabs. It is c. 1.2m in width and opens towards a nearby enclosure. It overlooks a wide expanse of bog and rough grazing to the east."
CO093-100----	Hut site	100m	This hut site was reported to the Archaeological Survey of Ireland by Tony Miller on 28th January 2013. He describes it as follows: "In addition this enclosure (CO093-099----) has a small hut site built against the exterior of the southern perimeter wall, just where some of the contiguous slabs are found. Its internal measurements are c. 1.8m north-south and c. 2m east-west. The walls are in a collapsed state and do not stand much above the ground level. No entrance is visible."
CO093-115----	Hut site	10m	A sub-rectangular hut site situated at the western end of a level terrace with an enclosure c.40m to the east. It has clear views over the main plateau of Shehy Mountain including further hut sites on the next 'step' down to the east (CO093-077001-to CO093-077005-). It measures c.4m east- west and c. 1.8m north-south with no clear entrance location. A c. 10m length of field boundary running north-south lies c. 2m to the east of this hut site.
CO093-030----	Kiln - lime	1,715m	Roadside (disused); on NE-facing slope. Overgrown front elev. (H c. 2m); pair of lintelled passages (H 0.6m; Wth

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
			0.4m) at base leading into rectangular stone-lined funnel (2.73m x 1.78m) with rounded corners.
CO093-011002-	Mass-rock	1,470m	This is '...what is known as "The Mass Altar"' (Anon. 1994, 6) and comprises a flat slab of rock (c. 3m x 1.2m; T 0.4m) which lies level with the SSE-sloping ground. The upper surface of the slab is level but there is a drop on its S side where it is supported towards either end by two orthostatic blocks. There is a chamber-like area (D 0.6m) dug out from under the slab between the supports.
CO093-056----	Quarry	1,255m	Listed as a 'quarry' in the SMR (1988) and the RMP (1998). The evidence is not sufficient to warrant accepting this as the location of an archaeological monument.
CO093-002----	Redundant record	1,530m	Listed as a 'mound' in the SMR (1988) and as a 'non-antiquity' in the RMP (1998). As a non-antiquity it does not constitute an archaeological monument.
CO093-031----	Redundant record	1,820m	In bogland, on W-facing slope. Large slab of sandstone.
CO092-015----	Ringfort - rath	1,630m	In pasture, on W-facing slope. Circular area (19m N-S; 18.3m E-W) enclosed by grass-covered earth and stone bank (H 1m), topped by stone wall. At E side, wall built along inner face of bank forms straight line, but bank maintains curve externally. Interior partially planted with conifers; remains of cultivation ridges in W half.
CO093-028----	Ringfort - rath	1,180m	In rough grazing, on gentle W-facing slope. Roughly circular area (19.5m N-S; 18.4m E-W); enclosed by bank (H 0.7m); external fosse (D 0.2m). Bank mainly composed of stones, with earthen base. Entrance to SE (Wth 0.8m), flanked by two large upright stones; blocked by field boundary running NE-SW which truncates outer bank face to SE
CO093-057----	Ringfort - rath	1,955m	On high ground with excellent views of the Cousane Gap to W, Shehy Mountains to N and Bandon River valley to SE. Oval raised area (37m N-S; 31m E-W) enclosed by scarp (H 1.3m) E->WSW; earthen bank (H 0.3m) WSW->E; second earthen bank WNW->NE (H 0.9m) separated from inner bank by intervening fosse. Cultivation ridges cross interior on N-S axis.
CO093-059----	Ringfort - rath	1,905	In pasture, on steep N-facing slope. Circular area (41m N-S; 40m E-W) enclosed by earthen bank (int. H 0.8m); external fosse (D 0.4m). Break in bank to N (Wth 7m), with possible causeway. Interior raised on N side to compensate for hillslope.
CO092-070----	Rock scribing	1,770m	In rough rocky grazing, on the N side of the road in the floor of the valley to the E of the Cousane Gap. A large lichen-covered area of bedrock with a rough grey surface sloping down to the SW on which a number of lighter-coloured, mainly linear pocked lines are visible. The lines are variously crossing or joining-up and form a rough parallelogram (c. 0.9m x 0.6m) towards the NE end of the area (c. 3.4m NE-SW x 3m N-S). The lighter-coloured lines display only occasional patches of grey.
CO092-083----	Souterrain	1,500m	No entry
CO092-037----	Standing stone	1,550m	On top of a high ridge commanding extensive views to N and S. Rectangular stone (H 1.5m; 1.15m x 0.25m) aligned NE-SW.
CO092-077----	Standing stone	600m	In rough grazing, on the S side of a ridge with views W along a valley. This standing stone (0.45m x 0.2m; H 1.22m) is rectangular in plan and section and is orientated E-W. A scatter of loose stones
CO093-026----	Standing stone	630m	In pasture on S-facing slope. Rectangular prostrate stone (L 1.2m; 0.76m x 0.6m).
CO093-027001-	Standing stone	760m	In pasture on W-facing slope to NW of standing stone (CO093-02702-). Sub-rectangular stone; long axis NW-SE

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
			(H 1.3m; 0.55m x 0.35m). Prostrate stone with two perforations lies on E side (L 2.5m; 0.6m x 0.4m).
CO093-027003-	Standing stone	760m	In pasture incorporated into field fence. Standing stone pair (CO093-02701-) to NW and anomolous stone group (CO093-02702-) to W. Subrectangular stone aligned NE-SW (H 3m; 1.25m x 0.5m).
CO093-032----	Standing stone	1,800m	In marsh on N-facing slope. Two stones shown on O.S. maps; one remains. Irregular stone (H 1.1m; 1.3m x 0.6m) aligned ENE-WSW.
CO093-055----	Standing stone	1,070m	In pasture on N-facing slope. Rectangular stone aligned E-W (H 1.9m; 0.4m x 0.14m).
CO092-014----	Wedge tomb	1,160m	In sheltered position c. 39m N of a low rocky ridge at head of Sruhaunphadeen valley to NE of Douce Mountain. Comprises gallery (L 3.1m; Wth 1.2m at W end, 0.95m at E) aligned ENE-WSW. Gallery sides each of two stones, those to W being shorter and set inside line of other two; inset backstone at E end. Gallery decreases in height from W to E; surrounded by closely-set outer walling and covered by two roofstones. No indications of surrounding mound. (de Valera and Ó Nualláin 1982, 23-4, Co. 33)
CO093-001----	Wedge tomb	900m	On NW-facing slope beside isolated outcrop of rock, at head of Sruhaunphadeen valley to NE of Douce Mountain. Comprises small gallery (L 2m; Wth 1.25m at W end, 0.75m at E) open to SW, covered by single roofstone, represented by three sidestones to N, two to S and inset backstone at E end. No indications of surrounding mound. (de Valera and Ó Nualláin 1982, 29, Co. 41)
CO093-003----	Wedge tomb	1,400m	On shoulder of N-facing slope, close to outcropping rock, at head of Sruhaunphadeen valley to NE of Douce Mountain. Comprises ruined E end of gallery (L 2.9m; Wth c. 1.3m) aligned E-W; represented by two sidestones to S, one fallen sidestone to N and inset backstone at E end. Outer-wallstones are present to N and S of gallery. Displaced roofstone lies above Eend. Traces of mound around N side of structure. Wedge-tomb (6397) stands c. 300m to E in Cornery townland. (de Valera and Ó Nualláin 1982, 26, Co. 36)
CO093-006----	Wedge tomb	1,465m	On small bog-covered platform on steep S-facing slope at head of Sruhaunphadeen valley, to NE of Douce Mountain. Comprises gallery (L 3.4m; Wth 1.1m at SW end) open to SW, represented by two sidestones to N, three to S and inset backstone at E end; two outer-wall stones stand beyond N side. Traces of mound to S and W of gallery. Wedge-tomb (6393) stands c. 300m to W in Cloghboola townland. (de Valera and Ó Nualláin 1982, 26-7, Co. 37)
CO093-007----	Wedge tomb	1,960m	On small platform on steep N-facing slope of Sruhaunphadeen valley to NE of Douce Mountain. Comprises ruined gallery (L c. 3.5m; Wth 0.5m at E end), aligned ENE-WSW, irregularly constructed of small stones and surrounded by closely-set outer walling. Two fallen stones at W end may be remains of facade. Incorporated in mound on edge of which lie two slabs, possibly displaced roofstones. (de Valera and Ó Nualláin 1982, 24-5, Co. 34)
CO093-076----	Wedge tomb	850m	In rough grazing, close to the foot of a W-facing slope in a clearing within a coniferous plantation at the head of Sruhaunphadeen valley on the NE side of Douce Mountain. The wedge-shaped gallery (L 1.95m; Wth 1.12m at W, narrowing to 0.65m at E), aligned WNW-ESE, is closed by a double backstone (H 0.45m) at E. Both the N and S sides are each formed by two uprights with the larger of the two set at the W end; the W end of the S side is broken and appears to represent a detached third stone. Three close-set outer-wall stones flank the N side of the gallery and a

MONUMENT NO.	TYPE	APPROX. DISTANCE FROM SITE	INVENTORY DESCRIPTION
			single outer-wall stone stands outside the E end of the S side. The E end of the gallery is covered by a roofstone (1.5m x 1m: T 0.15m), sloping to the E. Several portions of a broken slab lie prostrate among the ferns immediately to the W of the entrance and may represent the remnants of the roofstone from the W half of the gallery. Another wedge-tomb (CO093-001----) is c. 150m to the NNE.