
Appendix 10.1
Photographic Record

RECEIVED: 13/08/2024

THIS PAGE IS INTENTIONALLY BLANK

RECEIVED: 13/08/2024

RECEIVED: 13/08/2024



Plate 10.1: View of Field 1 looking northwest



Plate 10.2: View of Field 2 looking northeast



Plate 10.3: View of Field 3 looking west



Plate 10.4: View of townland boundary between Halverstown and Jigginstown, Field 3 looking northwest



Plate 10.5: View of Field 4 looking south with modern drainage ditch in foreground



Plate 10.6: View of Field 5 looking southwest



Plate 10.7: View of Field 6 looking northeast towards farm buildings



Plate 10.8: View of townland boundary between Halverstown and Newhall in Field 6, looking southeast



Plate 10.9: View of townland boundary between Jigginstown and Halverstown, Field 6, looking east



Plate 10.10: View of Field 7 looking northeast



Plate 10.11: View of Field 8 looking southeast



Plate 10.12: View of townland boundary between Jigginstown and Halverstown, Field 8, looking west



Plate 10.13: View of Field 9 looking west



Plate 10.14: View of Field 10 looking southwest towards recorded location of fulacht fia KD019-028---



Plate 10.15: View of recorded location of fulacht fia KD019-028---- (marked by ranging rod), looking west



Plate 10.16: View of Field 11 towards southwest



Plate 10.17: View of group of vernacular buildings
at centre of proposed development area, looking south



Plate 10.18: View of collapsed mud walled cottage within group of vernacular buildings
at centre of proposed development area, looking west



Plate 10.19: *View of brick and stone dwelling house within group of vernacular buildings at centre of proposed development area, looking west*

Appendix 10.2
Cultural Heritage Inventories

RECEIVED: 13/08/2024

THIS PAGE IS INTENTIONALLY BLANK

RECEIVED: 13/08/2024

RECEIVED: 13/08/2024

KD019-016---- (also **RPS NS019-092**)

Class: Mound

Townland: Osberstown

Scheduled for inclusion in the next revision of the RMP: Yes

Description: Named 'Moat' and shown as a raised and possibly steep-sided, circular earthwork or mound on a manuscript map (NLI Ms. 21 F 35 (1727-1838)). Extensive gravel extraction has taken place at this location over the years, recorded on both eds. of the OS 6-inch map (1838 and 1938-39) and on the intervening OS 25-inch map, which shows gravel pits and a 'Kildare Golf Course' pavilion in this area. No obvious visible trace of an earthwork survives.

KD019-017---- (also **RPS NS019-093**)

Class: Burial

Townland: Ploopluck

Scheduled for inclusion in the next revision of the RMP: Yes

Description: A cemetery of pit burials was discovered in an esker during gravel extraction in 1935. The recorded burials comprised: (1) an inhumation accompanied by a bowl food vessel; (2) an inhumation accompanied by a bowl food vessel; (3) a crouched inhumation accompanied by a bowl food vessel; (4) an unaccompanied inhumation. A fifth burial containing the inhumations of four individuals accompanied by a bowl food vessel and an urn sherd from this site may not be directly associated with the cemetery (Raftery 1951, 150).

KD019-028----

Class: Fulacht fia

Townland: Jigginstown

Scheduled for inclusion in the next revision of the RMP: Yes

Description: Some 30m N of a small, NW-flowing stream in well-drained, level pasture. Described in 1985 as horseshoe-shaped mound (diam. c. 6m N-S; H. 1m) open towards the S (SMR file). No obvious surface trace survived in 2000, but the area, although recently drained with a plastic field-pipe (Wth 0.5m; D 0.3m) just N of the site was still wet and rushy to the SE of the site. Sub-surface features may survive intact.

KD019-029---- (also **RPS NS019-080**)

Class: Church

Townland: Jigginstown

Scheduled for inclusion in the next revision of the RMP: Yes

Description: Named 'Templecarragh' on Noble and Keenan's 1752 Map of County Kildare, and 'Temple Carragh' (in ruins) on Taylor's 1782 map of the county. At the N end of a short, low, N-S pasture ridge. A very poorly preserved, rectangular structure (int. dims. L 8.3m E-W; Wth 4.1m) is built of randomly coursed limestone blocks and flags. The thick walls (av. T 1m) are almost levelled (max. H 1.6m) and a rubble-filled gap (Wth 1.4m) to W of centre in the N wall may be the site of the original doorway. Windows do not survive, but gaps in the E gable wall (Wth 1.5m) and near the W end of the S wall (Wth 1.6m) mark their locations. A single, chamfered quoin is visible on the external SE angle. A grass covered, raised, rectangular area, running E from the E gable (L 7.4m E-W), defined by a scarp (H 0.8m) may be the remains of an associated structure, although it appears unlikely to have been a chancel. Fitzgerald (1905, 355) noted the occurrence of human bones at the site, suggesting a possible graveyard (KD019-029001-).

KD019-029001-**Class:** Graveyard**Townland:** Jigginstown**Scheduled for inclusion in the next revision of the RMP:** Yes

Description: Fitzgerald (1905, 355) noted that although there were no, '... signs of graves.... small human bones have been thrown up to the surface by rabbits on the south side of the ruins (a church, KD019-029----), where it is slightly higher than the surrounding field, which goes by the name of the "Church Field" There is no obvious visible trace of a graveyard.

KD019-068----**Class:** Fulacht fia**Townland:** Jigginstown**Scheduled for inclusion in the next revision of the RMP:** No

Description: In 2005, archaeological monitoring (Licence no. 05E0442: www.excavations.ie) of topsoil-stripping associated with the construction of the Millennium Park Western Link Road identified a fulacht fia on the edge of a natural peat basin. It was subsequently excavated (Licence no. 05E0524: www.excavations.ie). A low, probably originally U-shaped mound (dims. L 8m N-S; Wth 6.8m) was composed of burnt sandstone, charcoal and peaty clay. A shallow rectangular trough (dims. L 1.5m; Wth 1.2m; D 0.2m) at the N edge contained a stake hole in each corner, suggesting it once contained a wooden structure. Some 23 stake-holes were found immediately S of the trough, of which 13 formed the outline of an oval structure. Material from the mound yielded a radiocarbon date of 3869 ± 52 BP (2480-2190 cal BC at 2 sigma), while material from the trough returned 3926 ± 71 BP (2620-2190 cal BC at 2 sigma). A second fulacht fia (KD019-028----) lay c. 400m to the W.

NIAH 11901903 / RPS NS019-059**Class:** Bridge**Townland:** Jigginstown

Description: Single-arch rubble stone hump back road bridge over canal, c.1800, with limestone ashlar voussoirs, cut-stone stringcourse and rubble stone parapet walls. Rubble stone walls. Rubble stone piers. Cut-stone stringcourse. Rubble stone parapet walls with render over. Dressed stone coping. Single round arch. Limestone ashlar voussoirs. Limestone ashlar soffits. Sited spanning Grand Canal (Herbertstown Branch) with tow path to east and grass banks to canal.