

15 MATERIAL ASSETS (WASTE)

15.1 Introduction

This chapter of the EIAR evaluates the likely impacts, if any, which the proposed development may have on Material Assets (related to waste management) as defined in the EIA Directive (Directive 2011/92/EU as amended by Directive 2014/52/EU) and the Environmental Protection Agency (EPA) Guidelines on the information to be contained in Environmental Impact Assessment Reports (2022).

A site-specific Resource Waste Management Plan (RWMP) has been prepared by AWN Consulting Ltd (Ref. LB/237501.0599WMR01) to deal with waste generation during the excavation and construction phase of the proposed development and has been included as Appendix 15.1. The RWMP was prepared in accordance with the Environmental Protection Agency's (EPA) document Best Practice Guidelines for the Preparation of Resource and Waste Management Plans for Construction & Demolition Projects (2021).

A separate Operational Waste Management Plan (OWMP) has also been prepared by AWN Consulting Ltd (Ref. LB/237501.0599WMR02) for the operational phase of the proposed development and is included in Appendix 15.2 of this chapter.

The Chapter has been prepared in accordance with European Commissions Guidelines, Guidance on the preparation of the Environmental Impact Assessment Report (2017), the EPA Guidelines on the Information to be contained in EIAR (2022).

These documents will ensure the management of wastes arising at the development site in accordance with legislative requirements and best practice standards.

15.2 Assessment Methodology

The assessment of the impacts of the proposed development, arising from the consumption of resources and the generation of waste materials, was carried out taking into account the methodology specified in relevant guidance documents, along with an extensive document review to assist in identifying current and future requirements for waste management, including national and regional waste policy, waste strategies, management plans, legislative requirements and relevant reports.

This Chapter is based on the proposed development, as described in Chapter 3 of this EIAR (Description of Project) and considers the following aspects:

- Legislative context;
- Construction phase (including site preparation and excavation works);
- Operational phase; and
- Reinstatement Phase

A desktop study was carried out which included the following:

- Review of applicable policy and legislation which creates the legal framework for resource and waste management in Ireland;
- Description of the typical waste materials that will be generated during the Construction and Operational phases; and
- Identification of mitigation measures to prevent waste generation and promote management of waste in accordance with the waste hierarchy.

Estimates of waste generation during the construction and operational phases of the proposed development have been calculated and are included in Section 15.4 of this Chapter. The waste types and estimated quantities are based on published data by the EPA in the National Waste Reports and the National Waste Statistics.

Mitigation measures are proposed to minimise the effect of the proposed development on the environment during the construction and operational phases, to promote efficient waste segregation and to reduce the quantity of waste requiring disposal. This information is presented in Section 15.6

A detailed review of the existing ground conditions on a regional, local and site-specific scale are presented in Chapter 7 of this EIAR (Land, Soils and Geology).

15.2.1 Legislation and Guidance

Waste management in Ireland is subject to EU, national and regional waste legislation and control which defines how waste materials must be managed, transported and treated. The overarching EU legislation is the Waste Framework Directive (2008/98/EC) as amended which is transposed into national legislation in Ireland. The cornerstone of Irish waste legislation is the Waste Management Act 1996 (as amended). European and national waste management policy is based on the concept of 'waste hierarchy', which sets out an order of preference for managing waste (prevention > preparing for reuse > recycling > recovery > disposal) (Figure 15.1).



Figure 15.1: Waste Hierarchy (Source: European Commission)

EU and Irish National waste policy also aims to contribute to the circular economy by extracting high-quality resources from waste as much as possible. Circular Economy (CE) is a sustainable alternative to the traditional linear (take-make-dispose) economic model, reducing waste to a minimum by reusing, repairing, refurbishing and recycling existing materials and products. (Figure 15.2).




Figure 15.2: Circular Economy (Source: Repak)

The Irish government issues policy documents which outline measures to improve waste management practices in Ireland and help the country to achieve EU targets in respect of recycling and disposal of waste. The most recent policy document, Waste Action Plan for a Circular Economy (WAPCE) – *Waste Management Policy in Ireland*, was published in 2020 and shifts focus away from waste disposal and moves it back up the production chain. The move away from targeting national waste targets is due to the Irish and international waste context changing in the years since the launch of the previous waste management plan, *A Resource Opportunity*, in 2012.

One of the first actions to be taken from the WAPCE was the development of the Whole of Government Circular Economy Strategy 2022-2023 'Living More, using Less' (2021) to set a course for Ireland to transition across all sectors and at all levels of Government toward circularity and was issued in December 2021.

The Circular Economy and Miscellaneous Provisions Act 2022 was signed into law in July 2022. The Act underpins Ireland's shift from a "take-make-waste" linear model to a more sustainable pattern of production and consumption, that retains the value of resources in our economy for as long as possible and that will to significantly reduce our greenhouse gas emissions. The Act defines Circular Economy for the first time in Irish law, incentivises the use of recycled and reusable alternatives to wasteful, single-use disposable packaging, introduces a mandatory segregation and incentivised charging regime for commercial waste, streamlines the national processes for End-of-Waste and By-Products decisions.

The strategy for the management of waste from the construction phase is in line with the requirements of the EPA's 'Best Practice Guidelines for the Preparation of Resource and Waste Management Plans for Construction & Demolition Projects' (2021). The guidance documents, *Best Practice Guidelines for the Preparation of Waste Management Plans for Construction and Demolition Projects (2006)* and *Construction and Demolition Waste Management: A Handbook for Contractors and Site Managers* (FÁS & Construction Industry Federation, 2002), were also consulted in the preparation of this assessment.

There are currently no Irish guidelines on the assessment of operational waste generation, and guidance is taken from industry guidelines, plans and reports including:

- The National Waste Management Plan for a Circular Economy 2024 – 2030 (NWMPC) (2024),
- BS 5906:2005 Waste Management in Buildings – Code of Practice,

- South Dublin County Council (SDCC) County of South Dublin (Segregation, Storage and Presentation of Household and Commercial Waste) Bye-laws (2018),
- EPA National Waste Database Reports 1998 – 2020, and
- The Circular Economy and National Waste Database Report 2021 (2023) and the EPA National Waste Statistics Web Resource.
-

15.2.2 Terminology

Note that the terminology used herein is consistent with the definitions set out in Article 3 of the Waste Framework Directive. Key terms are defined as follows: -

Waste - Any substance or object which the holder discards or intends or is required to discard.

Prevention - Measures taken before a substance, material or product has become waste, that reduce:

- a) the quantity of waste, including through the re-use of products or the extension of the life span of products;
- b) the adverse impacts of the generated waste on the environment and human health; or
- c) the content of harmful substances in materials and products.

Reuse - Any operation by which products or components that are not waste are used again for the same purpose for which they were conceived.

Preparing for Reuse - Checking, cleaning or repairing recovery operations, by which products or components of products that have become waste are prepared so that they can be re-used without any other pre-processing.

Treatment - Recovery or disposal operations, including preparation prior to recovery or disposal.

Recovery - Any operation the principal result of which is waste serving a useful purpose by replacing other materials which would otherwise have been used to fulfil a particular function, or waste being prepared to fulfil that function, in the plant or in the wider economy. Annex II of the Waste Framework Directive sets out a non-exhaustive list of recovery operations.

Recycling - Any recovery operation by which waste materials are reprocessed into products, materials or substances whether for the original or other purposes. It includes the reprocessing of organic material but does not include energy recovery and the reprocessing into materials that are to be used as fuels or for backfilling operations.

Disposal - Any operation which is not recovery even where the operation has as a secondary consequence the reclamation of substances or energy. Annex I of the Waste Framework Directive sets out a non-exhaustive list of disposal operations.

15.3 Receiving Environment

In terms of waste management, the receiving environment is largely defined by FCC as the local authority responsible for setting and administering waste management activities in the area. This is governed by the requirements set out in the NWMPCE 2024 – 2030 and the Waste Action Plan for a Circular Economy – Waste Management Policy in Ireland.

The waste management plans set out the following targets for waste management in the region:

- Achieve a recycling rate of 55% of managed municipal waste by 2025; and
- Reduce to 0% the direct disposal of unprocessed residual municipal waste to landfill (from 2016 onwards) in favour of higher value pre-treatment processes and indigenous recovery practices.

The Regional Waste Management Planning Offices have issued a National Waste Management Plan for a Circular Economy 2024 - 2030 (NWMPCE) in March 2024, which supersedes the Eastern midlands regional (EMR) waste management plan and the two other regional waste management plans. The

NWMPCE does not however dissolve the three regional waste areas. The NWCPCE sets the ambition of the plan to have a 0% total waste growth per person over the life of the Plan with an emphasis on non-household wastes including waste from commercial activities and the construction and demolition sector.

The *Fingal Development Plan 2023 – 2029* sets out the objectives for the FCC area which reflect those set out in the regional waste management plan and can be found in Appendix 15.1 and 15.2.

In terms of physical waste infrastructure, FCC no longer operates any municipal waste landfill in the area. There are a number of waste permitted and licensed facilities located in the EMR Waste Region for management of waste from the construction industry as well as municipal sources. These include soil recovery facilities, inert C&D waste facilities, municipal waste landfills, material recovery facilities and waste transfer stations.

However, these sites may not be available for use when required or may be limited by the waste contractor selected to service the development in the appropriate phase. In addition, there is potential for more suitably placed waste facilities or recovery facilities to become operational in the future which will be more beneficial from an environmental perspective.

The ultimate selection of waste contractors and waste facilities would be subject to appropriate selection criteria proximity, competency, capacity and serviceability.

A full description of the proposed Development can be found in Chapter 3 (Description of Proposed Development). The characteristics of the proposed development that are relevant in terms of waste management are summarised below.

15.4 Characteristics of the Proposed Development

The proposed development will comprise 296 No. Residential units consisting of 42 No. Duplex / apartments and 254 No. Houses ranging in height between 1.5 and 3 storeys; public open space including southern Monument Park which formed part of the Racecourse Park development permitted under ABP Reg. Ref. JP06F.311315; vehicular access to serve the development is proposed off Monument View; and all associated and ancillary site development, infrastructural, landscaping and boundary treatment works.

The proposed development will also comprise a new (temporary) rising main to serve this phase and previous development phases (1A to 1E inclusive), c.1.7km long, running from the interim St. Marnock's Pumping Station at Station Road/The Avenue (constructed under ABP Reg. Ref. 300514-17 & upgraded under ABP Reg. Ref. 312112-21) connecting to the North Fringe Sewer in the south via Phase 1E (permitted under FCC Reg. Ref. LRD0002/S3), Racecourse Park North and South (permitted under ABP Reg. Ref. JP06F.311315) including crossing under both Moyne Road and Mayne River; upgrade of pumping station and storage as required and all associated and ancillary site development and reinstatement. The proposed rising main and interim St. Marnock's Pumping Station will be decommissioned and these lands will then discharge by gravity to a proposed new Uisce Éireann Pumping Station adjacent to Portmarnock Bridge when same is completed.

The purpose of this section is to provide an overview of the key relevant details of the Construction Phase and Operational Phase of the proposed development. The information presented in this section is informed by the project design, but it is not a complete description of the Proposed Development. Therefore, it should be read in conjunction with the full development package.

For a more comprehensive understanding of the Proposed Development, please refer to Chapter 3: Description of Proposed Development) of the EIAR. That chapter provides a detailed overview of the lifecycle of the project, including reference to the architectural and civil engineering, drawings, plans, reports, and other relevant document in order to define the proposed development.

15.4.1 Demolition Stage

There will be no demolition as part of the proposed development.

15.4.2 Construction Stage

During the construction phase, waste will be produced from surplus materials such as broken or off-cuts of timber, plasterboard, concrete, tiles, bricks, etc. Waste from packaging (cardboard, plastic, timber) and oversupply of materials may also be generated. The appointed Contractor will be contractually required to ensure that oversupply of materials is kept to a minimum and opportunities for reuse of suitable materials is maximised.

There will be topsoil and subsoil excavated to facilitate construction of new foundations and underground services. The project engineers (Egis) have estimated that 40,100 m³ of material will need to be excavated to do so. It is currently envisaged that 6,800 m³ of excavated will be able to be retained and reused on site while the remaining 33,300 m³ of excavated material will be required to be removed off site reuse, recycling or disposal. Correct classification and segregation of the excavated material is required to ensure that any potentially contaminated materials are identified and handled in a way that will not impact negatively on workers or the environment.

If any material that requires removal from the site is deemed to be a waste, removal and reuse / recycling / recovery / disposal of the material will be carried out in accordance with the Waste Management Act 1996 (as amended), the Waste Management (Collection Permit) Regulations 2007 (as amended) and the Waste Management (Facility Permit & Registration) Regulations 2007 (as amended). The volume of waste requiring recovery / disposal will dictate whether a Certificate of Registration (COR), permit or licence is required for the receiving facility. Alternatively, the material may be classed as by-product under Regulation 27 (By-products), as amended, of S.I. No. 323/2020 - European Union (Waste Directive) Regulations 2011-2020, (previously Article 27 of the European Communities (Waste Directive)). For more information in relation to the envisaged management of by-products, refer to the RWMP (Appendix 15.1).

In order to establish the appropriate reuse, recovery and / or disposal route for the soils and stones to be removed off-site, it will first need to be classified. Waste material will initially need to be classified as hazardous or non-hazardous in accordance with the EPA publication Waste Classification – List of Waste & Determining if Waste is Hazardous or Non-Hazardous (2018).

Waste will also be generated from construction phase workers e.g. organic / food waste, dry mixed recyclables (waste paper, newspaper, plastic bottles, packaging, aluminium cans, tins and Tetra Pak cartons), mixed non-recyclables and, potentially, sewage sludge from temporary welfare facilities provided on-site during the Construction phase. Waste printer / toner cartridges, waste electrical and electronic equipment (WEEE) and waste batteries may also be generated in small volumes from site offices.

Further detail on the waste materials likely to be generated during the excavation and construction works are presented in the project-specific RWMP (Appendix 15.1). The RWMP provides an estimate (of the main waste types likely to be generated during the Construction phase of the proposed development. These are summarised in Table 15.1.

Waste Type	Tonnes	Reuse/Recycle		Recovery		Disposal	
		%	Tonnes	%	Tonnes	%	Tonnes
Mixed C&D	679.2	10	67.9	80	543.4	10	67.9
Timber	576.3	40	230.5	55	317.0	5	28.8
Plasterboard	205.8	30	61.7	60	123.5	10	20.6
Metals	164.7	5	8.2	90	148.2	5	8.2
Concrete	123.5	30	37.0	65	80.3	5	6.2
Mixed Waste	308.7	20	61.7	60	185.2	20	61.7
Total	2058.2		467.2		1397.5		193.5

Table 15.1: Estimated off-site reuse, recycle and disposal rates for construction waste

15.4.3 Operational Stage

As noted in Section 15.1, an OWMP has been prepared for the development and is included as Appendix 15.2. The OWMP provides a strategy for segregation (at source), storage and collection of all wastes generated within the building during the operational phase including dry mixed recyclables, organic waste and mixed non-recyclable waste as well as providing a strategy for management of waste glass, batteries, WEEE, printer/toner cartridges, chemicals, textiles, waste cooking oil and furniture.

The total estimated waste generation for the development for the main waste types based on the AWN waste generation model is presented in Table 15.2 below and is based on the uses and areas as advised by the project architects (Burke Kennedy Doyle Architects). Further breakdowns can be found with in Appendix 15.2 OWMP.

Waste Type	m ³ per week
	Residential Waste (Combined)
Organic Waste	5.89
DMR	41.19
Glass	1.14
MNR	22.54
Total	70.77

Table 15.2 Estimated waste generation for the proposed development for the main waste types

The residents will be required to provide and maintain appropriate waste receptacles within their units to facilitate segregation at source of these waste types. As required, the residents will need to bring these segregated wastes from their units to their allocated Waste Storage Area (WSA). All WSA's can be viewed on the plans submitted with the application and in the OWMP (Appendix 15.2).

The OWMP seeks to ensure the development contributes to the targets outlined in the NWMPCE and the FCC waste Bye-laws.

15.5 Potential Impact of the Proposed Development

15.5.1 Construction Stage

The Proposed Development will generate a range of non-hazardous and hazardous waste materials during site excavation and construction (see Appendix 15.1 for further detail). General housekeeping and packaging will also generate waste materials, as well as typical municipal wastes generated by construction employees, including food waste. Waste materials will be required to be temporarily stored in the construction site compound or adjacent to it, on-site pending collection by a waste contractor. If waste material is not managed and stored correctly, it is likely to lead to litter or pollution issues at the Development Site and in adjacent areas. The indirect effect of litter issues is the presence of vermin in areas affected. In the absence of mitigation, the effect on the local and regional environment is likely to be **indirect, short-term, significant and negative**.

The use of non-permitted waste contractors or unauthorised waste facilities could give rise to inappropriate management of waste, resulting in indirect negative environmental impacts, including pollution. It is essential that all waste materials are dealt with in accordance with regional and national legislation, as outlined previously, and that time and resources are dedicated to ensuring efficient waste management practices. In the absence of mitigation, the effect on the local and regional environment is likely to be **indirect long-term, significant and negative**.

Wastes arising will need to be taken to suitably registered / permitted / licenced waste facilities for processing and segregation, reuse, recycling, recovery, and / or disposal, as appropriate. There are numerous licensed waste facilities in the EMR which can accept hazardous and non-hazardous waste materials, and acceptance of waste from the Development Site would be in line with daily activities at these facilities. At present, there is sufficient capacity for the acceptance of the likely C&D waste arisings at facilities in the region. The majority of construction materials are either recyclable or recoverable. However, in the absence of mitigation, the effect on the local and regional environment is likely to be **indirect short-term, significant and negative**.

There is a quantity of topsoil and subsoil will need to be excavated to facilitate the proposed Development. A detailed review of the existing ground conditions on a regional, local site-specific scale are presented in Chapter 7. Excavated material that cannot be reused onsite will need to be removed off-site. Correct classification and segregation of the excavated material is required to ensure that any potentially contaminated materials are identified and handled in a way that will not impact negatively on workers as well as on water and soil environments, both on and off-site. However, in the absence of mitigation, the effect on the local and regional environment is likely to be **indirect, short-term, significant and negative**.

15.5.2 Operational Stage

The potential impacts on the environment of improper, or a lack of, waste management during the operational phase would be a diversion from the priorities of the waste hierarchy which would lead to small volumes of waste being sent unnecessarily to landfill. In the absence of mitigation, the effect on the local and regional environment is likely to be **indirect, long-term, significant and negative**.

The nature of the development means the generation of waste materials during the operational phase is unavoidable. Networks of waste collection, treatment, recovery and disposal infrastructure are in place in the region to manage waste efficiently from this type of development. Waste which is not suitable for recycling is typically sent for energy recovery. There are also facilities in the region for segregation of municipal recyclables which is typically exported for conversion in recycled products (e.g. paper mills and glass recycling).

If waste material is not managed and stored correctly, it is likely to lead to litter or pollution issues at the development site and in adjacent areas. The knock-on effect of litter issues is the presence of vermin in affected areas. However, in the absence of mitigation, the effect on the local and regional environment is likely to be **indirect, long-term, significant and negative**.

It is anticipated that Waste contractors will be required to service the proposed development on a scheduled basis to remove waste. The use of non-permitted waste contractors or unauthorised facilities could give rise to inappropriate management of waste and result in negative environmental impacts or pollution. It is essential that all waste materials are dealt with in accordance with regional and national legislation, as outlined previously, and that time and resources are dedicated to ensuring efficient waste management practices. However, in the absence of mitigation, the effect on the local and regional environment is likely to be **indirect, long-term, significant and negative**.

15.5.3 Do-Nothing Impact

If the proposed development was not to go ahead (i.e. in the Do-Nothing scenario) there would be no excavation or construction at this site. There would continue to be no operational waste generated from the proposed site. There would, therefore, be a **neutral effect** on the environment in terms of waste.

The site is zoned for development, and it is likely that in the absence of this subject proposal that a development of a similar nature would be progressed on the site that accords with national and regional policies, which can be found in Appendix 15.1 and Appendix 15.2, and therefore the likely significant effects would be similar to this proposal.

15.5.4 Cumulative**15.5.5 Construction Stage**

There are existing residential and commercial developments close by, along with the multiple permissions remaining in place in the area. Multiple developments in the area could potentially be developed concurrently or overlap in the construction phase.

For the purposes of this EIAR, the following is understood to be the Cumulative Development:

- Portmarnock South Phase 1D
172no. residential units, provision of Skylark Park, provision of new road connection to Moyne Road and upgrade of existing temporary foul water pumping station and 24 wastewater storage tank (under construction)
- Portmarnock South Phase 1E (Ref. LRD0002/S3)
195 no. residential units, provision of public open space and provision of road and drainage infrastructure. (construction commenced in December 2024)
- New Portmarnock Pumping Station (FCC Reg. Ref. F21A/0389 – ABP Ref. ABP-314663-22)
Permission was sought by Irish Water on 19 July 2021 for a Wastewater Pumping Station and this has been approved by An Bord Pleanála by Order dated 27 June 2024. The proposal generally comprised of modification of Portmarnock Bridge pumping station including decommissioning of redundant above and below ground plant and equipment, including the demolition of the control building.
- Racecourse Park (ABP Ref. JP06F.311315)
Fingal County Council have sought and obtained consent for a regional park on lands immediately south of Portmarnock South.

FCC applied to An Bord Pleanála under Section 177AE of the Planning and Development Act 2000, as amended, to carry out a park development project at the Racecourse Park located between Baldoyle and Portmarnock, Co. Dublin. Broadly, the proposal includes: -

- 4.5km of new walking and cycling routes including a bridge over the Mayne river and the repair to the railway underpass.
- Public lighting along key walking and cycling routes.
- Expanding the existing car park to cater for up to 161no. car parking spaces. Upgrading and expanding the existing playground.
- A Skate park and Teenage Adventure Playground.
- A Multi use games area.
- A dog run.
- A Bowls green.
- Four grass football pitches.
- A viewing platform.
- Tracing of circular archaeological feature through soft landscaping and removal of existing fence.
- Extension of existing reedbed south of Mayne river and creation of new brackish grassland north of Mayne river.
- All landscaping works in the park. This new substantial park amenity will be within c. 1 – 5 km of the proposed development (and wider Portmarnock lands) once completed.

Permission was granted by An Bord Pleanála on 20 September 2022.

- DART+ Coastal North Railway Order 2024 (ABP-320164-24)

Córas Iompair Éireann (CIE) applied to An Bord Pleanála under Section 37(1) of the Transport (Railway Infrastructure) Act 2001 (as amended and substituted) for the DART+ Coastal North Railway Order. The DART+ Coastal North (Northern Line) involving railway improvement works from Connolly Station to Drogheda Station, inclusive of the Howth branch line from Howth Junction Station to Howth Station from East Wall Junction (to the north of Connolly Station) through to Drogheda.

Case is due to be decided by 3 October 2025.

- Greater Dublin Drainage Strategic Infrastructure Development (SID) (ABP-312131-21)

Irish Water applied to An Bord Pleanála under Section 37E of the Planning and Development Act 2000, as amended for the development of a new wastewater treatment plant, sludge hub centre, orbital sewer, outfall pipeline and regional biosolids storage facility and is referred to as the Greater Dublin Drainage project.

Part of the route passes through the open space / bird quiet zone south of Phase 1D, 1E and 1F.

Case is ongoing.

Other developments in the area will be required to manage waste in compliance with national and local legislation, policies and plans which will mitigate against any potential cumulative effects associated with waste generation and waste management. As such the effect will be **short-term, not significant** and **neutral**.

15.5.6 Operational Stage

There are existing residential and commercial developments close by, along with the multiple permissions remaining in the area. All of the current and potential developments will generate similar waste types during their operational phases. Authorised waste contractors will be required to collect waste materials segregated, at a minimum, into recyclables, organic waste and non-recyclables. An increased density of development in the area is likely improve the efficiencies of waste collections in the area.

Other developments in the area will be required to manage waste in compliance with national and local legislation, policies and plans which will minimise/mitigate any potential cumulative impacts associated with waste generation and waste management. As such the effect will be a **long-term, imperceptible and neutral**.

15.5.7 Do-Nothing Impact

The potential Do-Nothing Impacts are the same as 16.5.3

15.6 Mitigation Measures (Ameliorative, Remedial or Reductive Measures)

This section outlines the measures that will be employed in order to reduce the amount of waste produced, manage the wastes generated responsibly and handle the waste in such a manner as to minimise the effects on the environment.

The concepts of the 'waste hierarchy' and 'circular economy' are employed when considering all mitigation measures.

The waste hierarchy states that the preferred option for waste management is prevention and minimisation of waste, followed by preparing for reuse and recycling / recovery, energy recovery (i.e. incineration) and, least favoured of all, disposal. A circular economy is a model of resource production and consumption in any economy that involves sharing, leasing, reusing, repairing, refurbishing, and recycling existing materials and products for as long as possible.

15.6.1 Construction Stage

The following mitigation measures will be implemented during the construction phase of the proposed development: -

Waste Management (WM)_1:

As previously stated, a project specific RWMP has been prepared in line with the requirements of the requirements of the EPA 'Best Practice Guidelines for the Preparation of Resource and Waste Management Plans for Construction & Demolition Projects' (2021) and is included as Appendix 15.1. The mitigation measures outlined in the RWMP will be implemented in full and form part of the mitigation strategy for the site. The mitigation measures presented in this RWMP will ensure effective waste management and minimisation, reuse, recycling, recovery and disposal of waste material generated during the excavation and construction stages of the proposed development.

- Prior to commencement, the appointed Contractor(s) will be required to refine / update the RWMP (Appendix 15.1) in agreement with SDCC and in compliance with any planning conditions, or submit an addendum to the RWMP to SDCC, detailing specific measures to minimise waste generation and resource consumption, and provide details of the proposed waste contractors and destinations of each waste stream.
- The Contractor will implement the RWMP throughout the duration of the proposed excavation and construction stages.

WM_2:

- A quantity of topsoil and sub soil will need to be excavated to facilitate the proposed development. The Development Engineers have estimated that the majority excavated material will need to be removed off-site. Correct classification and segregation of the excavated material is required to ensure that any potentially contaminated materials are identified and handled in a way that will not impact negatively on workers as well as on water and soil environments, both on and off-site.

WM_3:

- Building materials will be chosen to 'design out waste'.

WM_4:

- On-site segregation of waste materials will be carried out to increase opportunities for off-site reuse, recycling and recovery. The following waste types, at a minimum, will be segregated:
 - Concrete rubble (including ceramics, tiles and bricks);
 - Soil and stones;
 - Concrete, bricks, tiles and ceramics;
 - Wood, glass and plastics;
 - Metals;
 - Gypsum-based construction material;
 - Paper and cardboard;
 - Mixed construction and demolition (C&D) waste;
 - Chemicals (solvents, paints, adhesives, detergents etc.).

WM_5:

- Left over materials (e.g. timber off-cuts, broken concrete blocks / bricks) and any suitable construction materials shall be re-used on-site, where possible (alternatively, the waste will be sorted for recycling, recovery or disposal).

WM_6:

- All waste materials will be stored in skips or other suitable receptacles in designated areas of the site.

WM_7:

- Any hazardous wastes generated (such as chemicals, solvents, glues, fuels, oils) will also be segregated and will be stored in appropriate receptacles (in suitably banded areas, where required).

WM_8:

- A Resource Manager will be appointed by the main Contractor(s) to ensure effective management of waste during the excavation and construction works.

WM_9:

- All construction staff will be provided with training regarding the waste management procedures.

WM_10:

- All waste leaving site will be reused, recycled or recovered, where possible, to avoid material designated for disposal.

WM_11:

- All waste leaving the site will be transported by suitably permitted contractors and taken to suitably registered, permitted or licenced facilities.

WM_12:

- All waste leaving the site will be recorded and copies of relevant documentation maintained.

WM_13:

- Nearby sites requiring clean fill material will be contacted to investigate reuse opportunities for clean and inert material, if required. If any of the material is to be reused on another site as by-product (and not as a waste), this will be done in accordance with Regulation 27 (By-products), as amended, European Union (Waste Directive) Regulations 2011-2020. EPA approval will be obtained prior to moving material as a by-product.

These mitigation measures will ensure that the waste arising from the construction stage of the proposed development is dealt with in compliance with the provisions of the Waste Management Act 1996, as amended, associated Regulations and the Litter Pollution Act 1997 and the NWCPE. It will also ensure optimum levels of waste reduction, reuse, recycling and recovery are achieved and will promote more sustainable consumption of resources.

15.6.2 Operational Stage

The following mitigation measures will be implemented during the operational phase of the proposed development: -

WM_14:

- All waste materials will be segregated into appropriate categories and will be temporarily stored in appropriate bins or other suitable receptacles in a designated, easily accessible areas of the site.

WM_15:

- As previously stated, a project specific OWMP has been prepared and is included as Appendix 14.2. The mitigation measures outlined in the OWMP will be implemented in full and form part of the mitigation strategy for the site. Implementation of this OWMP will ensure a high level of recycling, reuse and recovery at the development. All recyclable materials will be segregated at source to reduce waste contractor costs and ensure maximum diversion of materials from

landfill, thus achieving the targets set out in the NWMPCE , Waste Action Plan for a Circular Economy – Waste Management Policy in Ireland and the SDCC waste bye-laws.

- The Residents of the site during the operational stage will be responsible for ensuring the ongoing implementation of this OWMP and the abiding of SDCC waste bye-laws, ensuring a high level of recycling, reuse and recovery at the site of the proposed development.

WM_16:

- On-site segregation of all waste materials into appropriate categories including (but not limited to):
 - Organic waste;
 - Dry Mixed Recyclables;
 - Mixed Non-Recyclable Waste;
 - Glass;
 - Waste electrical and electronic equipment (WEEE);
 - Batteries (non-hazardous and hazardous);
 - Cooking oil;
 - Light bulbs;
 - Cleaning chemicals (pesticides, paints, adhesives, resins, detergents, etc.);
 - Furniture (and from time to time other bulky waste); and
 - Abandoned bicycles.

WM_17:

- The Residents will ensure that all waste materials will be stored in colour coded bins or other suitable receptacles in designated, easily accessible locations. Bins will be clearly identified with the approved waste type to ensure there is no cross contamination of waste materials.

WM_18:

- The Residents will ensure that all waste collected from the site of the proposed development will be reused, recycled or recovered, where possible, with the exception of those waste streams where appropriate facilities are currently not available; and

WM_19:

- The Residents will ensure that all waste leaving the site will be transported by suitable permitted contractors and taken to suitably registered, permitted or licensed facilities.

These mitigation measures will ensure the waste arising from the development is dealt with in compliance with the provisions of the *Waste Management Act 1996*, as amended, associated Regulations, the *Litter Pollution Act 1997*, *The NWMPCE* and the FCC waste bye-laws. It will also ensure optimum levels of waste reduction, reuse, recycling and recovery are achieved.

15.7 Residual Impact of the Proposed Development

The implementation of the mitigation measures outlined in Section 15.6 will ensure that targeted rates of reuse, recovery and recycling are achieved at the site of the Proposed Development during the construction and operational phases. It will also ensure that European, National and Regional legislative waste requirements with regard to waste are met and that associated targets for the management of waste are achieved.

15.7.1 Construction Stage

A carefully planned approach to waste management as set out in Section 15.6.1 and adherence to the RWMP (which includes mitigation) (Appendix 15.1) during the construction phase will promote resource efficiency and waste minimisation. When the mitigation measures are implemented and a high rate of prevention reuse, recycling and recovery is achieved, the predicted impact of the construction phase on the environment will be **short-term, imperceptible and neutral**.

15.7.2 Operational Stage

During the operational phase, a structured approach to waste management as set out in Section 15.6.2 and adherence to the OWMP (which includes mitigation) (Appendix 15.2) will promote resource efficiency and waste minimisation. When the mitigation measures are implemented and a high rate of reuse, recycling and recovery is achieved, the predicted impact of the operational phase on the environment will be **long-term, imperceptible and neutral**.

15.7.3 Worst Case Impact

In a worst-case scenario, if no mitigation measures found in Section 15.6 or in Appendixes 15.1 and 15.2 are followed, lack of waste prevention, poor onsite waste management, non-permitted waste contractors or unauthorised waste facilities could give rise to inappropriate management of waste offsite and result in negative environmental impacts or pollution as shown in Section 15.5.

15.8 Monitoring

The management of waste during the construction phase will be monitored by the Contactor's appointed Resource Manager to ensure compliance with the above-listed mitigation measures, and relevant waste management legislation and local authority requirements, including maintenance of waste documentation. Monitoring proposals for the construction phase are summarised in Table 15.4.

The management of waste during the operational phase will be monitored by the Operator / Facilities Management to ensure effective implementation of the OWMP internally and by the nominated waste contractor(s). Monitoring proposals for the operational phase are summarised in Table 15.5.

Likely Significant Effect	Monitoring Proposals
Litter Pollution	The Contractor will review and maintain waste records and site audits
Unlicensed Waste Collection (Illegal Dumping)	A register will be maintained and reviewed. A copy of all waste collection permits will be maintained.
Insufficient Waste Facilities	A register will be maintained and reviewed. A copy of all waste collection permits will be maintained.
Lack of waste Classification	An appointed Resource Manager will monitor all on-site waste segregation and classification

Table 15.4: Monitoring Proposals for the Construction Stage

Likely Significant Effect	Monitoring Proposals
Unlicensed Waste Collection (Illegal Dumping)	The operator/ facilities management company will maintain waste receipts on-site for a period of 7 years and make available to FCC as requested.
Poor Waste Segregation	Waste generation volumes will be monitored by the operator / facilities management company
Litter Pollution	Waste storage areas will be monitored by the operator / facilities management company

Table 15.5: Monitoring Proposals for the Operational Stage

15.8.1 Construction Stage

The objective of setting targets for waste management is only achieved if the actual waste generation volumes are calculated and compared. This is particularly important during the excavation and construction works, where there is a potential for waste management objectives to become secondary to other objectives, i.e. progress and meeting construction schedule targets. The mitigation measures in the RWMP specify the need for a Resource Manager to be appointed, who will have responsibility for monitoring the actual waste volumes being generated and ensuring that contractors and sub-contractors are segregating waste as required. Where targets are not being met, the Resource Manager will identify the reasons for this and work to resolve any issues. Recording of waste generation during the construction phase of the proposed development will enable better management of waste contractor requirements and identify trends. The data should be maintained to advise on future developments.

15.8.2 Operational Stage

During the operational phase, waste generation volumes will be monitored by residents against the predicted waste volumes outlined in the OWMP. There may be opportunities to reduce the number of bins and equipment required, where estimates have been too conservative. Reductions in bin and equipment requirements will improve efficiency and reduce waste contractor costs.

15.9 Reinstatement

In the event that the Proposed Development is discontinued, there is not likely to be any significant impacts on waste management at the site.

The Proposed Development may be decommissioned at some stage in the future. At that time, a demolition or refurbishment plan will be formulated for the decommissioning phase of the Proposed Development to ensure no waste nuisance occurs at nearby sensitive receptors.

15.10 Difficulties Encountered

Until final materials and detailed construction methodologies have been confirmed, it is difficult to predict with a high level of accuracy the construction waste that will be generated from the proposed works as the exact materials and quantities may be subject to some degree of change and variation during the construction process.

While it is possible to initially select a licensed waste facility for soil disposal, there is potential to encounter contaminated material or material with naturally occurring variations in minerals and chemicals that necessitates sending it to a different suitably licensed facility. The sampling and testing carried out in the Site Investigation (SI) process provides spot samples, and further testing may be required during the excavation process, as the true condition of all excavated materials cannot be ascertained with certainty until this is undertaken.

There is a number of licensed, permitted and registered waste facilities in the Fingal County region, in the surrounding counties, the eastern midlands waste region and in Ireland and Northern Ireland. However, these sites may not be available for use when required or may be limited by the waste contractor selected to service the development in the appropriate phase. In addition, there is potential for more suitably placed waste facilities or recovery facilities to become operational in the future which will be more beneficial from an environmental perspective.

Licensed waste facilities have annual limitations on material that they can important as part of their license agreements. Because of this it would not make it possible to commit to a singular specific receiving facility as it is not available throughout the excavation phase. It would not be viable to cease a development and wait until a receiving facilities annual receiving quotas are reset. In a normal development waste facilities would switch between facilities with available capacity.

The ultimate selection of waste contractors and waste facilities would be subject to appropriate selection criteria proximity, competency, capacity, serviceability, and cost.