

APPENDIX 14.2: ARCHAEOLOGICAL SURVEY OF IRELAND INVENTORY DESCRIPTIONS

Monument No.	Classification	Townland	ASI Inventory Description
CO106-090----	Road - road/trackway	BARNAGOWLANE EAST	No description
CO106-091----	Hut site	BARNAGOWLANE EAST	In rough hill grazing, on a NW-facing slope. The remains of a D-shaped hut site (4.4m E-W) defined by the jumbled lower courses of a curving drystone wall (T 0.6m; H 0.7m) with a straight E side (L 4.1m). Rubble is scattered in the interior. An enclosure (CO106-091001-) adjoins the hut site at the N and another hut site (CO106-091002-) is c. 40m to the SSW.
CO106-092----	Standing stone	BARNAGOWLANE EAST	In pasture, on a NW-facing slope with a view across the Mealagh River valley to the Maughnaclea Hills. This standing stone (1.8m x 0.7m; H 1.3m) tapers from a wide base to a narrow flat top and is orientated NE-SW. (Myler 1998. 81-2).
CO106-093----	Fulacht fia	BARNAGOWLANE WEST	In reclaimed pasture, on a N-facing slope. According to Myler (1998, 82), a half circle of burnt stones was said to have been exposed on a grassy knob on the W bank of a stream. The field has been reclaimed and there are no visible remains of this possible fulacht fia.
CO106-034----	Megalithic tomb - wedge tomb	BARNAGOWLANE WEST	On low rise in valley bottom about 100m S of Mealagh river. Wedge-shaped gallery (L 2.8m; Wth 1.2m at W end, 0.8m at E) open to SW, represented by two orthostats and fallen sidestone to N, backstone to E; covered by a single roofstone. Three outer-wall stones visible at E end gallery. Remains of mound survive to N and W of monument.
CO106-036----	Standing stone	COOMLEAGH EAST	In rough grazing overlooking Mealagh River to S. Rectangular stone (H 1.5m; 1m x 0.3m) aligned NE-SW. Myler (1998, 72) records this stone as being 'located to the north of the road on the higher ground opposite the previous stone (CO106-037----). It is in pasture on a south facing slope with a stone ditch to its eastern side'.
CO106-037----	Standing stone	COOMLEAGH EAST	In rough grazing overlooking Mealagh River to S. Irregular stone (1.8m H; 1.2m x 1.7m). Myler (1998, 71) records the location of the large stone 'just over the ditch on the south side of the road'.
CO106-038----	Standing stone	COOMLEAGH EAST	In pasture on S slopes of Maughanaclea Hills. Irregular stone aligned ENE-WSW (H 1.7m; 1.3m x 0.5m). Myler (1998, 73) notes that it is pentagonal shaped and that 'the stone has markings on its edge.'
CO106-039----	Stone row	COOMLEAGH EAST	On platform of rough pasture on N side of valley of Melagh river. Row of three stones, aligned NE-SW, and 2.6m in overall length, NE stone is 0.4m L, 0.35m T and 0.4m H; its top appears to be broken. Next stone, 1.3m to the SW, is 0.8m L, 0.25m T, and 1.5m H. SW stone lies prostrate 1m from last; it is 4.25m by 0.9m and at least 0.15m thick.
CO106-054----	Enclosure	LEITRY UPPER	In reclaimed pasture atop low knoll. Circular area (21.5m N-S; 22.4m E-W) enclosed by ruinous stone bank (H 0.85m). Four contiguous slabs line bank internally at E; modern stone walling atop bank SW->NW. Interior flat though covered with field clearance stones. Known locally as "lios".

Monument No.	Classification	Townland	ASI Inventory Description
CO106-058----	Standing stone	GARRANES NORTH	In level pasture; rectangular stone (H 0.9m; 0.5m x 0.8m).
CO106-059----	Standing stone	LEITRY UPPER	In pasture, on N side of gravel ridge. Rectangular, flat-topped stone aligned NE-SW (H 0.9m; 0.5m x 0.8m).
CO106-060----	Standing stone	LEITRY UPPER	In recently reclaimed land on S-facing slope; upright stone (H c. 1.1m; Wth 1m).
CO106-066----	Enclosure	DERREENACRINNIG EAST	In rough grazing on peaty soil on the floor of a valley with views SW to Castledonovan. A circular area (diam. 19m) is defined by the remains of a stone wall (T 1.1m; H 0.6m) consisting of an inner and an outer row of contiguous stone slabs with an infill of smaller stones and earth. The wall is best preserved SE-W and elsewhere it is in a more jumbled state, especially along the NE arc where it has been badly damaged. The entrance (Wth 1.6m), at S, is defined by two parallel slabs (H 1.2m and 0.85m, respectively). The interior is slightly uneven. There is a hut site (CO106-066001-) in the N quadrant and another hut site (CO106-066002-) adjoins the enclosing wall externally at SSW.
CO106-065----	Standing stone	DERREENACRINNIG EAST	On a break of a NNW-facing slope, at the foot of a ridge. This standing stone was recorded in March 1996 and described as a thin, rectangular, upright slab (1.2m x 1.32m x 0.6-0.1m) on a NNW-SSE orientation. There is a single cupmark on both sides of the slab: the cupmark on the ENE side measures 0.08-0.09m in diameter and is 0.05m deep; the cupmark on the WSW side measures 0.07m in diameter and is 0.04m deep. The cupmarks are positioned exactly opposite each other so that they almost form a hole through the slab. (SMR file)
CO106-067001-	Enclosure	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a NW-facing hillslope with views across a valley to Mullaghmesha. A circular area (diam. 11m) is defined by the remains of a collapsed drystone wall (T 0.8m; H 0.5m) consisting of large stones, some of which are partially sod-covered. A boulder (H 1.1m) is incorporated into the wall at NW. The interior slopes down to the NW. A hut site (CO106-067002-) is c. 35m to the SW.
CO106-067002-	Hut site	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a break on a NW-facing hillslope. The remains of a circular hut site (diam. 7m) defined by a moss-covered stone wall (T 0.7m; H 0.4m) which protrudes above the surface of the bog. The interior, which is partially obscured by rubble, is raised (H 0.4m) at the NW and cut (D 0.2m) into the bank at the SE. There is an enclosure (CO106-067001-) c. 35m to the NE.
CO106-067003-	Hut site	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a break on a NW-facing hillslope. The remains of a circular hut site (7.5m NE-SW; 7m NW-SE) defined by a collapsed drystone wall (T 0.6m; H 0.4m) which is partially obscured by heather and moss. The almost level interior is raised (H 0.7m) at the NW and cut (D 0.4m) into the upslope at the SE to compensate for the hillslope. There is a hut site (CO106-067004-) c. 25m to the S and two other hut sites (CO106-067007-, CO106-067008-) are c. 30m to the W.
CO106-067004-	Enclosure	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a break on a NW-facing hillslope with views across a valley to Mullaghmesha. A circular area (diam. 9m) is defined by a partially sod-

Monument No.	Classification	Townland	ASI Inventory Description
			covered collapsed drystone wall (T 0.7m; H 0.55m). The level interior, in pasture, is raised (H 0.3m) at NW and cut into the upslope (D 0.5m) at SE to compensate for the hillslope. There is a hut site (CO106-067003-) c. 25m to the NNE and another (CO106-067005-) c. 35m to the S.
CO106-067005-	Hut site	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a NW-facing hillslope. The remains of an oval hut site (8m NW-SE; 6m NE-SW) defined by a collapsed drystone wall that is in a jumbled state. The lower course consists mainly of boulder-type stones. The interior, which is in pasture, is uneven. A hut site (CO106-067004-) is c. 35m to the N and a second hut site (CO106-067006-) is c. 25m to the SW.
CO106-069----	Enclosure	DERREENACRINNIG EAST	In pasture, on a W-facing slope with views W across a valley to Mullaghmesha. A circular area (11m N-S; 10.5m E-W) is defined by the remains of a stone wall displaying traces of an inner and outer row of contiguous slabs, especially E-NW. Rubble has been deposited against and on the enclosing element NW-E. Two parallel slabs, 2.2m apart, indicate an entrance at SE. Grass-covered stones are scattered in the level interior, which has been raised (H 1m) at W and cut into the bank (D 0.2m) at E to compensate for the hillslope.
CO106-067006-	Hut site	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a terrace on a NW-facing hillslope. The remains of a circular hut site (diam. 6m) defined by a stone wall (T 1m; H 0.4m) which consists of an inner and an outer row of contiguous slabs with a sod-covered infill of smaller stones. The level interior is raised (H 0.3m) at the NW and cut (D 0.2m) into the upslope at the SE to compensate for the hillslope. Another hut site (CO106-067005-) is c. 25m to the NE.
CO106-068----	Enclosure	DERREENACRINNIG EAST	In rough wet pasture on a terrace on a W-facing slope with views W across a valley to Mullaghmesha. The ground rises steeply to the E. A roughly oval-shaped area (20m E-W; 14m N-S) is defined by the remains of a stone wall (T 1m; H 0.3m) largely obscured by long grass. A slab (H 1m; 1.7m x 0.1m) stands with its long axis N-S on the perimeter at W, where a second enclosure (CO106-068001-) adjoins.
CO106-070----	House - vernacular house	GARRANES NORTH	No description
CO106-071----	Redundant record	GARRANES NORTH	In rough wet pasture on a terrace on a W-facing slope with views W across a valley to Mullaghmesha. The ground rises steeply to the E. A roughly oval-shaped area (20m E-W; 14m N-S) is defined by the remains of a stone wall (T 1m; H 0.3m) largely obscured by long grass. A slab (H 1m; 1.7m x 0.1m) stands with its long axis N-S on the perimeter at W, where a second enclosure (CO106-068001-) adjoins.
CO106-072----	Hut site	MULLAGHMESHA	The remains of an oval hut site (3m N-S; 2m E-W) defined by a curving drystone wall (H 0.75m) which abuts an E-W stone wall (L 7.5m) along its S arc. There is an entrance (Wth 0.8m) at the SE. (pers. comm. J. Kiely)
CO106-073----	Hut site	MULLAGHMESHA	The most south-westerly of three conjoined hut sites (see CO106-073001-, CO106-073002-). This hut site is described as being 4m x 3m in diameter. (pers. comm. J. Kiely)

Monument No.	Classification	Townland	ASI Inventory Description
CO106-094----	Well	BARNAGOWLANE WEST	No description
CO106-103----	Hut site	MULLAGHMESHA	This hut site (diam. 2m) is described as being 'partially intact'. There is another hut site (CO106-103001-) c. 3m to the S. (pers. comm. J. Kiely)
CO106-091001-	Enclosure	BARNAGOWLANE EAST	In rough hill grazing, on a NW-facing slope with views W to Bantry Bay and NW across the Mealagh River valley. A rectangular area (7m N-S; 4m E-W) is defined by the remains of a roughly constructed stone wall (T 0.5m; H 0.4m). Rubble is scattered in the interior, which slopes down to the N. A hut site (CO106-091---) adjoins the enclosure at S and a second hut site (CO106-091002-) lies c. 40m to the SSW.
CO106-091002-	Hut site	BARNAGOWLANE EAST	In rough hill grazing, on a NW-facing slope. The remains of an oval hut site (2m E-W; 1.4m N-S) defined by a collapsed drystone wall (T 0.5m; H 0.4m), part of which protrudes above the surface of the bog. The entrance (Wth 0.5m) is at the N. A second hut site (CO106-091---) and an enclosure (CO106-091001-) are c. 40m to the NNE.
CO106-107----	Hut site	DERREENACRINNIG WEST	In rough hill grazing, on a terrace on a S-facing slope overlooking Castledonovan. The remains of a rectangular hut site (4.8m N-S; 1.8m E-W) defined by the lower courses of a clay and stone wall (T 0.6m; H 0.4m). A break at SW may indicate the entrance location. The site is sheltered by rising ground to the W, N and E.
CO106-066001-	Hut site	DERREENACRINNIG EAST	In rough grazing, within the N quadrant of an enclosure (CO106-066----). The remains of a circular hut site (diam. 4.4m) defined by a jumbled, partially grass-covered, stone wall (T 0.6m; H 0.3m) which protrudes above the surface of the peaty soil. The level interior is partially obscured by rubble.
CO106-066002-	Hut site	DERREENACRINNIG EAST	In rough grazing, on the floor of a valley with views SW to Castledonovan. The remains of a D-shaped hut site (2m N-S) defined by a jumbled, curving, stone wall (T 0.6m; H 0.45m) with a straight N side (L 2.8m) which is formed by the external S arc of an enclosure (CO106-066----). The stone wall of the hut site protrudes above the surface of the peaty soil. The well-defined entrance to the enclosure is c. 2m to the E.
CO106-067007-	Hut site	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a NW-facing hillslope. The remains of a D-shaped hut site (2m N-S) defined by a collapsed, curving, drystone wall (T 0.7m; H 0.4m) with a straight S side (L 2.2m) formed by the face of outcropping rock. The drystone wall is jumbled and is partially covered by sods. The entrance (Wth 0.6m) is at the N. There is a hut site (CO106-067008-) c. 3m to the W and another hut site (CO106-067003-) is c. 30m to the E.
CO106-067008-	Hut site	DERREENACRINNIG EAST	In rough grazing, with occasional surface boulders, on a NW-facing hillslope. The remains of a D-shaped hut site (2m N-S) defined by the jumbled and poorly preserved lower courses of a curving stone wall (T 0.6m; H 0.5m) with a straight S side (L 2.1m). The wall consists mainly of boulder-type stones, which are partially covered with moss and sods. A hut site (CO106-067007-) is c. 3m to the E and second hut site (CO106-067003-) is c. 30m to the E.
CO106-108001-	Hut site	GARRANES NORTH	In rough grazing, on a NE-facing hillslope. The remains of a circular hut site (diam. 3m) defined

Monument No.	Classification	Townland	ASI Inventory Description
			by a partially collapsed, roughly constructed, drystone wall (T 0.65m; H 0.6m), the lower courses of which protrude above the surface of bog. The level interior is cut (D 0.4m) into upslope at the SE to compensate for the hillslope. Another hut site (CO106-108002-) is c. 45m to the NE.
CO106-108002-	Hut site	GARRANES NORTH	In rough grazing, on a NE-facing hillslope. The remains of an oval hut site (4m N-S; 3m E-W) defined by a partially collapsed drystone wall (T 0.5m; H 0.4m) which protrudes above shallow bog. The interior is level. Two hut sites (CO106-108003-, CO106-108004-) adjoin this hut site externally at the SE and the S, respectively. Another hut site (CO106-108001-) is c. 45m to the SW.
CO106-108003-	Hut site	GARRANES NORTH	In rough grazing, on a NE-facing hillslope. The remains of a circular hut site (diam. 2.8m) defined by the partially collapsed lower courses of a drystone wall (T 0.5m; H 0.45m) which protrude above shallow bog. Two other hut sites (CO106-108002-, CO106-108004-) adjoin this hut site at the NW and the W, respectively.
CO106-108004-	Hut site	GARRANES NORTH	In rough grazing, on a NE-facing hillslope. The remains of a D-shaped hut site (2m E-W) defined by a collapsing, curving, drystone wall (T 0.6m; H 0.6m) with a straight E side (L 2.5m). The drystone wall (T 0.6m; H 0.6m) protrudes above shallow bog. The interior is level. Two hut sites (CO106-108002-, CO106-108003-) adjoin this hut site at the N and E, respectively. Another hut site (CO106-108005-) is c. 20m to the NE.
CO106-108005-	Hut site	GARRANES NORTH	In rough grazing, on a NE-facing hillslope. The remains of a circular hut site (diam. 2.2m) defined by a jumbled, roughly constructed drystone wall (T 0.55m; H 0.45m) which protrudes above shallow bog. The interior is level. There is an entrance (Wth 0.4m) at the E. Two hut sites (CO106-108006-, CO106-108004-) are 7m to the NE and c. 20m to the SW, respectively.
CO106-108006-	Hut site	GARRANES NORTH	In rough grazing, on a NE-facing hillslope. The remains of a circular hut site (diam. 3.4m) defined by a stone wall (T 0.6m; H 0.3m) E-WNW which protrudes above shallow bog and elsewhere by intermittent remains of the wall. The interior is level. Another hut site (CO106-108005-) is c. 7m to the SW.
CO106-109----	Hut site	GARRANES NORTH	In rough heather and gorse-covered hill grazing, on a terrace on a S-facing slope overlooking Castledonovan. The remains of a roughly circular hut site (4.4m N-S; 4m E-W) defined by the lower courses of a partially collapsed, single-stone wide, drystone wall (T 0.45m; H 0.55m). Rubble is scattered in the level interior. A linear E-W wall forms a separate compartment in the N quadrant; its function is unclear.
CO106-070001-	Field boundary	GARRANES NORTH	In rough heather and gorse-covered grazing, on a stony W-facing slope with a view W across a valley towards Mullaghmesha. The remains of several intermittent stretches of relict stone field boundaries (T 1.6m; H 0.6m) extending over a roughly rectangular area (c. 100m NE-SW; c. 70m NW-SE). The best preserved section of relict boundaries comprises a roughly D-shaped enclosed area (dims. 70m NW-SE) with a straight NW side (L 50m). This area is indicated on the OS 6-inch map. The thin stony ground indicates that turf-cutters have exposed many of the

Monument No.	Classification	Townland	ASI Inventory Description
			relict walls in the area in the past.
CO106-068001-	Enclosure	DERREENACRINNIG EAST	In rough pasture, on a terrace on a W-facing slope with views W across a valley to Mullaghmesha. An oval area (11m N-S; 9.5m E-W) is defined by the remains of a stone wall (T 1m; H 0.3m) S-NW and elsewhere by intermittent stones protruding above the ground. A slab (H 1m; 1.7m x 0.1m) stands with its long axis N-S on the perimeter at E, where a second enclosure (CO106-068----) adjoins.
CO106-103001-	Hut site	MULLAGHMESHA	The remains of this hut site are described as having a diameter of 2.5m and a wall height of c. 0.5m. There is another hut site (CO106-103----) c. 3m to the N. (pers. comm. J. Kiely)
CO106-073001-	Hut site	MULLAGHMESHA	This is the middle example of three conjoined hut sites (see CO106-073----, CO106-073002-). This hut site is described as being 2.5m x 2m in diameter. (pers. comm. J. Kiely)
CO106-073002-	Hut site	MULLAGHMESHA	This is the most north-easterly example of three conjoined hut sites (see CO106-073----, CO106-073001-). This hut site is described as being 2m in diameter and is partially destroyed. (pers. comm. J. Kiely)