

Appendix A7.4 2016 VOC Emission Survey



Unit 32 De Granville Court, Dublin Rd, Trim, Co. Meath

Tel: +353 46 9437922 Mobile: +353 87 6829011 E-mail: <u>info@odourireland.com</u>

E-mail: info@odourireland.com john@odourireland.ie Website: www.odourireland.com

KLRP-VOC/SURFACEEMISSIONS/2016/1 SURFACE EMISSIONS SURVEY AT KERDIFFSTOWN, NAAS, CO. KILDARE

PERFORMED BY ODOUR MONITORING IRELAND ON BEHALF OF JACOBS

PREPARED BY:	Dr. John Casey & Dr. Brian Sheridan
ATTENTION:	Ms. Claire McLaughlin
FACILITY NAME:	Kerdiffstown
DATE OF MONITORING VISIT:	26 th July 2016
NAME AND ADDRESS OF CLIENT ORGANISATION:	Kerdiffstown Landfill Remediation Project (KLRP), Naas, Co. Kildare
NAME AND ADDRESS OF MONITORING ORGANISATION:	Odour Monitoring Ireland, Unit 32 DeGranville Court, Dublin Road, Trim, Co. Meath
DATE OF REPORTING:	29 th Aug. 2016
NAME AND THE FUNCTION OF THE PERSON APPROVING THE REPORT:	Dr. Brian Sheridan, Managing Partner, Odour Monitoring Ireland
REPORT NUMBER:	2016351(1)
REVIEWERS:	

TABLE OF CONTENTS

Sectio	Section Pa	
Docui Recor	OF CONTENTS MENT AMENDMENT RECORD RD SHEET UTIVE SUMMARY	i ii iii iv
1.	Introduction	1
1.1. 1.2.	Background to work Task completed during inspection	1 1
2. 2.1.	Techniques used "Odour hog" monitoring within the facility	2 2
2.2. 2.3.	Meteorological conditions Current facility gas collection infrastructure on the facility	2
3. 3.1.	Results Volatile organic compound surface emissions locations identified	4
3.2.	within KLRP Close out meeting with facility manager	4 6
4.	Conclusions	7
5.	References	7
6.	Appendix I-Volatile organic compound surface emission contour map & Cell capping outline map	s 8
7.	Appendix II-Calibration certificates and procedures	12
8.	Appendix III-Surface Emissions surveys 2011 to 2015	16

DOCUMENT AMENDMENT RECORD

Client: Kildare County Council

<u>Title:</u> KLRP-VOC/SurfaceEmissions/2016/1 Surface emissions Survey at Kerdiffstown Landfill Remediation Project, Naas, Co. Kildare

Project Number	er:2016351		Document	Reference	: KLRP-	
i rojoot mambi	1 Tojout Humborizo 10001			VOC/SurfaceEmissions/2016/1		
2016351(1)	Document for review	JWC	BAS	JWC	29/08/2016	
Revision	Purpose/Description	Originated	Checked	Authorised	Date	
		ODOUR monitoring				

Executive Summary

Kildare County Council commissioned Odour Monitoring Ireland to perform a surface emissions survey at Kerdiffstown Landfill in order to ascertain any likely sources of facility gas surface emissions. The survey was carried out on the 26th July 2016.

During the surface emissions survey, the following tasks were performed on site:

- 1. Identification of the key mechanisms that lead to the release of facility gas surface emissions from the site.
- 2. Identify geographically on a site map, the locations of facility gas surface emissions in order to perform remediation of the identified surface emissions areas.

The following conclusions were drawn from the survey:

- Twelve zones of surface emissions were identified within the facility that exceeded recommended trigger levels. These zones are identified geographically on a site map contained in *Appendix I* of this report.
- Currently none of the facility area is permanently capped. Therefore the surface emission criterion averaged over the capped area does not apply. There were three surface emissions zones greater than or equal to 500 ppm around identified features. There were nine surface emissions zones greater than or equal to 100 ppm instantaneous reading on open surfaces within the facility footprint.
- Nine zones of surface emissions were identified within the facility on 14th October 2015.

1. Introduction

1.1. Background to work

Odour Monitoring Ireland was commissioned by Kildare County Council to perform a specified independent Volatile organic compound surface emissions survey at the Kerdiffstown facility. The assessment involved a volatile organic compound (VOC) surface emissions survey of the facility in order to ascertain the VOC emission points and mark them upon a map for remediation. This report presents a summary of the findings of a VOC surface emissions survey at Kerdiffstown Landfill Remediation Project (KLRP), Naas, Co. Kildare. The report is based on scientific measurements and observations made during a site visit conducted on the 26th July 2016.

1.2. Scope of work

The main aims of the survey included:

- Surface emissions monitoring in accordance with AG6 requirements carried out by Dr. John Casey,
- Discussion meeting with facility manager once survey was complete in order to communicate main surface emissions areas for immediate remediation, where necessary

KLRP

2. **Techniques used**

This section describes the techniques used throughout the study. The surface emissions surveying and reporting was performed by Dr. John Casey, Odour Monitoring Ireland. Dr. John Casey has preformed surface emissions monitoring survey's on behalf of Odour Monitoring Ireland for regulatory bodies in Ireland and Northern Ireland, local authorities in Ireland, private waste operators in Ireland and borough councils in Northern Ireland. A full documented list of previous survey are available upon request.

2.1. "Odour hog" monitoring within the facility

The "odour hog" (i.e. Version 2, 4 years old with less than 3.5 second response time for the flame ionisation detector (FID) VOC analyser is a portable, intrinsically safe, survey VOC dual monitor, which provides fast and accurate readings of organic and inorganic vapours. A photo ionisation detector (PID) uses an ultraviolet (UV) light source (photo) to ionise a gas sample and detect its concentration. Ionisation occurs when a molecule absorbs the high energy UV light, ejecting a negatively charged electron and forming of positively charged molecular ion. The gas becomes electrically charged. These charged particles produce a current that is easily measured at the sensor electrodes. Only a small fraction of the VOC molecules are ionised. A PID does not respond to methane. A FID is similar to a flame thermocouple detector, but measures the ions from the flame instead of the heat generated. The FID detects the methane fraction, which provides greater sensitivity in terms of methane surface emissions detection but not necessarily odour hence why the PID data is also interpreted. The FID/PID analyser was calibrated with certified reference material isobutylene and methane before commencement of the survey, (see calibration certificates for gases used in Appendix II). The calibration readings were rechecked in accordance with AG6 requirements.

Using the continuous kinematic "odour hog" with integrated GPS (i.e Magellan Professional with sub centimetre accuracy post processed), the capping of the facility was surveyed for potential surface emissions areas. Those areas identified were geo-referenced and highlighted for remediation. This technique is useful for comparison in surface emissions area within the same facility on different surveys. The surface emissions maps generated for the particular facility can be used to assess the effectiveness of implemented mitigation techniques and to qualitatively assess the nature of surface emissions from the facility. All surface emissions surveying was carried out in accordance with Air Guidance Note 6.

Efforts should be made to attain surface emissions <100 ppm from open surfaces and <500 ppm around features such as vertical wells, leachate collection sumps, leachate slope risers and other projections out of the waste body (Casey et al., 2008). These are minimum standards, which should lead to greater facility collection efficiencies thus reducing the impact on the general environment.

2.2. **Meteorological conditions**

Table 2.1 illustrates the predominant wind direction during the monitoring exercise. The meteorological conditions were characterised for the day of monitoring and were as follows:

Table 2.1. Meteorological conditions during Kerdiffstown facility TVOC survey.

26 th Jul. 2016			
Average wind speed 13 km/hr Wind direction southerly			
Temperature 19°C	1019 mbar		
Dry weather			

During the VOC and gas field survey, wind deviated from a southerly direction.

2.3 Current facility gas collection infrastructure on the facility

The current collection system consists of vertical wells, there are gravity condensate removal devices on the landfill gas abstraction system within the facility. Vertical facility gas abstraction is employed in the facility. There are two operational installed facility gas enclosed flares (500 m³/hr & 250 m³/hr) capacity enclosed flares. At the time of the survey one flare was in operation.

KLRP

3. **Results**

3.1. Volatile organic compound surface emissions locations identified within KLRP

Figure 6.2 and Table 3.1 illustrates the results obtained for the capping surface emissions survey. A total of twelve individual surface emissions zones were identified. Each surface emissions zone is discussed separately in this manner in order to allow for the development of remediation strategies to mitigate the individual surface emissions areas.

Document No. 2016351(ver.1) Visit No: 01 Year: 2016

KLRP

Table 3.1. Capping VOC surface emission locations results with source identities correlating with *Figure 6.2 (see Appendix I)*.

Location ID	Easting (m)	Northing (m)	Max VOC conc. (ppm)	Identification and Mitigation	Recommended trigger levels
K1	291395	222205	557	Discrete Feature: Intermediate Cap, Vertical Well G35. Investigate and remediate the cause of the surface emissions.	<500ppm
K2	291407	222233	594	Discrete Feature: Intermediate Cap, Vertical Well G31. Investigate and remediate the cause of the surface emissions.	<500ppm
K3	291374	222272	3,847	Discrete Location: Intermediate Cap, Surface area. Investigate and remediate the cause of the surface emissions.	<100ppm
K4	291326	222261	387	Discrete Location: Intermediate Cap, Surface area. Investigate and remediate the cause of the surface emissions.	<100ppm
K5	291380	222296	184	Discrete Location: Intermediate Cap, Surface area. Investigate and remediate the cause of the surface emissions.	<100ppm
K6	291369	222337	398	Discrete Location: Intermediate Cap, Surface area. Investigate and remediate the cause of the surface emissions.	<100ppm
K7	291291	222310	6,947	Discrete Feature: Intermediate Cap, Vertical Well. Investigate and remediate the cause of the surface emissions.	<500ppm
K8	291220	222295	154	Discrete Location: Intermediate Cap, Surface area. Investigate and remediate the cause of the surface emissions.	<100ppm
K9	291215	222327	384	Discrete Location: Intermediate Cap, Surface area. Investigate and remediate the cause of the surface emissions.	<100ppm
K10	291238	222333	3,954	Discrete Location: Intermediate Cap, Surface areas. Investigate and remediate the cause of the surface emissions.	<100ppm
K11	291246	222369	4,178	Discrete Location: Intermediate Cap, Surface area. Investigate and remediate the cause of the surface emissions.	
K12	291263	222324	3,749	Discrete Location: Intermediate Cap, Surface areas. Investigate and remediate the cause of the surface emissions.	<100ppm

www.odourireland.com 5

---KLRP

Twelve sources of facility gas surface emissions were identified (see Figures 6.2 and Table 3.1) within the facility.

Currently none of the facility area is permanently capped. Therefore the surface emission criterion averaged over the capped area does not apply. There were three surface emissions zones greater than or equal to 500 ppm around identified features. There were nine surface emissions zones greater than or equal to 100 ppm instantaneous reading on open surfaces within the facility footprint.

3.2. Close out meeting with facility manager

Following completion of the surface emissions survey, the surface emissions team and the facility manager discussed all aspects and general conclusions of the survey. The facility manager was informed of the potential areas of surface emissions (see section 2.4 and section 3 of the report for details).

4. **Conclusions**

The following conclusions were drawn from the survey of Kerdiffstown Facility:

- The surface emissions contour map generated from the kinematic Volatile organic compound (VOC) survey illustrated surface areas of facility gas surface emissions.
- Currently none of the facility area is permanently capped. Therefore the surface emission criterion averaged over the capped area does not apply. There was three surface emissions zones greater than or equal to 500 ppm around identified features. There were nine surface emissions zones greater than or equal to 100 ppm instantaneous reading on open surfaces within the facility footprint.


5. References

Casey, J.W., Sheridan, B.A., Henry, M., Reynolds, K., (2008). Effective tools for managing odours from facility facilities. International Conference on Environmental Odour Monitoring and Control, Rome, Italy, July 6-8, 2008.

6. Appendix I- Volatile organic compound surface emissions contour map & Cell capping outline & LFG infrastructure map

Figure 6.1. Cell capping outline & LFG infrastructure on the facility.






Document No. 2016351(ver.1) Visit No: 01 Year: 2016

---KLRP

Figure 6.2. Facility gas surface emissions monitoring within the facility (colour scale area indicating TVOC gas colour scale).





www.odourireland.com 11

7. Appendix II-Calibration certificates and procedures.

7.1 Span & Calibration procedure

Necessary Calibration gases: Zero gas (0ppm), 98.8ppm and 988ppm methane (Calibration certificates below).

Calibration is carried out in accordance with manufacturers guidelines.

Location: Zero span instrument onsite.


Frequency: Before, midway through, and after the surface emissions survey, typically therefore at 3-4 hour intervals. If the survey only last 2 to 3 hours the instrument is checked before and after the event.


Instrument settling: The FID is switched on and left to settle for a period of 30 minutes minimum.

Span Procedure: The zero and span gases shall be introduced under the same flow and pressure conditions using the sample probe at the end of the sample line. The adjustment procedure shall be as follows:


- a) Feed the zero gas (0ppm) into the FID and set the zero;
- b) Feed the span gas (98.8ppm) and adjust the instrument accordingly;
- c) Feed the zero gas into the FID once more and check that the reading returns to zero; if not repeat steps a) to c).
- d) repeat procedure A to C to verify

Equipment is maintained and operated as specified by the manufacturer.






Appendix III Surface emissions mapping from 2011 to 2016. 8.



www.odourireland.com 14



www.odourireland.com 15



Appendix A7.5 October 2016 Dust and Odour Report

TEST REPORT 131062

Analysing Testing Consulting Calibrating

3HP

Client:

Priority Construction 162 Clontarf Road Clontarf Dublin 3

FAO: Mr. Paraic Madden

BHP Ref No.: 16/10/1380

Order No.:

Date Received: 21st October 2016 Date Tested: 27th 21st October 2016

Test Specification: Nil

BHP New Ro

New Road Thomondgate Limerick Ireland Tel +353 61 455399 Fax + 353 61 455447

E Mail

dervlapurcell@bhp.ie

Item: Monitoring of emissions to air at locations O1, O2, O3 & O4 at the at the Kerdiffstown Landfill located near Naas, Co Kildare.

For and on behalf of BHP Ltd.

Dervla Purcell

Date Issued: 1st November 2016

Supplement to report No. N/A

DE AM

Test results relate only to this item. This test report shall not be duplicated except in full and with the permission of the test laboratory

BHP CEM Laboratory Page 1 of 7

Contents

1.0	Scope of Survey
2.0	Survey Approach
3.0	Date of survey
4.0	Results

5.0 Conclusions

Appendix A: Map of the Site

Appendix B: Photographs of the monitoring locations

BHP CEM Laboratory Page 2 of 7

1.0 SCOPE OF SURVEY

At the request of Paraic Madden of Priority Construction, BHP Laboratories Ltd undertook to perform gas monitoring and odour observations at 4 nominated locations in Kerdiffstown Landfill, Co Kildare.

2.0 SURVEY APPROACH

All locations were assessed for ammonia, hydrogen sulphide and mercaptans by Drager tube. On site odour observations were also noted at each location

The locations are named D1-D4. They are the same locations as the noise monitoring locations and the dust gauges. A site map showing the monitoring locations is presented in Appendix A. Photographs of the sampling locations are presented in appendix B.

3.0 DATE OF SURVEY

Sampling was carried on the 21st October 2016 by Aidan Daffy.

BHP CEM Laboratory Page 3 of 7

4.0 RESULTS

Results of the gas monitoring and odour observations survey are presented in the following table:


	<u>Table 1</u> Kerdiffstown Landfill - Monitoring Locations 21 st October 2016						
Sample No.	Location	Wind Speed m/s	Wind Direction	Drager Tube	Colour Change	Result (ppm)	Sampling Observations
				Ammonia	None	< 0.25	
1	D1	0-1	Е	Mercaptans	None	< 0.5	No odour observed.
				Hydrogen Sulphide	None	< 0.2	
				Ammonia	None	< 0.25	
2	D2	0-1	Е	Mercaptans	None	< 0.5	No odour observed.
				Hydrogen Sulphide	None	< 0.2	
				Ammonia	None	< 0.25	
3	D3	0-1	Е	Mercaptans	None	< 0.5	No odour observed.
				Hydrogen Sulphide	None	< 0.2	
				Ammonia	None	< 0.25	
4	D4	0-1	Е	Mercaptans	None	< 0.5	No odour observed.
				Hydrogen Sulphide	None	< 0.2	

5.0 CONCLUSIONS

There was no Ammonia, Mercaptan or Hydrogen Sulphide detected above the limit of detection at all monitoring locations as can be seen in Table 1.

BHP CEM Laboratory Page 4 of 7

 $\label{eq:Appendix A} \textbf{Map indicating odour-monitoring locations}$



BHP CEM Laboratory Page 5 of 7

Appendix B

Photographs of odour monitoring locations on-site

Odour monitoring Location D1



Odour monitoring Location D2



BHP CEM Laboratory Page 6 of 7

Odour monitoring Location D3



Odour monitoring Location D4



BHP CEM Laboratory Page 7 of 7



Appendix A7.6 2016 Flare Emissions Monitoring Report

Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1



Report Title	Air Emissions Compliance Monitoring Emissions Report		
Company address	Air Scientific Ltd., 32 DeGranville Court, Dublin road, Trim, Co. Meath		
Stack Emissions Testing Report Commissioned by	Kildare County Council		
Facility Name	Kerdiffstown Landfill		
Contact Person	Ms. Claire McLoughlin		
EPA Licence Number	WL0047-02		
Licence Holder	Kerdiffstown Landfill, F1		
Stack Reference Number	F1		
Dates of the Monitoring Campaign	28/07/2016		
Job Reference Number	KELATL1280716 / 2016390		
Report Written By	Dr. John Casey		
Report Approved by	Dr. Brian Sheridan		
Stack Testing Team	Dr. John Casey		
Report Date	13/09/2016		
Report Type	Test Report Compliance Monitoring		
Version	1		
Signature of Approver	Brian Sheridan Technical Manager		



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Contents

1.	Executive Summary	4
- 1	. Monitoring Objectives	4
	Overall Aim of the monitoring Campaign	4
	Special Requirements	4
	Target Parameters	4
	Emission Limit Values	4
	Reference Conditions	4
	Overall Results	5
	Accreditation details	5
	Monitoring Dates & Times	6
	Process details	7
	Monitoring, Equipment & Analytical Methods	8
	Sampling Deviations	10
	Reference Documents	10
	Suitability of sampling location	11
	Stack diagram	12
2.	APPENDICES	13
ı	I. Appendix I - Monitoring Personnel & Equipment	13
	Stack Emissions Monitoring Personnel	13
ı	II. Appendix II - Stack Details & flow characteristics	14
	Preliminary stack survey calculations	
I	V. Appendix III - Individual parameter sampling details and results	
	Carbon Monoxide Quality Assurance	
	Carbon Monoxide Results & Sampling details	
	Carbon Monoxide Trend	
	Carbon Monoxide Measurement Uncertainty	24
	Oxides of Nitrogen Quality Assurance	
	Oxides of Nitrogen Results & Sampling details	
	Oxides of Nitrogen Trend	
	Oxides of Nitrogen Measurement Uncertainty	
	Total Volatile Organic Carbon Quality Assurance	29
	Total Volatile Organic Carbon Results and Sampling Details	30
	Total Volatile Organic Carbon Trend	
	Total Volatile Organic Carbon Measurement Uncertainty	
	Hydrogen Chloride Sampling Details & Results	
	Hydrogen Chloride Quality Assurance	
	Hydrogen Chloride Results & Measurement Uncertainty	
	Hydrogen Fluoride Sampling Details & Results	
	Hydrogen fluoride Quality Assurance	
	Hydrogen Fluoride Results & Measurement Uncertainty	
	Sulphur Dioxide Quality Assurance	
	Sulphur Dioxide Results & Sampling details	
	Sulphur Dioxide Trend	
	Sulphur Dioxide Measurement Uncertainty	



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Opinions and interpretations expresses herein are outside the scope of Air Scientific Limited INAB accreditation. This test report shall not be reproduced, without the written approval of Air Scientific Limited. All sampling and reporting is completed in accordance with Environmental Protection Agency Air Guidance Note 2 requirements.



Year: 2016 Office: Trim

Visit No: 1

IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Executive Summary

Monitoring Objectives

Overall Aim of the monitoring Campaign

The aim of the monitoring campaign was to demonstrate compliance with a set of emission limit values as specified in the site licence.

Special Requirements

There were no special requirements.

Target Parameters

Carbon Monoxide (CO)	
Oxides of Nitrogen (NOx) as NO ₂	
Total Volatile Organic Carbon (TOC)	
Hydrogen Chloride (HCL)	
Hydrogen Fluoride (HF)	
Sulphur Dioxide (SO ₂)	
Stack Gas Temperature	
Volume (m³.h ⁻¹)	

Emission Limit Values

Emission Limit Values / Mass Emissions Limit Values	mg.m ⁻³	kg.h ⁻¹
СО	-	-
NOx as NO ₂	-	-
TOC	-	-
HCL	-	-
HF	-	-
SO ₂	-	-
Stack Gas Temperature	-	-
Volume (m³.h ⁻¹)	-	-

Reference Conditions

Reference Conditions	Value
Oxygen Reference %	3
Temperature °C	273.15
Total Pressure kPa	101.3
Moisture %	Yes



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Executive Summary

Overall Results

	Concentration				
Parameter	Units	Result	MU +/-	Limit	Compliant
Carbon Monoxide (CO)	mg.m ⁻³	19.13	2.99	-	N/A
Oxides of Nitrogen (NOx) as NO ₂	mg.m ⁻³	17.74	2.39	-	N/A
Total Volatile Organic Carbon (VOC)	mgC.m ⁻³	4.23	0.60	-	N/A
Hydrogen Chloride (HCL)	mg.m ⁻³	0.82	0.003	-	N/A
Hydrogen Fluoride (HF)	mg.m ⁻³	<0.28	0.01	-	N/A
Sulphur Dioxide (SO ₂)	mg.m ⁻³	929.98	58.76	-	N/A
Oxygen (%)	% v/v	8.13	0.15	-	N/A
Stack Gas Temperature	K	1288.15	-	-	N/A

Accreditation details

Air Scientific Limited	INAB319T
External Analytical Laboratory	UKAS1549
Other	-



Document No.: KELATL1280716 / 2016390 Visit No: 1 Year: 2016 Office: Trim

IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Executive Summary

Monitoring Dates & Times

Parameter	Run	Location ID	Sampling Dates	Sampling Time On	Sampling Time Off	Duration (mins.)
Carbon Monoxide (CO)	Run 1	F1	28/07/2016	10:33:00	11:04:00	00:31:00
	Run 2	-	-	-	-	-
	Run 3	-	-	-	-	-
Oxides of Nitrogen (NOx) as NO ₂	Run 1	F1	28/07/2016	10:33:00	11:04:00	00:31:00
	Run 2	-	•	•	•	-
	Run 3	-		-	-	-
Total Volatile Organic Carbon (VOC)	Run 1	F1	28/07/2016	10:36:08	11:04:08	00:30:00
	Run 2	-	-	-	-	-
	Run 3	-	-	-	-	-
Hydrogen Chloride (HCL)	Run 1	F1	28/07/2016	09:05:00	09:37:00	00:32:00
	Run 2	-		-	-	-
	Run 3	-		-	-	-
Hydrogen Fluoride (HF)	Run 1	F1	28/07/2016	09:50:00	10:21:00	00:31:00
	Run 2	-	-	-	-	-
	Run 3	-	-	-	-	-
Sulphur Dioxide (SO ₂)	Run 1	F1	28/07/2016	10:33:00	11:04:00	00:31:00
	Run 2	-	-	-	-	-
	Run 3	-	-	-	-	-
Oxygen (%)		F1	28/07/2016	10:33:00	11:04:00	00:31:00



Document No.: KELATL1280716 / 2016390 Visit No: 1 Year: 2016 Office: Trim

IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Executive Summary

Process details

Parameter		
Process status	Normal	
Capacity (per/hour) (if applicable)	69m3/hr	
Continuous or Batch Process	Continuous	
Feedstock	LFG	
Abatement System	No	
Abatement Systems Running Status	N/A	
Fuel	LFG	
Plume Appearance	Yes	
Other information	None	



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Executive Summary

Monitoring, Equipment & Analytical Methods

	Monitoring				Analysis	
Parameter	Standard	Technical Procedure	Accredited Testing	Testing Lab	Analytical Technique	Analysis Lab
Carbon Monoxide (CO)	EN15058:2006	SOP 2004	Yes	AirSci	NCIR By Horiba PG-250	AirSci
Oxides of Nitrogen (NOx)	EN14792:2006	SOP 2002	Yes	AirSci	Chemiluminescence	AirSci
Total Volatile Organic Carbon (TOC)	EN12619:2013	SOP 2009	Yes	AirSci	Flame Ionisation Detection	AirSci
Hydrogen Chloride (HCL)	EN1911:2010	SOP 2014	Yes	AirSci	Ion Chromatography	SAL
Hydrogen Fluoride (HF)	EN15713:2006	SOP 2024	No	AirSci	Ion Chromatography	SAL
Sulphur Dioxide (SO2)	TGN 21	SOP 2012	Yes	AirSci	NDIR Absorption	AirSci
Oxygen (%)	EN14789:2005	SOP 2008	Yes	AirSci	Paramagnetic	AirSci
Stack Gas Temperature	EN16911:2013	SOP 2005	No	AirSci	Thermocouple	AirSci



Document No.: KELATL1280716 / 2016390 Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

List of Equipment

ID	Item of Equipment	Manufacturer	Serial No.
ASLTM12EQ509	3010 MinfiFID	Signal Instruments	16764
ASLTM12EQ517	Testo 400 Gas Pressure Vacumn and Flow	Testo	00828828/305
			100063602044367-
ASLTM12EQ520	Buhler Sample Gas Cooler	Buhler Technologies	001
ASLTM13EQ504	Horiba PG2500 Portable Flue Gas Analzer	Horiba	41432840053
	10 metre industrial heated sample line		
ASLTM13EQ509	(Temp controller box 1 & 2)	Neptech	13B088
ASLTM15EQ505	Mass flow meter	Siargo	A1K05286



IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Sampling Deviations

Parameter	Deviation
Standard ID	EN1911 & EN15713 - absorption efficiency <95%
Standard ID	-
Standard ID	-
Standard ID	-

Reference Documents

Risk Assessment (RA)	SOP1011
Site Review (SR)	SOP1015
Site Specific Protocol (SSP)	SOP1015



Visit No: 1 Year: 2016 Office: Trim

IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Executive Summary

Suitability of sampling location

General Information	Value
Permanent/Temporary	Temporary
Inside/ Outside	Outside

Platform Details		
Irish EPA Technical Guidance Note AG1 / BS EN 15259 Platform Requirements	Value	Comment
Sufficient Working area to manipulate probe and measuring instruments	Yes	-
Platform has 2 handrails (approx. 0.5m & 1.0 m high)	Yes	-
Platform has vertical base boards (approx. 0.25 m high)	Yes	-
Platform has chains / self closing gates at top of ladders	Yes	-
There are no obstructions present which hamper insertion of sampling equipment	No	-
Safe Access Available	Yes	=
Easy Access Available	Yes	-

Sampling Location / Platform Improvement Recommendations	
None	

BSEN 15259 Homogeneity Test Requirements

1: There is no requirement to perform a BSEN15259 Homogenity Test on this stack

E.g. Select Option


- 1: There is no requirement to perform a BSEN15259 Homogenity Test on this stack
 2: Test results were obtained from previous Homogeneity test carried out by ASL
- 3: Test results were obtained from previous Homogeneity test carried out by Alternative contractor 4: Other: Enter Description



IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Executive Summary

Stack diagram





Visit No: 1 Year: 2016 Office: Trim 0716 / 2016390 IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

APPENDICES

II. Appendix I Monitoring Personnel & Equipment

Stack Emissions Monitoring Personnel

Team Leader	Name	John Casey
	Qualifications	PhD. (Eng.), MSc. (Agr.), B. Agr. Sc.
	System approval	Air Scientific Limited Approved
		-



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

III. Appendix II Stack Details & flow characteristics

Preliminary stack survey calculations

General Stack Details		
Stack details	Units	Value
Date of survey		28/07/2016
Time of survey		-
Туре		Circular
Stack Diameter / Depth, D	m	-
Stack Width, W	m	-
Average Stack Gas Temp., Ta	С	1015
Average Static Pressure, P static	kPa	-
Average Barometric Pressure, Pb	kPa	-
Type of Pitot		-
Are Water Droplets Present ?		-
Average Pitot Tube Calibration Coeff, Cp		-
Negative flow		-
Highly homogeneous flow stream/gas velocity		Yes

Sample Port Size	mm	-
Initial Pitot Leak Check	Pa	-
Final Pitot Leak Check	Pa	-
Orientation of Duct		Vertical
Pitot Tube Cp		0.998
Number of Lines Available		1
Number of Lines Used		1



Visit No: 1 Year: 2016 Office: Trim

nev.no. i						
Sampling Line A						
Point	Distance to duct (m)	Pa	Temp °C	Velocity (m/s)	Oxygen (%)	Angle of Swirl
1	-	-	-	-	-	-
2	-	-	-	-	-	-
3	-	-	-	-	-	-
4	-	-	-	-	-	-
5	-	-	-	-	-	-
6	-	-	-	-	-	-
7	-	-	-	-	-	-
8	-	-	-	-	-	-
9	-	-	-	-	-	-
10	-	-	-	-	-	-
Average	-	-	-	-	-	-
Min	-	-	-	-	-	-
Max	_	-	_	_	_	_



Visit No: 1 Year: 2016 Office: Trim

Sampling Line B						
Point	Distance to duct (m)	Pa	Temp °C	Velocity (m/s)	Oxygen (%)	Angle of Swirl
1	-	-	-	-	-	-
2	-	-	-	-	-	-
3	-	-	-	-	-	-
4	-	-	-	-	-	-
5	-	-	-	-	-	-
6	-	-	-	-	-	-
7	-	-	-	-	-	-
8	-	-	-	-	-	-
9	-	-	-	-	-	-
10	-	-	-	-	-	-
Average	-	-	-	-	-	-
Min	-	-	-	-	-	-
Max	-	_	-	-	-	_



Visit No: 1 Year: 2016 Office: Trim

-		-	_				
	R	e	٧.	N	lo:	1	

Component	Conc. ppm	Conc. Dry % v/v	Conc. Wet % v/v	Molar Mass
Carbon Dioxide CO ₂	-	10.31	-	44.01
Oxygen O ₂	-	8.12	-	32
Nitrogen N ₂	-	81.57	-	28.1
Moisture (H₂O)	-	-	9	18.02
Reference Conditions	Units	Numbers		
Temperature	°C	273.15		
Temperature Total Pressure	°C kPa	273.15 101.3		
<u> </u>	-			



Visit No: 1 Year: 2016 Office: Trim

Stack Gas Composition & Molecular Weights								
Component	Molar Mass M	Density Kg/m³	Conc. Dry % v/v	Dry Volume Fraction r	Dry Conc. kg/m³ pi	Conc. wet % v/v	Wet Volume Fraction r	Wet Conc.kg/m ³ pi
Carbon Dioxide CO ₂	44.01	1.96	10.31	0.1031	0.20	9.38	0.09	0.18
Oxygen O ₂	32	1.43	8.12	0.0812	0.12	7.39	0.07	0.11
Nitrogen N ₂	28.1	1.25	81.57	0.8157	1.02	74.23	0.74	0.93
Moisture (H₂O)	18.02	0.80	-	-	-	9	0.09	0.07
	-	-	-	-	-	-	-	-
where p=M/22.41	-	-	-	-	-	-	-	-
pi = r x p								



Visit No: 1 Year: 2016 Office: Trim

Calculation of Stack Gas Densities		
Determinand	Units	Result
Dry Density (STP), P STD	kg.m ⁻³	1.341
Wet Density (STP), P STW	kg.m ⁻³	1.297
Dry Density (Actual), P Actual	kg.m ⁻³	-
Average wet Density (Actual), P ActualW	kg.m ⁻³	-
Where		
P STD = sum of component concentrations, kg/m3 (excluding water vapour)	-	-
P STW = (P STD + pi of H2O) / (1 + (pi of H2O / 0.8036))	-	-
P actual = P STD x (T STP / (P STP)) x (Pa / Ta)	-	-
P actual W (at each sampling point) = P STW x (Ts / Ps) x (Pa / Ta)	-	-



Visit No: 1 Year: 2016 Office: Trim

Sampling Plane Validation Criteria	Value	Units	Requirement	Compliance	Method
Lowest Differential Pressure	-	Pa	>5 Pa	N/A	EN16911:2013
Lowest Gas Velocity	-	m/s	-	N/A	-
Highest Gas Velocity	-	m/s	-	N/A	-
Ratio of Above	-	:1	<3:1	N/A	EN16911:2013
Mean Velocity	-	m/s	-	N/A	-
Angle of flow with regard to duct axis		degrees	< 15	N/A	EN16911:2013
No local negative flow	-	-	-	N/A	-
Homogeneous flow stream/gas velocity	-	-	-	N/A	-

Calculation of stack Gas Velocity, V	
Velocity at Traverse Point, V = Kcp * Sqroot ((2 * DP) / Density)	-
Where	
Kpt = Pitot tube calibration coefficient	-
Compressibility correction factor, assumed at a constant 0.998	0.998

Gas Volumetric Flowrate	Units	Result
Gas Volumetric Flow Rate (Actual)	m ³ .h ⁻¹	-
Gas Volumetric Flow Rate (STP, Wet)	m ³ . h ⁻¹	-
Gas Volumetric Flowrate (STP, Dry)	m ³ . h ⁻¹	-
Gas Volumetric Flowrate REF to Oxygen	m ³ . h ⁻¹	-



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

IV. Appendix III Individual parameter sampling details and results

Carbon Monoxide Quality Assurance

Compline Details		
Sampling Details		
Stack ID	F1	-
	Units	Run 1
Parameter		
Sampling Times	-	10:32
Sampling Dates	-	28/07/2016
Instrument Range	ppm	200
Span Gas Value	ppm	149
Acceptable Gas Range	-	Yes
Quality Assurance	Units	Run 1
Conditioning Unit Temperature	С	2
Average Temperature	< C	2
Allowable Temperature	-	4
Temperature Acceptable	-	Yes
Pump flow rate	l/min.	0.5
Zero Drift	Units	Run 1
Zero Down Sampling Line (Pre)	ppm	0.2
Zero Down Sampling Line (Post)	ppm	0.4
Zero drift	ppm	0.2
Allowable Zero Drift	ppm	2.97
Zero Drift Acceptable	-	Yes
Span Drift	Units	Run 1
Span Down Sampling Line (Pre)	ppm	148.8
Span Down Sampling Line (Post)	ppm	150.4
Span Drift	ppm	1.6
Allowable Span Drift	ppm	2.97
Span Drift Acceptable (Y/N)	-	Yes
Leak Check		
Span Gas Conc.	ppm	149
Recorded Conc. down Line	ppm	148.8
Leak check acceptable (< 2%)	(Y/N)	Yes
	, ,	
Test Conditions	Units	Run 1
Run Ambient Temperature Range	С	15



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Carbon Monoxide Results & Sampling details


Parameter	Units	Run 1
Concentration	mg.m ⁻³	13.65
Uncertainty	mg.m ⁻³	2.99
Mass Emission	kg.h	-

General Sampling Information	
Parameter	Value
Standard	EN15058
Technical Procedure	SOP2004
Probe material	SS
Filtration Type/Size	PTFE
Heated Head Filter Used	Yes
Heated Line Temperature	190
Span Gas Reference Number	ASLTM15ING508
Span Gas Expiry Date	Nov-17
Span Gas Start Pressure (bar)	20
Gas Cylinder Concentration (ppm)	149
Span Gas Uncertainty (%)	<2
Zero Gas Type	Nitrogen
Number of Sampling Lines Used	1
Number of Sampling Points Used	1
Sample Point I.D's	F1
Reference Conditions	
Temperature (K)	273.15
Pressure (kPa)	101.3
Gas (Wet or Dry)	Dry
Oxygen	3



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Carbon Monoxide Trend





Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Carbon Monoxide Measurement Uncertainty

	Units	Run 1
Measured Quantities		
Certified Range of Analyser	ppm	1.36 to 1000
Operational Range of Analyser	ppm	200
Measured Reading	ppm	10.92
Measured Quantities	Units	Run 1
Nonlinearity	%	0.9
Temperature Dependent Zero drift	%	0.14
Temperature Dependent Span drift	%	-0.12
Cross-sensitivity	%	0.08
Leak	%	0
Calibration Gas Uncertainty	%	<2
Parameter	Units	Run 1
Combined uncertainty	mg.m ⁻³	0.99
Expanded uncertainty	mg.m ⁻³	1.98
Uncertainty corrected to std conds.	mg.m ⁻³	2.99
Expanded uncertainty expressed with a level of confidence of 95%	% of ELV	-
Expanded uncertainty expressed with a level of confidence of 95%	mg.m ⁻³	2.99
Expanded uncertainty expressed with a level of confidence of 95%	% of value	21.90
Requirement in standard is for uncertainty to be < 10% at ELV at standard conditions		



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Oxides of Nitrogen Quality Assurance

0. " 5 : "		
Sampling Details		
Stack ID	F1	-
	Units	Run 1
Parameter		
Sampling Times	-	10:32
Sampling Dates	-	28/07/2016
Instrument Range	ppm	250
Span Gas Value	ppm	158
Acceptable Gas Range	-	Yes
Quality Assurance	Units	Run 1
Conditioning Unit Temperature	С	2
Average Temperature	< C	2
Allowable Temperature	-	4
Temperature Acceptable	-	Yes
Pump flow rate	l/min.	0.5
Zero Drift	Units	Run 1
Zero Down Sampling Line (Pre)	ppm	0.1
Zero Down Sampling Line (Post)	ppm	0
Zero drift	ppm	0.1
Allowable Zero Drift	ppm	3.16
Zero Drift Acceptable	-	Yes
Span Drift	Units	Run 1
Span Down Sampling Line (Pre)	ppm	158.4
Span Down Sampling Line (Post)	ppm	156.3
Span Drift	ppm	2.1
Allowable Span Drift	ppm	3.16
Span Drift Acceptable (Y/N)	-	Yes
Leak Check		
Span Gas Conc.	ppm	158
Recorded Conc. down Line	ppm	158.4
Leak check acceptable (< 2%)	(Y/N)	Yes
	(•)	
Test Conditions	Units	Run 1
Run Ambient Temperature Range	С	15
NOx Converter Efficiency	%	95.3



IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Oxides of Nitrogen Results & Sampling details


Parameter	Units	Run 1
Concentration	mg.m ⁻³	12.66
Uncertainty	mg.m ⁻³	2.39
Mass Emission	kg.h⁻¹	-

General Sampling Information	
Parameter	Value
Standard	EN14792
Technical Procedure	SOP2002
Probe material	SS
Filtration Type/Size	PTFE
Heated Head Filter Used	Yes
Heated Line Temperature	190
Date & Result of last converter check	95.3 18/12/2015
Span Gas Reference Number	ASLTM15ING533
Span Gas Expiry Date	Dec-16
Span Gas Start Pressure (bar)	40
Gas Cylinder Concentration (ppm)	158
Span Gas Uncertainty (%)	<2
Zero Gas Type	Nitrogen
Number of Sampling Lines Used	1
Number of Sampling Points Used	1
Sample Point I.D's	F1
Reference Conditions	
Temperature (K)	273.15
Pressure (kPa)	101.3
Gas (Wet or Dry)	Dry
Oxygen	3



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Oxides of Nitrogen Trend





Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Oxides of Nitrogen Measurement Uncertainty

Measured Quantities	Units	Run 1
Nonlinearity	%	1.4
Temperature Dependent Zero drift	%	-0.04
Temperature Dependent Span drift	%	-0.25
Cross-sensitivity	%	0.5
Leak	%	0
Calibration Gas Uncertainty	%	<2
Mass Flow Controllers (Dilution) Uncertainty	%	<1
NOx Converter Efficiency	%	95.3
Parameter	Units	Run 1
Combined uncertainty	mg.m ⁻³	0.77
Expanded uncertainty	mg.m ⁻³	1.55
	.3	
Uncertainty corrected to std conds.	mg.m ⁻³	2.39
Expanded uncertainty expressed with a level of confidence of 95%	% of ELV	-
Expanded uncertainty expressed with a level of confidence of 95%	mg.m ⁻³	2.39
Expanded uncertainty expressed with a level of confidence of 95%	% of value	18.84
Requirement in standard is for uncertainty to be < 10% at ELV at standard conditions		



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Total Volatile Organic Carbon Quality Assurance

		1
Sampling Details		
Stack ID	F1	-
	Units	Run 1
Parameter		
Sampling Times	-	10:36
Sampling Dates	-	28/07/2016
Instrument Range	ppm	100
Span Gas Value	ppm	79
Acceptable Gas Range	-	Yes
Quality Assurance	Units	Run 1
Oven Temperature	С	193
Average Temperature	< C	193
Temperature Acceptable	-	Yes
Sample line temperature	С	190
Zero Drift	Units	Run 1
Zero Down Sampling Line (Pre)	ppm	0.1
Zero Down Sampling Line (Post)	ppm	0.4
Zero drift	ppm	0.3
Allowable Zero Drift	ppm	1.5
Zero Drift Acceptable	-	Yes
Span Drift	Units	Run 1
Span Down Sampling Line (Pre)	ppm	78.9
Span Down Sampling Line (Post)	ppm	77.8
Span Drift	ppm	1.1
Allowable Span Drift	ppm	1.5
Span Drift Acceptable (Y/N)	-	Yes
Leak Check		
Span Gas Conc.	ppm	79
Recorded Conc. down Line	ppm	78.9
Leak check acceptable (< 2%)	(Y/N)	Yes
	(1/14)	163



IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Total Volatile Organic Carbon Results and Sampling Details


Parameter	Units	Run 1
Concentration	mgC.m ⁻³	3.02
Uncertainty	mgC.m ⁻³	0.60
Mass Emission	kg.h ⁻¹	-

General Sampling Information	
Parameter	Value
Standard	EN12619
Technical Procedure	SOP2009
Probe material	SS
Filtration Type/Size	PTFE
Heated Head Filter Used	Yes
Heated Line Temperature	190
Span Gas Reference Number	ASLTM15ING532
Span Gas Expiry Date	01/12/2018
Span Gas Start Pressure (bar)	30
Gas Cylinder Concentration (ppm)	79
Span Gas Uncertainty (%)	<2
Zero Gas Type	Ambient
Number of Sampling Lines Used	1
Number of Sampling Points Used	1
Sample Point I.D's	F1
Reference Conditions	-
Temperature (K)	273.15
Pressure (kPa)	101.3
Gas (Wet or Dry)	Dry
Oxygen	3



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Total Volatile Organic Carbon Trend





Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Total Volatile Organic Carbon Measurement Uncertainty

	Units	Run 1
Measured Quantities		
Certified Range of Analyser	ppm	0.5 to 1000
Operational Range of Analyser	ppm	100
Measured Reading	ppm	1.71
Measured Quantities	Units	Run 1
Nonlinearity	%	0.068
Temperature Dependent Zero drift	%	0.3
Temperature Dependent Span drift	%	0.3
Cross-sensitivity	%	-
Leak	%	<2
Calibration Gas uncertainty	%	<2
Parameter	Units	Run 1
Combined uncertainty	mg.m ⁻³	0.30
Expanded uncertainty	mg.m ⁻³	0.60
Expanded uncertainty expressed with a level of confidence of 95%	% of ELV	-
Expanded uncertainty expressed with a level of confidence of 95%	% of value	19.75
Expanded uncertainty expressed with a level of confidence of 95%	mg.m ⁻³	0.60
Requirement in standard is for uncertainty to be < 10% at ELV at standard conditions		



IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Hydrogen Chloride Sampling Details & Results

myarogon omonuo cumpung zotano a nocuno			
Stack ID	F1	Run 1	
Sample ID	F1HCL1	mls	
Impinger 1 ID	F1HCL1+2	130	
Impinger 2 ID	-	-	
Impinger 3 ID	F1HCL3	130	
Time on	09:05		
Time off	09:37		
Leak Check Results			
Prior to test:	0.03	l/min	
Post Test:	0.02	l/min	
Sample Volume Flow Rate:	1.8	l/min	
Standard Requirement:	<2	%	
Test Result:	0	%	
Test Status	Pass		
Calibration Details			
Pump Number:	-		
Calibration Unit:	ASLTM15EQ505		
Calibration Rate Before Test:	1.8	litres per minute	
Calibration Rate After Test:	1.900	litres per minute	
Average sample Volume:	1.8	litres per minute	
Sample Test Time:	32	minutes	
Pump Gas Temperature:	0	°C	
Pump Sample Pressure:	101.3	kPa	
Actual Sample Volume:	0.05760	m ³	
Normalised Gas Volume:	0.05760	Nm ³	



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Hydrogen Chloride Quality Assurance

Stack ID	F1	-
Date	28/07/2016	-
Start time	-	09:05:00
Finish Time	-	09:37:00
	Units	Run 1
Leak test results		
Mean Sampling Rate	l/min	1.8
Pre-sampling leak rate	l/min	0.03
Post-sampling leak rate	l/min	0.02
Leak rate	l/min	0
Acceptable leak rate (<2%)	Y/N	Yes
Filtration		
Filter Material	-	N/A
Filter Size	mm	N/A
Max. Filter Temp	degrees	N/A
Absorbers Type	Glass/PTFE/ Other	PTFE
Absorption Solution	-	Di H2O
Absorption Efficiency		
Total Imp1 + Imp 2 + Imp 3	ug	33.8
Impinger 3	ug	6.5
Absorption efficiency	%	81
Acceptable Absorption Eff.	>95% (Y/N)	N
Blank sample		
Blank sample ID	-	F1HCLB
Blank result	mg/m³	<0.11
Acceptable Blank	<10% ELV (Y/N)	Y
	()	
Testing laboratory		
Laboratory Name	-	UKAS1549
Test certificate Number	-	589741
		1 222



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Hydrogen Chloride Results & Measurement Uncertainty

Stack ID	F1	Run 1
Date	-	
Start time	09:05	
Finish Time	09:37	
Results		
Laboratory Result	33.8	μg/ml
Impinger final Volume	260	ml
Concentration	0.03	mg
Sample Volume	0.058	Nm³
Emissions Concentration	0.59	mg.m ⁻³
Mass Emissions	-	kg.h ⁻¹

	Units	Run 1
	Units	Run 1
Parameter		
Combined Uncertainty	mg.m ⁻³	0.001
Expanded uncertainty as percentage of measured value	% of measured value	4.80
Expanded uncertainty in units of measurement	mg.m ⁻³	0.003
Expanded uncertainty as percentage of limit value	% Of ELV	-



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Hydrogen Fluoride Sampling Details & Results

Sampling Details		Run 1
Stack ID	F1	-
Start time	09:50	
Finish Time	10:21	
Leak Check Results	10.21	
Prior to test:	0.02	l/min
Post Test:	0.02	l/min
Sample Volume Flow Rate:	1.9	l/min
Standard Requirement:	<2	%
Test Result:	0	%
Test Status	Pass	
Calibration Details		
Pump Number:	-	
Calibration Unit:	ASLTM15EQ505	
Calibration Rate Before Test:	1.9	l/min
Calibration Rate After Test:	1.9	l/min
Average sample Volume:	1.9	l/min
Sample Test Time:	31	min
Pump Gas Temperature:	0	°C
Pump Sample Pressure:	101.3	kPa
Actual Sample Volume:	0.05890	m ³
Normalised Gas Volume:	0.06473	Nm³



IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Hydrogen fluoride Quality Assurance

Start time	-	09:50:00
Finish Time	-	10:21:00
	Units	Run 1
Leak test results		
Mean Sampling Rate	l/min	1.9
Pre-sampling leak rate	l/min	0.02
Post-sampling leak rate	l/min	0.02
Leak rate	l/min	0.00
Acceptable leak rate (<2%)	Y/N	Yes
Filtration		
Filter Material	-	N/A
Filter Size	mm	N/A
Max. Filter Temp	degrees	N/A
Absorbers Type	Glass/PTFE/ Other	Glass
Absorption Solution	-	0.1m NaOH
Absorption Efficiency		
Total Imp 1 + Imp2 + Imp3	ug	13
Impinger 3	ug	6.5
Absorption efficiency	%	50
Acceptable Absorption Eff.	>95% (Y/N)	N
Blank sample		
Blank sample ID	-	F1HFB
Blank result	mg/m ³ <0.08	
Acceptable Blank	<10% ELV (Y/N)	Υ



IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Hydrogen Fluoride Results & Measurement Uncertainty

Sampling Details		Run 1
Stack ID	F1	
Date	-	
Start time	09:50:00	
Finish Time	10:21:00	
Results		
Laboratory Result	13	μg/ml
Impinger final Volume	260	ml
Concentration	0.01	mg
Sample Volume	0.06	Nm ³
Emissions Concentration	<0.20	mg.m ⁻³
Mass Emissions	-	kg.h⁻¹

	Units	Run 1
	Units	Run 1
Parameter		
Combined Uncertainty	mg.m ⁻³	0.005
Expanded uncertainty as percentage of measured value	% of measured value	4.742
Expanded uncertainty in units of measurement	mg.m ⁻³	0.010
Expanded uncertainty as percentage of limit value	% Of ELV	-



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Sulphur Dioxide Quality Assurance

Sampling Details		
Stack ID	F1	
	Units	Run 1
Parameter	Onits	nuii i
Sampling Times	_	10:32
Sampling Dates		28/07/2016
Instrument Range		1000
Span Gas Value	ppm	506
Acceptable Gas Range	- ppiii	Yes
	_	-
Quality Assurance	Units	Run 1
Conditioning Unit Temperature	С	2
Average Temperature	< C	2
Allowable Temperature	-	4
Temperature Acceptable	-	Yes
Pump flow rate	l/min.	0.5
	_	-
Zero Drift	Units	Run 1
Zero Down Sampling Line (Pre)	ppm	0
Zero Down Sampling Line (Post)	ppm	6
Zero drift	ppm	6
Allowable Zero Drift	ppm	25
Zero Drift Acceptable	-	Yes
	-	-
Span Drift	Units	Run 1
Span Down Sampling Line (Pre)	ppm	510
Span Down Sampling Line (Post)	ppm	488
Span Drift	ppm	22
Allowable Span Drift	ppm	25
Span Drift Acceptable (Y/N)	-	Yes
	-	-
Leak Check		
Span Gas Conc.	ppm	506
Recorded Conc. down Line	ppm	510
Leak check acceptable (< 2%)	(Y/N)	Yes
	-	-
Test Conditions	Units	Run 1
Run Ambient Temperature Range	С	15



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Sulphur Dioxide Results & Sampling details


Parameter	Units	Run 1
Concentration	mg.m ⁻³	663.52
Uncertainty	mg.m ⁻³	58.76
Mass Emission	kg.h	-

General Sampling Information	
Parameter	Value
Standard	TGN 21
Technical Procedure	2012
Probe material	SS
Filtration Type/Size	PTFE
Heated Head Filter Used	Yes
Heated Line Temperature	190
Date & Result of last converter check	-
Span Gas Reference Number	ASLTM15ING507
Span Gas Expiry Date	Nov-16
Span Gas Start Pressure (bar)	30
Gas Cylinder Concentration (ppm)	506
Span Gas Uncertainty (%)	<2
Zero Gas Type	N
Number of Sampling Lines Used	1
Number of Sampling Points Used	1
Sample Point I.D's	F1
Reference Conditions	
Temperature (K)	273.15
Pressure (kPa)	101.3
Gas (Wet or Dry)	Dry
Oxygen	3



Visit No: 1 Year: 2016 Office: Trim IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Sulphur Dioxide Trend





IPPC Licence No.: WL0047-02 Licence Holder: Kerdiffstown Landfill, F1 Facility Location: Kerdiffstown Landfill Rev.No: 1

Sulphur Dioxide Measurement Uncertainty

	Units	Run 1
Measured Quantities		
Certified Range of Analyser	ppm	2.14 to 1000
Operational Range of Analyser	ppm	1000
Measured Reading	ppm	232.00
Measured Quantities	Units	Run 1
Nonlinearity	%	0.8
Temperature Dependent Zero drift	%	0.8
Temperature Dependent Span drift	%	2
Cross-sensitivity	%	1.5
Leak	%	0
Calibration Gas Uncertainty	%	<2 %
Parameter	Units	Run 1
Combined uncertainty	mg.m ⁻³	9.43
Expanded uncertainty	mg.m ⁻³	18.86
Uncertainty corrected to std conds.	mg.m ⁻³	58.76
Expanded uncertainty expressed with a level of confidence of 95%	% of ELV	-
Expanded uncertainty expressed with a level of confidence of 95%	mg.m ⁻³	58.76
Expanded uncertainty expressed with a level of confidence of 95%	% of value	8.86
Requirement in standard is for uncertainty to be < 10% at ELV at standard conditions		

