



CYAL50382430 © Tailte Eireann - Surveying.

- Notes:**
1. Topographical survey to ITM grid reference and Malin Head Ordnance Datum.
 2. Do not scale from this drawing.
 3. All dimension are in metres unless noted otherwise.
 4. Proposed pipework material shall be
 - Gravity = Polypipe Polysewer pipework and fittings.
 - Pumped = PE100 SDR 11 butt fusion welded joints.
 5. Proposed foul water drainage has been designed to achieve a minimum self-cleansing velocity of 0.75m/s.
 6. Proposed manhole covers shall be the Noroc ductile iron cover by EJ Covers, load class D400 to IS EN 124.
 7. Proposed WwTP shall be the BMS Blivet Unit BL300 with a 20:30 discharge standard.

- Legend:**
- Planning Boundary
 - Gravity Drain & Manhole
 - Pumped Rising Main

PL2	29/08/25	EG	SM	JMacC
Issued for RFI				
PL1	11/12/15	J.B.	J.B.	JMacC
Issued for Planning				
Rev	Date	By	Chkd	Appd

ARUP
One Albert Quay
Cork, Ireland
Tel +353 (0)21 422 3200
www.arup.com



Project Title
Ringaskiddy Resource
Recovery Centre

Drawing Title
Proposed Foul Drainage
Layout
Sheet 1 of 2

Scale at A1	1:500
Role	Site Infrastructure
Suitability	Response to Request for Information
Arup Job No	Rev
307174-00	PL2
Name	
C-000-021	