



CYAL50382430 © Tailte Eireann - Surveying.

Notes:

- Topographical survey to ITM grid reference and Malin Head Ordnance Datum.
- Do not scale from this drawing.
- All dimension are in metres unless noted otherwise.
- Proposed pipework shall be ductile iron Class K9 cement lined pipework and fittings with a factory applied cement sealant.
- All valves and fittings shall be PN16 rated.
- Thrust blocks shall be located at all vertical and horizontal changes in direction of 22.5° or greater.
- The fire hydrant location and number shall be agreed with the Fire Office during the Fire Certificate stage. Shown here indicatively only.
- The proposed bulk water meter specification shall conform to Irish Water requirements.

Legend:

Planning Boundary

Proposed Potable Main

Proposed Fire Main

Existing Watermain

Existing Watermain to be removed

Proposed Hydrant

Proposed Water Meter

PL2	29/08/25	EG	SM	JMacC
Issued for RFI				
PL1	11/12/15	J.B.	J.B.	JMacC
Issued for Planning				
Rev	Date	By	Chkd	Appd

ARUP

One Albert Quay
Cork, Ireland
Tel +353 (0)21 422 3200
www.arup.com

Client

INDAVER

Project Title

Ringaskiddy Resource Recovery Centre

Drawing Title

Proposed Potable & Fire Main Layout

Scale at A1 1:500

Role	Site Infrastructure
Suitability	Response to Request for Information
Arup Job No	307174-00
Name	C-000-031
Rev	PL2