11 SUMMARY OF MITIGATION MEASURES

- 1 The evaluation of likely significant impacts of the proposed development as described throughout this Environmental Impact Statement (EIS) includes recommendations for specific measures to avoid, reduce and, if possible, offset the major adverse effects (i.e. mitigation measures). These measures are considered necessary to minimise environmental impacts associated with the proposed development during both its construction and operational phases. They are also referred to in this EIS as a Schedule of Mitigation Measures or Schedule of Environmental Commitments.
- 2 **Table 11.1** provides a collective summary of the proposed mitigation measures for both the construction and operational phases of the proposed development. The table includes the following:
 - Mitigation measure item number;
 - Approximate location of mitigation measure;
 - Mitigation objective and commitment;
 - An outline of the mitigation measure;
 - Timing of the mitigation measure; and
 - Monitoring requirements.
- 3 As set out in **Table 11.1**, there may be a requirement for additional consultation to be carried out during the construction period with landowners and certain prescribed authorities, in particular to ensure (i) the effectiveness of mitigation measures in relation to the environmental effects and (ii) that landowners are aware of the specific works that will take place pursuant to the proposed development.
- 4 **Table 11.1** provides a brief summary of recommended mitigation measures. This table should be read in conjunction with individual chapters of the EIS for more detail or further explanation.
- 5 It should also be noted that any and all conditions attached to any approval which An Bord Pleanála (the Board) may decide to grant, will be incorporated fully into the appointed contractors' scope of work. In this regard, an outline of the *Construction Environmental Management Plan* (CEMP) is presented in **Appendix 7.1, Volume 3B Appendices** of the EIS.

Table 11.1: Schedule of Commitments (Summary of Mitigation Measures from Chapters of the EIS)

Item CONSTR	Location (along the proposed route)	Mitigation Objective and Commitment <i>TER 7, VOLUME</i> 3B)	Mitigation Measure – NOTE ALL OTHER MITIGATION MEASURES ARE ALSO RELEVANT TO CONSTRUCTION M	Timing of Mitigation Measure //ITIGATION	Monitoring to Ensure Effectivenes s of Mitigation
1.1	General construction	Construction Management	In the event of approval being granted for the proposed development and prior to commencement of works, the contractor(s) which will be appointed by the Electricity Supply Board (ESB) will prepare a detailed <i>Construction Environmental Management Plan</i> (CEMP). An outline CEMP is included as, Appendix 7.1 , Volume 3B Appendices in the EIS. The scope of the final CEMP will detail <i>inter alia</i> the implementation and management of environmental controls and mitigation measures (detailed in the EIS and summarised below). Monitoring of the construction phase shall be carried out by an Environmental Officer, in association with an ecologist (Ecologist Clerk of Work (ECoW)) and archaeologist to ensure that all mitigation measures contained in the EIS and CEMP are implemented.	Pre-construction Phase	Yes. Detailed CEMP produced by contractor and agreed by ESB and subsequently with local and relevant prescribed authorities.
1.2	General construction	Construction Management – Client Engineer	A Client Engineer will be appointed and shall monitor and inspect the detailed designs, plant, material, and works including scheduling to ensure that these meet the requirements of the functional specification, designs and transmission standards.	Pre-construction Phase	Yes
1.3	General construction	Construction Management	Prior to construction, Notices and Schedules, as well as maps confirming the position of towers as approved by the Board, will be issued to landowners. EirGrid representatives will meet with landowners to deal with any queries the landowner may have following the issuing of the Notice.	Pre-construction Phase	None

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
1.4	General construction	Construction Management – working hours	Access to the site will be during daylight for all construction stages. It is not anticipated that construction works will be carried out on Sunday, or Bank Holidays or that any construction works will be carried out in hours of darkness.	Construction Phase	None
1.5	General construction	Landowner Liaison	Prior to commencing the works, discussions will take place between the appointed landowner agents and landowners to ensure awareness of the specific works that will take place pursuant to the proposed development. All landowners will be contacted prior to access being required on their lands and a date of commencement for the works will be provided to the landowner before any work begins. The detailed design of access routes and construction methodology to be used, chosen from the methodologies identified in the EIS, will be based on the condition of land at the time of construction and will be discussed with the landowner prior to the commencement of works.	Pre-construction Phase	None
1.6	General construction	Construction Management	Prior to commencement of construction a full traffic management plan will be produced and implemented.	Pre-construction Phase	Monitoring required during construction
1.7	General construction	Construction Management	A Construction and Waste Management Plan (forming part of the CEMP) will be implemented to minimise waste and ensure correct handling and disposal of construction waste streams.	Pre-construction Phase	None
1.8	General construction	Reinstatement	Once all the works are complete, the land used for temporary access routes and construction areas around the overhead structures will be reinstated as close as possible to their original condition.	Post Construction Phase	None

Item HUMAN HUMAN	Location (along the proposed route) BEINGS – POPUI BEINGS – LAND	Mitigation Objective and Commitment LATION & ECONOM	Mitigation Measure //IC (CHAPTERS 2 VOLUMES 3C and 3D) - No specific mitigation measures. Refer to other top VOLUMES 3C and 3D)	Timing of Mitigation Measure bics.	Monitoring to Ensure Effectivenes s of Mitigation
2.1	General construction	Construction Management	A method statement and work programme that shows the detailed phasing of work will be prepared prior to commencement of work.	Pre-construction Phase	None
2.2	General construction and operational maintenance works	Landowner Liaison	A wayleave agent will be appointed by the contractor to liaise with the landowners along the line route and ensure that their requirements for entry are met, so far as is possible. Land owners will be notified in advance of the commencement of any construction or maintenance works.	Construction Phase and Operation Phase	None
2.3	General construction	Comply with ESB / IFA agreement	All employees and contractors involved in the construction phase will receive adequate training – in particular in relation to issues relating to livestock safety and bio security on farms.	Construction Phase	None
2.4	General construction	Maintain access to agricultural land	The contractor will ensure that land owners have reasonable access to all parts of their farm during the construction phase.	Construction Phase	None
2.5	General construction	Minimise the risk of spreading	Disease protocols will be adhered to. The contractor will comply with any Department of Agriculture, Food & the Marine regulation pertaining to crops and livestock diseases.	Construction Phase	Yes

	Location	Mitigation		Timing	of	Monitoring
	(along the	Objective and		Mitigation		to Ensure
ltem	proposed	Commitment	Mitigation Measure	Measure		Effectivenes
	route)					s of
						Mitigation
		animal and crop				
		diseases				
2.6	N/A – general	Fencing of	Where required, appropriate fencing will be erected to exclude livestock from sites of	Construction		None
	construction	construction	construction.	Phase		
		areas to prevent				
		disturbance				
2.7	General	Minimise impact	In the unlikely event that rock breaking or pilling are required, owners of livestock in adjoining	Construction		None
	construction	of rock breaking	fields will be notified in advance.	Phase		
		or piling, if				
		required				
2.8	General	Minimise impacts	Where top soil is stripped back it will be replaced. All disturbed field surfaces will be re-instated.	Construction		None
	construction	to soil	It will be the construction policy to minimise non-tracked vehicular access to sites in wet weather.	Phase		
			Temporary access tracks (aluminium or panel tracks) will be laid in certain sites to avoid damage			
			to soil.			
			Vehicles which leak oil or fuel will not be allowed on construction or access sites. Any soil			
			contaminated by fuel or concrete spillage will be removed from the site and dealt with			
			appropriately as per legislative requirements.			

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
2.9	General construction	Minimise impacts to land drains	Affected land drains will be directed in a manner that maintains existing land drainage.	Construction Phase	None
2.10	General construction and operation phase	Ensure health and safety	ESB will provide safety information directly to all affected land owners e.g. <i>Guidelines for Safe</i> <i>Working near Overhead Electricity Lines in Agriculture</i> and <i>Code of Practice for Avoiding Danger</i> <i>from Overhead Electricity Lines</i> . These publications will enable farmers to fulfil their statutory requirements under Health and Safety Regulations.	Construction Phase and Operation Phase	None
2.11	General construction and operation phase	Minimise impact on livestock	Helicopter inspections will be announced in local newspapers and the Farmer's Journal.	Operation Phase	None
HUMAN	BEINGS – TOURI	SM (CHAPTERS 4	VOLUMES 3C and 3D) – No specific mitigation measures. Refer to other topics.		
HUMAN	BEINGS – EMF ((CHAPTERS 5 VOLU	MES 3C and 3D)		
3.1	MSA	Minimise EMF levels	The configuration of the phases (that is the spatial arrangement of the two sets of three vertically aligned electricity wires) on the existing double circuit towers will be optimised to ensure EMF levels are minimised.	Pre-construction	None

Item	Location (along the proposed route)	Mitigation Objective and Commitment APTERS 6 VOLUME	Mitigation Measure S 3C and 3D)	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
4.1	General	Minimising risks such as disturbance to wildlife and protection of water quality	 The key approach for minimising risks such as disturbance to wildlife and protection of water quality is the appointment of an appropriately experienced Ecological Clerk of Works (ECoW) on site during construction, to monitor the effectiveness of proposed mitigation measures in relation to known environmental effects and mitigation measures proposed in the EIS: The role of the ECoW will include: Supervision of construction works and ensure compliance with legislation; Monitoring habitats and species during the course of construction works and effectiveness of mitigation; Provision of advice regarding the avoidance and minimisation of potential disturbance to wildlife; Provide recommendations on appropriate responses / actions to site specific issues (e.g. identification of previously unrecorded breeding sites during construction works); and Liaison with NPWS, IFI and other prescribed authorities, when required. In addition to the construction phase, it is recommended that a site ecologist (ECoW) also be appointed during the pre-construction (landowner liaison stage) and post construction phases (up to 5 years) in particular to monitor mitigation measures regarding wintering birds. 	Construction Phase and initial Operation Phase (5 years plus)	Yes. Monitored by ECoW.

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing Mitigation Measure	of	Monitoring to Ensure Effectivenes s of Mitigation
4.2	General	Construction Management	A CEMP will be implemented for the construction phase of the project with respect to all mitigation.	Construction Phase		Yes. Monitored by Environmental Officer
4.3	General	Construction Management	Work method statements, which will incorporate all the mitigation measures identified in the EIS, will be developed by construction and site contractors, agreed with statutory authorities and ECoW (where appropriate), and implemented by construction crews for all construction activities.	Construction Phase		Yes. Monitored by Environmental Officer
4.4	General	Protection aquatic ecology	As required, temporary silt screens will be installed in drains /small streams deemed to be at possible risk of water pollutant discharge. Where possible, towers (access routes, stringing areas and indicative works areas) have been located away from sites of ecological importance. Furthermore, where possible, access to tower locations will be via existing tracks that are regularly used by farm machinery. Existing field access points (e.g. gaps / farm gates) to local roads will be used to avoid creating additional hedgerow gaps.	Construction Phase		Yes. Monitored by ECoW.
4.5	General	Minimise impacts to habitats	Semi natural habitats such as wetlands and hedgerows will be avoided.	Construction Phase		Yes. Monitored by ECoW.
4.6	General	Avoid the spread	Any invasive plant material noted on site will be removed off site and disposed of at appropriate	Construction		Yes.

	Location	Mitigation		Timing of	Monitoring
	(along the	Objective and		Mitigation	to Ensure
ltem	proposed	Commitment	Mitigation Measure	Measure	Effectivenes
	route)				s of
					Mitigation
		and introduction	licensed waste disposal facility. Any invasive species found to occur within 15m of working	Phase	Monitored by
		of invasive	areas will require its eradication to avoid the spread of invasive species, to ensure compliance		ECoW.
		species and	with the European Communities (Birds and Natural Habitats) Regulations 2011 (S.I. No. 477 of		
		noxious weeds	2011).		
4.7	General	Maintenance of	All landscaping / reconnection works must ensure that only native species are utilised. Non-	Construction	Yes. Monitored
		habitat	native species will be avoided.	Phase	by ECoW
		connectivity			
4.8	General	To minimise	Hedgerow, tree and scrub vegetation that are to be retained which are located in close proximity	Construction	Yes. Monitored
		impacts to	to working areas will be clearly marked and fenced off to avoid accidental damage during	Phase	by
		habitats	excavations and site preparation. No materials will be stored within 5 metres of hedgerows /		Environmental
			trees / scrub.		Officer
4.9	Towers	To minimise	The vegetation will be removed to ground level. Works will be implemented in a manner to	Construction	Yes. Monitored
	located at field	impacts to	minimise soil disturbance and compaction outside of the tower foundations. Post construction a	Phase	by ECoW.
	boundaries	habitats i.e. field	wooden fence will be installed around the tower base to prevent livestock access and replanting		
		boundaries	carried out with low growing woody species of local provenance including Blackthorn, Hawthorn		
		comprised of	and Hazel. This will allow re-establishment of the hedgerow in the gap where the tower is		
		hedgerows	located. It is expected that the hedgerows would be sufficiently robust within 5 years following		
			construction that fencing could be removed. Where required, disturbed areas of grassland will		
			be appropriately prepared and reseeded with a locally sourced grass mix, similar to that already		
			occurring within the surrounding fields. Reseeding works will be undertaken within 3 weeks of		

Item	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure construction works to avoid flushing of exposed soil downstream.	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
4.10	General	To minimise impacts to habitat i.e. trees	Tree cutting and lopping in proximity to conductors will be undertaken in a manner which minimises the requirement for extensive tree lopping. Large mature trees will be pollarded by qualified foresters / tree surgeons so as to retain as much of the treeline / linear habitat structure and in a manner which retains ground flora species and which does not kill the tree. The trimming regime will involve a scalloping or profiling effect which will minimise the effect on vegetation. Overall, it will not change the structure and ecological function of these linear woodland features, and will not measurably affect associated fauna post construction.	Construction Phase	Yes. Monitored by ECoW / Environmental Officer
4.11	General	To minimise impacts to habitats i.e. trees	Where construction work is required close to mature trees, the National Joint Utilities Group <i>Guidelines for the Planning Installation and Maintenance of Utility Services in Proximity to Trees</i> (NJUG 10) will be followed so as to minimise damage.	Construction Phase	Yes. Monitored by ECoW / Environmental Officer
4.12	General	To minimise impacts to breeding birds	Scrub, hedgerow or tree removal / trimming will be undertaken outside of the bird nesting period, which begins on March 1st and continues until August 31st, in order to protect nesting birds. All birds and their nesting places are protected under the <i>Irish Wildlife Act 1976</i> (as amended 2000).	Construction Phase	Yes. Monitored by ECoW / Environmental Officer

Item	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing c Mitigation Measure)f	Monitoring to Ensure Effectivenes s of Mitigation
4.13	General	Protection aquatic ecology	A drainage and sediment control plan will be implemented by contractors during site works. The plan will detail specific mitigation measures (taken from mitigation measures, outlined in Chapter 6 and 8 of this EIS) to address site specific issues.	Construction Phase		Yes. Monitored by Environmental Officer
4.14	General	Protection aquatic ecology	Potential impacts caused by spillages, drip and or spills during the construction phase will be reduced by the maintenance of an adequate supply of spill kits and hydrocarbon adsorbent packs at labelled stations at all working areas, with all vehicles on-site carrying spill kits. All personnel will be fully trained in the use of the equipment. Any used spill kits will be disposed of appropriately off-site.	Construction Phase		Yes. Monitored by Environmental Officer
4.15	General	Protection aquatic ecology	A 24 hour, 7 day per week Emergency Response protocol for leaks / spill of hydrocarbons and / or chemicals will be drawn up and implemented. This must be implemented in the unlikely event of an accidental spillage of chemicals, hydrocarbons or release of protection aquatic ecology sediment to the surface or ground water system.	Construction Phase		Yes. Monitored by Environmental Officer
4.16	General	Protection aquatic ecology and sensitive habitats	Excavated materials from construction works will be deposited within the works area where there is no significant risk of runoff into local watercourses.	Construction Phase		Yes. Monitored by ECoW / Environmental Officer

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing Mitigation Measure	of	Monitoring to Ensure Effectivenes s of Mitigation
4.17	General	Protection aquatic ecology water	As part of their environmental and works requirements, the contractor will establish a maintenance schedule and operational procedure / method statement for silt and pollution control measures during the construction period. This will be monitored for effectiveness by the contractor and ECoW.	Construction Phase		Yes. Monitored by Environmental Officer
4.18	General	Protection aquatic ecology Compliance with best practice	Oil, petrol and other fuel containers will be double-skinned and bunded to be able to contain 110% volume. Bund specification will conform to the current best practice for oil storage such as Enterprise Ireland's <i>Best Practice Guide BPGCS005 Oil Storage</i> Guidelines.	Construction Phase		Yes. Monitored by Environmental Officer
4.19	General	Protection aquatic ecology Compliance with best practice	Pouring of concrete will only take place in designated locations and concrete washings will be treated off site following current best practice guidelines including <i>Pollution Prevention Guidelines for Northern Ireland and Scotland</i> . Concrete washings will not be discharged to surface water and poured concrete will be allowed to cure for a minimum of 48 hours in the dry.	Construction Phase		Yes. Monitored by Environmental Officer
4.20	General	Protection aquatic ecology	Raw or uncured waste concrete or similar will be disposed of by removal to approved / licensed disposal site. It is noted that there will be a concrete truck wash out at the batching plant area. This washout will be directed to the three bay water recycler provided at this location.	Construction Phase		Yes. Monitored by Environmental Officer
4.21	General	Protection aquatic ecology	Water courses which have been identified as potentially at risk of pollution from construction activities (e.g., drains and smaller streams linked to the River Boyne and Blackwater) will have appropriately designed silt traps (based on drain and potential runoff characteristics identified)	Construction Phase		Yes. Monitored by Environmental

	Location	Mitigation		Timing of	Monitoring
	(along the	Objective and		Mitigation	to Ensure
ltem	proposed	Commitment	Mitigation Measure	Measure	Effectivenes
	route)				s of
					Mitigation
			installed in consultation with IFI (where necessary). Refer to Chapter 8 in Volumes 3C and 3D		Officer
			for details.		
4.22	General	Protection	Refuelling of machinery, will be carried out on level, hard surfaced designated areas where	Construction	Yes.
		aquatic ecology	possible, at least 20m from watercourses and drainage ditches. In the event that refuelling is	Phase	Monitored by
			required outside of this area, fuel will be transported in a mobile double skinned tank and a spill		Environmental
			tray will be employed during refuelling operations.		Officer
4.23	General	Protection	All machinery will be regularly maintained and checked for leaks. Services will not be	Construction	Yes.
		habitats and	undertaken within 50m of aquatic features, including dry drainage ditches. Servicing must be	Phase	Monitored by
		aquatic ecology	undertaken on level, hard surfaced designated areas where possible.		Environmental
					Officer
4.24	General –	Protection	Construction materials such as hydrocarbon, cement and grout will be stored in bunded areas or	Construction	Yes.
	Construction	aquatic ecology	silos which will be regularly inspected by the site manager.	Phase	Monitored by
					Environmental
					Officer
4.25	General –	Protection	Weather conditions will be taken into account when planning construction activities to minimise	Construction	Yes.
	construction	aquatic ecology	risk of extreme run off from works areas.	Phase	Monitored by
					Environmental
					Officer
4.26	General –	To minimise	Given the likely timescale (likely to be greater than 2 years) between any decision to grant	Pre-construction	Yes.

	Location	Mitigation		Timing	of	Monitoring
	(along the	Objective and		Mitigation		to Ensure
Item	proposed	Commitment	Mitigation Measure	Measure		Effectivenes
	route)					s of
						Mitigation
	construction	impacts to bats	planning approval and actual site clearance and construction, confirmatory bat surveys /	Phase	and	Monitored by
			monitoring of specific mature trees identified for felling will be undertaken by a bat specialist prior	Construction	I.	ECoW.
			to tree cutting. In order to proceed with the felling of trees that may be identified as bat roosts, it	Phase		
			will be necessary to acquire a derogation licence from NPWS. NRA, (2006) Guidance in relation			
			to tree felling and hedgerow removal will be followed throughout the site clearance phase of the			
			proposed development.			
4.07	Conoral	To minimino				Vac
4.27	General –	To minimise	Pre-construction surveys to confirm presence / absence of Otter breeding sites in relation to the	Pre-construc	tion .	Yes.
	construction	impacts to Otters	conditions which have been evaluated this EIS will be undertaken at watercourses and adjacent	Phase	and	Monitored by
			habitats that occur in close proximity to tower locations and tree felling areas.	Construction		ECOVV.
			Details of the pre-construction verification / monitoring methodology and the approach to be	Phase		
			taken will be outlined in the CEMP that is to be drawn up for the construction phase of the			
			development with reference to relevant guidance documents. No direct impacts are expected to			
			arise as works will require an agreed method statement and be monitored by the ECoW.			
4.28	General –	To minimise	Given the likely timescale between any decision to grant planning approval and the	Pre-construc	tion	Yes.
	construction.	impacts to	commencement of actual site clearance and construction, pre-construction surveys to confirm	Phase	and	Monitored by
		Kingfishers	the conditions which have been evaluated will be undertaken at watercourses and adjacent	Construction	i	ECoW.
		5	habitats (linked to the River Boyne and Blackwater) that occur in close proximity to tower	Phase		
			locations and tree felling areas to confirm presence / absence of Kingfisher breeding sites.			

Item	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
4.29	General – construction	To minimise impacts to Badgers	Surveys for Badger setts will be conducted at woody vegetation required for cutting. This is required to confirm that site clearance activities are in line with the receiving environment considered in this EIS. A buffer zone will be established around any known Badger setts through the erection of temporary posts and wires with "no entry" signs erected. Any works within 50m of a sett will require a licence from NPWS. No direct impacts are expected to arise as works will require an agreed method statement and be monitored by the ECoW.	Pre-construction Phase and Construction Phase	Yes. Monitored by ECoW.
4.30	General – Operational Phase	To minimise impacts on Whooper Swans	The key operational impacts identified are potential collision risks to Whooper swans. Mitigation by avoidance of feeding and roosting sites has been implemented as far as possible in the route selection for the alignment. Flight Diverters (Swan Flight Diverter markers constructed from high-impact grey PVC (UV stabilised) fitted at approximately 5m apart along each earthwire, are proposed at specific locations identified in the EIS. This line marking is proposed for the earth wire to increase visibility of the earth wire to flying birds.	Operational	Yes. Annually for 10 years.
4.31	General	Hedgerow re- growth and fence maintenance	Where poor or no hedgerow re-growth has occurred, replanting with similar native hedgerow species will be carried out so as to ensure linear habitats are retained / re-established. If new fencing is required or maintenance then this will be agreed and implemented with the landowner.	Post Construction	Yes. 2 years post construction.
4.32	General		Monitoring will be undertaken to determine the effectiveness of proposed flight diverter mitigation.	Post construction	Yes. Annually for 10 years.

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing Mitigation Measure	of	Monitoring to Ensure Effectivenes s of Mitigation
4.33	General – During maintenance works	During maintenance works, consideration will be given to ensure ongoing protection of water quality.	Depending on the nature of the proposed maintenance works; there may be a requirement for risk assessments of potential impacts to surface waters and appropriate mitigation will be implemented where a risk is identified.	Post construction		Yes. Ongoing (depending works requirements)
SOILS, G	EOLOGY AND H	YDROGEOLOGY ((CHAPTERS 7 OF VOLUMES 3C AND 3D)			
5.1	Lemgare CGS, Altmush CGS, Galtrim CGS and the Boyne CGS	To mitigate potential impacts	 The mitigation measures agreed with the GSI for site investigation works / construction of the towers include the following; Continued consultation with the GSI; Limiting excavation by only excavating the required footprint; Maintaining an adequate distance from Lemgare pNHA, and Altmush Stream; and The GSI will be notified about any significant new section / feature that is exposed within the tower footprint. 	Construction Phase		None
5.2	General	Effective treatment of spoil material	Excavated soil and subsoil will be stored adjacent to the excavation area. Excavated material will be reused in situ where possible. In the event no material is suitable / wanted for reuse by landowners, subsoil will be disposed of in accordance with all applicable legislative requirements.	Construction Phase		None

Item	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing Mitigation Measure	of	Monitoring to Ensure Effectivenes s of Mitigation
5.3	General	Dealing with unexpected contaminated land	All excavated materials will be visually assessed for signs of possible contamination such as staining or strong odours. Should it be determined that any of the soil excavated is contaminated, this will be dealt with appropriately as per all applicable legislative requirements.	Construction Phase		Monitoring required during construction
5.4	General	To minimise impact from material spillages	All oils and fuels used during construction will be stored on temporary proprietary bunded surface (i.e. contained bunded plastic surface). These will be moved to each tower location as construction progresses. Refuelling of construction vehicles and the addition of hydraulic oils or lubricants to vehicles will take place away from surface water gullies or drains. No refuelling will be allowed within 50m of a stream / river. Spill kits and hydrocarbon absorbent packs will be stored in this area and operators will be fully trained in the use of this equipment.	Construction Phase		Monitoring required during construction
5.5	General	Minimise impacts to soils	Controlling working practices by, for example, minimising land take, avoiding repetitive handling of soils, minimising vehicle movements off road and limiting the size of stockpiles will reduce the compaction and erosion of material. Soils will be reinstated at the towers and along the temporary access route.	Construction Phase		None
5.6	Tower Locations	Minimise impacts to existing wells and boreholes	Where it is necessary to dewater to construct the tower foundations in close proximity of wells, monitoring will be carried out of wells within 100m of the tower locations.	Construction Phase		Monitoring required during construction
5.7	General – construction	Minimise impacts to existing wells	Water pumped from the excavations may contain suspended solids. Settlement may be required to reduce the suspended solids concentrations to protect the quality of the receiving water	Construction Phase		Monitoring required during

	Location	Mitigation		Timing	of	Monitoring
	(along the	Objective and		Mitigation		to Ensure
ltem	proposed	Commitment	Mitigation Measure	Measure		Effectivenes
	route)					s of
						Mitigation
		and boreholes.	system. Settlement will be undertaken by a standard water filtration system to control the			construction
		Protection of the	amount of sediment in surface water runoff.			
		quality of the	Direct discharge to streams or rivers will not be permitted.			
		receiving water				
		system.				
5.8		Tara Mines	Liaison will be undertaken with Tara Mines during construction / operation phase to ensure no			
			conflicts arise.			
WATER	CHAPTERS 8 OF	VOLUMES 3C AN	D 3D)			
6.1	General	To prevent water	All works will be undertaken with due regard to the guidance contained within CIRIA Document	Construction		None
	Construction	pollution	C741 2015 Environmental Good Practice on Site.	Phase		
	Phase					
6.2	Where tree	To prevent water	Consultation will be undertaken with Inland Fisheries Ireland (IFI) and NPWS before	Construction		Monitoring
	felling may be	pollution during	commencing felling operations in areas of importance to fisheries and wildlife. Sediment traps	Phase		required during
	required	felling of forestry	will be installed prior to felling and maintained on a daily basis throughout felling operations.			Construction
			Trees will be felled away from the aquatic zone. Machine extraction will not occur in the riparian			Phase.
			zone.			
			On sites where risk of erosion is high (steep slopes and / or adjacent to rivers), brash mats will			
			be used to avoid soil damage, erosion and sedimentation. Brash mat renewal will take place			
			when they become heavily used and worn. Provision will be made for brash mats along all off-			

Item	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure road routes, to protect the soil from compaction and rutting. Felling will not occur during periods of high rainfall to prevent runoff. No refuelling or machinery maintenance will occur within 50m of an aquatic zone. Timber will be stored on dry areas away from the riparian zones. The forest felling effects of the overhead transmission line will be short term during construction phase.	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
6.3	Near watercourses (including the River Boyne and Blackwater)	Protection of Watercourses	Silt barrier / silt curtains will be used where towers or works are undertaken near watercourses. In relation to the River Boyne and Blackwater the towers are located a minimum of 60m and 100m respectively from these rivers. However, notwithstanding this distance, it is proposed to use silt barriers / curtains for tower construction near those rivers.	Construction Phase	Monitoring required during construction
6.4	General Construction	Minimise impacts on soils	Stockpiles will be graded to a <1:4 profile. Topsoil and subsoils will be stored separately. Stockpiles of mineral soils and peat will be <2m and <1m respectively. Geotechnical supervision in combination with monitoring will ensure that any peat encountered is stored in suitable areas.	Construction Phase	Monitoring required during construction
6.5	Near watercourses	Protection of Watercourses	Where it would be necessary to dewater to construct the tower foundations precautions will be taken to ensure there is no adverse effects on nearby watercourses including the resultant water being filtered before discharge.	Construction Phase	Yes on the discharge water quality.
6.6	Near watercourses	Protection of Watercourses	 Precautions will be taken to avoid spillages. These include: Use of secondary containment, e.g. bunds around oil storage tanks; Use of drip trays around mobile plant; 	Construction Phase	Yes during construction

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure Supervising all deliveries and refuelling activities; and	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
			Designating and using specific impermeable refuelling areas isolated from surface water drains.		
6.7	Near watercourses	Protection of Watercourses	With regard to on site storage facilities and activities, any raw materials and fuels, will be stored within bunded areas, if appropriate to guard against potential accidental spills or leakages. All equipment and machinery will have regular checking for leakages and quality of performance.	Construction Phase	Yes - equipment
6.8	Near watercourses	Protection of Watercourses	All site personnel will be trained and aware of the appropriate action in the event of an emergency, such as the spillage of potentially polluting substances. Spill kits are retained to ensure that all spillages or leakages are dealt with immediately and staff are trained in their proper use. Any servicing of vehicles will be confined to designated and suitably protected areas. Any pollution incident or spill will be reported to the regulator and remediated to their original condition.	Construction Phase	Ongoing monitoring required during construction
6.9	Near watercourses	Protection of Watercourses	Wash down and washout of concrete transporting vehicles will not be permitted at the location of construction. Such wash down and washout activities will take place at an appropriate facility offsite.	Construction Phase	Ongoing monitoring required during construction
6.10	Temporary Access Tracks and Tower	Protection of watercourses	At certain locations where very poor soft ground is encountered, Type 2 temporary access track may have to be laid.	Construction Phase	None

Item	Location (along the proposed route) Foundations	Mitigation Objective and Commitment	Mitigation Measure Generally temporary access tracks use rubber or aluminium road panels. Temporary access tracks will be up to 4m wide and routed away from drains where possible. In sensitive locations silt barriers will be used to prevent direct runoff to local watercourses.	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
6.11	Temporary Access Routes and Tower Foundations	Protection of water quality	Preventative measures will ensure that input suspended solids concentrations will be minimised at source. This will be achieved by ensuring that all silt / clay and topsoil is properly stored during the construction phase of the development.	Construction Phase	Ongoing Monitoring required during construction.
6.12	Construction- Temporary Access Routes and Tower Foundations	Protection of Water Quality	Water quality monitoring will be undertaken prior to the commencement of construction to confirm baseline data and ensure there is no deterioration in water quality. This will be targeted on watercourses considered to be at a higher risk of pollution (i.e. towers where there are watercourses within 20m of the construction works). Water quality monitoring will include daily inspection of adjacent watercourses.	Prior to and during the Construction Phase	Ongoing Monitoring, observing and sampling required during construction.
6.13	Construction- Material Storage Yard	Protection of Water Quality	The surface water drainage system at the construction material storage yard will take into account the recommendations of the CIRIA C468 and utilises SuDs (sustainable urban drainage) devices where appropriate. Runoff from site will be limited to greenfield runoff rates. Runoff will pass through a silt trap, oil interceptor and settlement lagoon before being discharge to the	Prior to and during the Construction Phase	Ongoing observing and sampling required during

	Location	Mitigation		Timing of	Monitoring
	(along the	Objective and		Mitigation	to Ensure
Item	proposed	Commitment	Mitigation Measure	Measure	Effectivenes
	route)				s of
					Mitigation
			surface water.		construction
6.14	Woodland Substation	Protection of Water Quality	Implementing the design standards of the GDSDS, the surface water drainage system at Woodland takes into account the recommendations of the GDSDS and utilises SuDs (sustainable urban drainage) devices where appropriate. Runoff from hardstand areas at Woodland Substation will be limited to greenfield runoff rates.	Prior to and during the Construction Phase	Ongoing observation required
AIR – NC	DISE & VIBRATIO	N (CHAPTER 9 OF	VOLUMES 3C AND 3D)		
7.1	Construction Phase	To ensure compliance with appropriate European Standards	The contractor appointed will have to ensure that all plant items used during the construction phase will comply with standards outlined in European Communities (<i>Construction Plant and Equipment</i>) (<i>Permissible Noise Levels</i>) Regulations (1990). The contractor will make reference to BS5228: Noise Control on Construction and Open Sites (2009), which offers detailed guidance on the control of noise from construction activities.	Construction Phase	Ongoing monitoring required during construction.
7.2	Construction Phase	To ensure the adoption of appropriate practices during construction	 It is proposed that various practices be adopted including: Night time working will typically not occur; however, there may be a necessity to continue to operate generator, pumps or other equivalent machinery at a number of locations, where the digging of foundations and erection of towers may cause activity to remain in one location for a longer period of time; On these infrequent occasions screening and enclosures can be utilised. For maximum effectiveness, a screen should be positioned as close as possible to either the noise source or receiver. The screen should be constructed of material with a mass of > 7kg/m2 and should have no gaps or joints in the barrier material. This can be used to 	Construction Phase	Ongoing monitoring required during construction.

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	 Mitigation Measure limit noise impact to 45dB (A) Leq (BS 5228 acceptable night time level) at any noise sensitive receptors, if required by agreement with the local authority; Appoint a site representative responsible for matters relating to noise; and 	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
			• Establishing channels of communication between the contractor / developer, local authority and resident i.e. for notification of requirement of night works, should this be required.		
7.3	Construction Phase	Use of appropriate noise control measures during construction	 Furthermore, it is envisaged that a variety of practicable noise control measures will be employed, these may include: Selection of plant with low inherent potential for generation of noise and / or vibration; Erection of temporary barriers around items such as generators or high duty compressors. For maximum effectiveness, a barrier should be positioned as close as possible to either the noise source or receiver. The barrier should be constructed of material with a mass of > 7kg/m2 and should have no gaps or joints in the barrier material, As a rough guide, the length of a barrier should be 5 times greater than its height. A shorter barrier should be bent around the noise source, to ensure no part of the noise source is visible from the receiving location; and Positioning of noisy plant as far away from sensitive receptors, as permitted by site constraints. 	Construction Phase	Ongoing monitoring required during construction
7.4	Construction	Use of appropriate	Any construction works that have the potential to cause vibration at sensitive receptors will be carried out in accordance with the limit values as set out in the EIS.	Construction	Ongoing monitoring

Item	Location (along the proposed route) Phase	Mitigation Objective and Commitment construction phase vibration mitigation	Mitigation Measure	TimingofMitigationMeasurePhase	MonitoringtoEnsureEffectivenessofMitigationrequired duringconstruction
7.5	Operational Phase	Use of appropriate operational phase noise mitigation measures	It is not expected that noise arising from the proposed development will cause significant noise impact. Corona noise may be audible under certain weather conditions and in close proximity to the line. Corona noise is caused predominantly by items of transmission line hardware, other than conductors, e.g. clamps, and can be mitigated by replacement of individual items of hardware. Aeolian noise very rarely occurs on 400 kV lines and is not expected to arise on the proposed development. Recommended mitigation measures for Aeolian noise include the fitting of air flow spoilers on conductors and the fitting of composite insulators.	Operational Phase	Ongoing monitoring required during construction
7.6	Unknown at time of writing	To minimise noise impact to sensitive receptors	Use of temporary noise barriers around rock breaking activity if noise impact to sensitive receptors is deemed likely.	For duration of localised rock breaking	Noise monitoring of closest sensitive receptor or representative location.

ltem AIR - QU	Location (along the proposed route) ALITY AND CLIM	Mitigation Objective and Commitment IATE (CHAPTER 10	Mitigation Measure OF VOLUME 3C AND 3D)	Timing of Mitigation Measure	Monitoring to Ensure Effectivenes s of Mitigation
8.1	General Development wide – construction phase	Protection of properties from significant dust nuisance	 Mitigation measures will be employed on a site-specific basis based on a review of the construction activities involved and their proximity to nearby receptors in each location. The site specific mitigation measures will be employed to ensure that properties within 50m of the construction locations will not be subject to significant dust nuisance. The types of mitigation measures include the following: A water bowser will be available to spray work areas, especially during periods of excavations works coinciding with dry periods of weather, in order to suppress dust migration; All loads which could cause a dust nuisance will be covered to minimise the potential for fugitive emissions; and Stockpiled material during the construction phase will be sprayed during periods of dry weather in order to suppress dust migration from the site. 	Construction Phase	Ongoing monitoring required during construction (in the context the CEMP).
LANDSC	APE CHAPTER 1	1 OF VOLUMES 30	: AND 3D)		
9.1	Development wide – construction phase	Minimise physical landscape effects on vegetation	The key mitigation measures described in the Flora and Fauna section (section 4 of this table) will serve to minimise physical landscape effects arising from disturbance to vegetation and soils. The key mitigation measures as described in the Flora and Fauna section in relation to landscape effects are; using existing access routes and gaps in hedgerows, reinstatement of hedgerows and ground vegetation (with similar or better quality planting), protection of retained	Construction and Operational Phase	Ongoing monitoring required by a qualified Landscape

	Location	Mitigation		Timing	of	Mon	itoring	ļ
	(along the	Objective and		Mitigation		to	Ensu	re
Item	proposed	Commitment	Mitigation Measure	Measure		Effe	ctivene	es
	route)					s		of
						Mitiç	jation	
			vegetation, sensitive vegetation pruning methods including pollarding of mature trees to retain			Archi	tect	
			hedgerow lines, monitoring of vegetation establishment over 24 months, and replanting in the			durin	g	
			event of any reinstatement failures. Hedgerows will be maintained to ensure no vegetation is tall			const	ruction	
			enough to potentially interfere with the conductors.			and	inspecti	on
						of	reinstate	ed
						planti	ing over	r a
						24	mor	nth
						perio	d	
9.2	Development	Minimise	The mitigation measures in section 5 – Soils, Geology and Hydrogeology will serve to minimise	Construction		Ongc	bing	
	wide –	physical	physical landscape effects on soil and subsequent vegetation establishment. The key mitigation	and Operatior	nal	moni	toring	
	construction	landscape	measures as described in this section in relation to landscape effects are; correct removal,	Phase		requi	red by	а
	phase	effects on soil	storage and reinstatement of subsoil and topsoil, avoidance of soil compaction and removal and			qualif	iied	
			disposal of soil where not required for reinstatement.			Land	scape	
						Archi	tect	
						durin	g	
						const	ruction	
						and i	inspectio	on
						of e	arthwor	'ks
						over	a :	24
						mont	n period	1
9.3	Blackwater	To mitigate	Micro mitigation is possible through the retention or enhancement of trees and hedgerows in key	Construction		Ongc	oing	

	Location	Mitigation		Timing	of	Moni	itoring
	(along the	Objective and		Mitigation		to	Ensure
Item	proposed	Commitment	Mitigation Measure	Measure		Effec	tivenes
	route)					s	of
						Mitig	jation
	Valley	landscape	locations	phase		monit	oring
		character and				requir	red by a
		visual impact in a				qualif	ied
		valley landscape				Lands	scape
						Archit	tect
						during	g
						const	ruction
						and	
						inspe	ction of
						reinst	ated
						planti	ng over
						a 24	month
						period	b
9.4	Brittas Estate	To reduce the	The clearance of existing vegetation will be minimised in this area and in consultation with the	Construction		Ongo	ing
		potential impact	landowner appropriate screening could be planted on either side of the entrance road and other	phase		monit	orina
		on a historic	locations within the estate to limit the views towards the proposed development.			requir	red by a
		designed				qualif	ied
		landscape				Lands	scape
						Archit	tect
						during	g
1						const	ruction

	Location	Mitigation		Timing	of	Monitoring
	(along the	Objective and		Mitigation		to Ensure
Item	proposed	Commitment	Mitigation Measure	Measure		Effectivenes
	route)					s of
						Mitigation
						of reinstated
						planting over a
						24 month
						period
9.5	Boyne Valley	To mitigate	Micro mitigation is possible through the retention or enhancement of trees and hedgerows in key	Construction		Ongoing
		landscape	locations.	phase		monitoring
		character and				required by a
		visual impact in a				qualified
		valley landscape,				Landscape
		on a protected				Architect
		viewpoint and on				during
		a view from				construction
		Bective Abbey				and inspection
						of reinstated
						planting over a
						24 month
						period.=
MATERIA	AL ASSETS – GE	NERAL (CHAPTER	12 OF VOLUMES 3C AND 3D)			
10.1	Development	To minimise	A pre-construction survey for utilities such as gas, electricity, telecoms etc. will be undertaken	Prior	to	None

Item	Location (along the proposed route) wide - General	Mitigation Objective and Commitment impacts on electricity, telecoms & gas	Mitigation Measure during the construction phase, including ground investigations, to confirm the conditions which have been encountered in the EIS.	Timing Mitigation Measure construction	of	Monitoring to Ensure Effectivenes s of Mitigation
10.2	At the crossing of OHL and telecoms services is necessary	To minimise disruption to existing electricity & telecoms services during construction	Certain obstacles along a straight have to be guarded such as road / railway crossings and other transmission or distribution lines by way of temporary guard poles.	Construction phase		None
10.3	Development Wide General – Construction Phase	To comply with Best Practice Guidelines on the Preparation of Waste Management Plans for Construction & Demolition Projects (2006)	Waste management will be carried out in accordance with <i>Best Practice Guidelines on the</i> <i>Preparation of Waste Management Plans for Construction & Demolition Projects</i> (2006) produced by the Department of Environment, Community and Local Government. A Construction Waste Management Plan (which will form part of the CEMP) will be implemented to minimise waste and ensure correct handling and disposal of construction waste streams. The key principles underlying the plan will be to minimise waste generation and to segregate waste at source.	Construction Phase		None

	Location	Mitigation		Timing	of	Monitoring
	(along the	Objective and		Mitigation		to Ensure
Item	proposed	Commitment	Mitigation Measure	Measure		Effectivenes
	route)					s of
						Mitigation
10.4	Development wide General – Operational Phase	To ensure the appropriate recovery / disposal of operational waste (such as packaging etc.) arising from occasional maintenance activities	A negligible amount of light waste generated in the operational phase of the proposed development arising in maintenance and cleaning operations, replacement of lighting units as required, oils arising from occasional maintenance activities and packaging materials will be removed off site by licensed contractors for appropriate recovery / disposal at licensed facilities.	Operational Phase		Monitoring required during Operational Phase (during maintenance)
10.5	Development wide General - Operational Phase	To ensure safe aviation activity at Trim Airfield	Landing aircraft using Runway 28 would need to be visually aware of where the towers are located and a formal approach procedure of <i>'visual contact of towers / cables required before starting field approach'</i> should be introduced. The OHLs will be below the obstacle limitation surfaces for Trim Airfield, but making them more conspicuous through the fitting of marker spheres should be considered between Towers 355 and 357. The landscape consultants propose fitting 60cm diameter spheres at 30 metre intervals alternating orange and white	Operational Phase		None

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing Mitigation Measure	of	MonitoringtoEnsureEffectivenessofMitigation
10.6	Development wide General - Operational Phase	To ensure safe Ballooning activity in the vicinity of the proposed development	The potential presence of the proposed development will have to be considered by the balloon pilots as part of their flight planning. The power line will have to be considered by the balloon pilots for launching and landing, but as stated by the IAA balloon pilots are allowed fly over power lines.	Operational Phase		None
MATERIA	AL ASSETS – TR	AFFIC (CHAPTER 1	3 OF VOLUMES 3C AND 3D)			
11.1	Development Wide General – Construction Phase	The preparation and implementation of a Construction Traffic Management Plan. The objective of this plan will be to minimise the impact caused by the construction stage of the	 It shall be a requirement of the contractor appointed to construct the project to prepare a detailed Construction Traffic Management Plan prior to the commencement of construction operations. As a minimum, the mitigation measures should include the following: Development of a detailed construction programme aimed at minimising peaks in traffic volumes on specific roads; Continuous monitoring of the roads used for construction; Identification of traffic management measures with respect to road closures; Measures for continuous liaison with local authorities and other relevant stakeholders; Identification of traffic management measures at site entrances; and Measures for accommodating emergency response vehicles along the haul routes. 	Prior to t commenceme of t construction phase. Continuous updating throughout t construction stage.	he nt he	Monitoring of roads used during construction stage required.

Item	Location (along the proposed route)	Mitigation Objective and Commitment project.	Mitigation Measure	Timing Mitigation Measure	of	Monitoring to Ensure Effectivenes s of Mitigation		
CULTURAL HERITAGE (CHAPTER 14 OF VOLUMES 3C AND 3D)								
12.1	General – Construction	To mitigate against potential impacts during the construction phase	 In areas where it has been identified that there is the potential that archaeological, architectural or cultural heritage site, structures, monuments or features could be impacted on during the construction phase, one or more of the following mitigations measures have been recommended in the EIS: Archaeological monitoring – in areas of moderate archaeological potential, excavations associated with construction works and / or facilitating access to the construction site and / or stringing areas will be monitored by a suitably qualified archaeologist. In the event that archaeological deposits are discovered, work in the area will cease immediately and the archaeologist will liaise with the National Monuments Service of the DAHG and the National Museum of Ireland. Archaeological testing – best practice in areas of high archaeological potential demands caution, to ensure that archaeological deposits are identified as early as possible, thereby ensuring that any loss from the archaeological record is minimised. Under a monitoring remit, an archaeologist will observe normal construction works, usually undertaken with a toothed excavator bucket. During archaeological testing a 	Prior to construction phase a throughout construction	and	Ongoing implementatio n of archaeological monitoring, archaeological testing and other recommended mitigation strategies.		

ltem	Location (along the proposed	Mitigation Objective and Commitment	Mitigation Measure	Timing Mitigation Measure	of	Mor to Effe	nitoring Ensur ectivene	re Is of
						Miti	gation	
			 licensed eligible archaeologist supervises excavations undertaken with a toothless grading bucket, under licence to the National Monuments Service of the DAHG, thereby ensuring the early identification of archaeological deposits and minimal loss to the archaeological record. Undertaking this confirmatory surveying will ensure that sufficient time can be allowed within the construction schedule for the excavation of any archaeological deposits discovered. Demarcation – where it has been identified that there is the potential that an archaeological, architectural or cultural heritage site, structure or monument or could be impacted upon in gaining access to construct the proposed development then demarcation has been recommended to prevent any inadvertent damage. A suitably qualified archaeologist will access the site prior to the commencement of construction works in the area and demarcate a buffer around the site, structure or monument that will remain in place throughout any construction works in the vicinity. Confirmation of temporary access routes – at a number of locations confirmation of the proposed construction temporary access routes will take place, in consultation with the construction team and prior to commencement of construction works, to ensure that the surviving historic fabric of buildings is not impacted on in gaining access for construction activities. To this end the temporary access routes may be revised, sensitive features highlighted and demarcated or different construction machinery or methods (as identified in the EIS) may be used that can access the site without impacting on the historic fabric. 					

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure have be to be trimmed in the vicinity of upstanding remains of buildings that are indicated on historic mapping. This work will be monitored by a suitably qualified	Timing Mitigation Measure	of	Monitoring to Ensure Effectivenes s of Mitigation
			archaeologist to ensure that the historic fabric of the buildings is not impacted upon by the works.			
12.2	Development Wide General – Construction Phase	To ensure the implementation of the mitigation measures during the construction phase	It is recommended that a suitably qualified cultural heritage consultancy / consultant be appointed to oversee the effective implementation of the mitigation measures recommended in this EIS for the construction phase of the proposed development. The consultancy / consultant should maintain continuing liaison with the National Monuments Service of the DAHG throughout the construction phase of the development.	Construction phase		None
12.3	Development wide general	To comply with the Code of Practice Between the National Monuments Service of the DoEHLG (now DAHG) and ESB Networks (2009)	In line with the Code of Practice Between the National Monuments Service of the DoEHLG (now DAHG) and ESB Networks (2009), a project archaeologist will be appointed to oversee the effective implementation of the recommended archaeological mitigation during the proposed works.	Construction phase		None

ltem	Location (along the proposed route)	Mitigation Objective and Commitment	Mitigation Measure	Timing Mitigation Measure	of	MonitoringtoEnsureEffectivenessofMitigation
12.4	Teltown Zone of Archaeological Amenity (ZAA)	To mitigate impact on Teltown ZAA	 The following mitigation strategies have been formulated for the Teltown ZAA: Test pits for other environmental and engineering disciplines will be subject to archaeological monitoring by a suitably qualified archaeologist; Archaeological testing – best practice in areas of high archaeological potential demands caution, to ensure that archaeological deposits are identified as early as possible, thereby ensuring that any loss from the archaeological record is minimised. During archaeological testing a licence eligible archaeologist supervises excavations undertaken with a toothless grading bucket, under licence to the National Monuments Service of the DAHG, thereby ensuring the early identification of archaeological deposits and minimal loss to the archaeological deposits discovered. All tower and guarding locations within the Teltown ZAA will be subject to a regime of pre-construction archaeological testing under licence to the National Monuments Service of the DAHG. The National Monuments Service of the DAHG. The National Monuments Service of the DAHG. During the construction phase a suitably qualified archaeologist will monitor site access and construction works. Ensure that where appropriate low ground pressure vehicles or panel tracks are used to minimise ground disturbance. Type 3 temporary access tracks will not be used within the Teltown ZAA. Low ground pressure vehicles and Type 2 	Construction phase		None

	Location	Mitigation		Timing (of	Monitoring
	(along the	Objective and		Mitigation		to Ensure
Item	proposed	Commitment	Mitigation Measure	Measure		Effectivenes
	route)					s of
						Mitigation
			temporary access tracks will be used to minimise ground disturbance. The Derrick Pole			
			Methodology (see Volume 3B Section 7.3.4.3.2 of the EIS) will be used for tower			
			construction; mobile cranes will not be used; and			
			A suitably qualified archaeologist will monitor access and construction of any guarding			
			areas required within the ZAA.			
12.5	Various	To mitigate	Refer to summary of mitigation measures as listed in Chapter 14, Volumes 3C and Volume 3D.	Construction		Monitoring
	Locations	against potential		phase		required during
		impacts during				construction
		the construction				
		phase of tower				
		locations,				
		guarding areas				
		and 110kV line				
		crossings, and				
		associated				
		temporary				
		access tracks.				
12.6	Brittas House	To reduce the	The clearance of existing vegetation will be minimised in this area and in consultation with the	Construction		Monitoring
	(RPS No.	potential impact	landowner appropriate screening will be planted on either side of the lane to limit the views	phase		required during
	MH005-105)	on the setting of	towards the proposed development.			construction
		entrance avenue				

	Location	Mitigation		Timing of	Monitoring
	(along the	Objective and		Mitigation	to Ensure
Item	proposed	Commitment	Mitigation Measure	Measure	Effectivenes
	route)				s of
					Mitigation
		to Brittas House			
		(RPS No.			
		MH005-105), Co			
		Meath			
12.7	Development	To mitigate	Potential impacts on archaeological, architectural or cultural heritage sites, monuments,	During	Ongoing
	wide –	against potential	structures or features during maintenance works that may be required during the operational	maintenance or	monitoring
	operational	impacts during	phase of the proposed development are best mitigated through ongoing liaison with the National	upgrade works	required during
		the operational	Monuments Service and the Architectural Heritage Advisory Unit at the DAHG and local heritage	that may be	the operational
		phase	and conservation officers within the County Councils.	required during	phase (during
				the operational	upgrading /
				phase	maintenance
					works).