



REMEDIAL ENVIRONMENTAL IMPACT ASSESSMENT Report (rEIAR)

Volume II: Main Report

Ros an Mhíl Deep Water Quay

Department of Agriculture, Food and the Marine

October 2025

Project No.	Doc. No.	Rev.	Date	Prepared By	Checked By	Approved By	Acceptance Code / Status
24984	6002	A	29/10/2025	MT	MT	CF	Final

MWP, Engineering and Environmental Consultants
Address: Reen Point, Blennerville, Tralee, Co. Kerry, V92 X2TK, Ireland
www.mwp.ie



Disclaimer: This Report, and the information contained in this Report, is Private and Confidential and is intended solely for the use of the individual or entity to which it is addressed (the “Recipient”). The Report is provided strictly on the basis of the terms and conditions contained within the Appointment between MWP and the Recipient. If you are not the Recipient you must not disclose, distribute, copy, print or rely on this Report (unless in accordance with a submission to the planning authority). MWP have prepared this Report for the Recipient using all the reasonable skill and care to be expected of an Engineering and Environmental Consultancy and MWP do not accept any responsibility or liability whatsoever for the use of this Report by any party for any purpose other than that for which the Report has been prepared and provided to the Recipient.

Contents

Chapter 1 Introduction

1.	Introduction	1-1
1.1	The Applicant	1-2
1.2	Application Site	1-2
1.3	Application Background	1-3
1.4	Remedial Environmental Impact Assessment	1-5
1.4.1	Remedial Environmental Impact Assessment Report (rEIAR).....	1-5
1.4.2	Remedial EIAR Content	1-5
1.4.3	Legislation and Guidelines	1-6
1.4.4	Assessment of Likely Significant Effects.....	1-6
1.4.5	Scoping for Potential Cumulative Effects.....	1-9
1.4.6	Structure of the Remedial EIAR (rEIAR)	1-13
1.5	Consultation	1-14
1.5.1.1	Meetings.....	1-14
1.5.1.2	Written Communication	1-14
1.6	Project Team	1-17
1.7	Difficulties Encountered	1-21
1.8	Note on Quotation.....	1-21
1.9	Note on Drawings and Graphics	1-21
1.10	References	1-21

Chapter 2 Project Description

2.	Project Description	2-1
2.1	Introduction	2-1
2.2	Development Site and Location	2-1
2.3	Project Summary	2-3
2.3.1	Permitted Development (PI Ref 17/967)	2-3
2.3.2	Overview of Works undertaken between January 2023 and 10 July 2023.....	2-6
2.3.3	Overview of Works undertaken between 11 th July 2023 and 20 th May 2024	2-7
2.3.4	Future Works required for completion of Deep Water Quay.....	2-9

2.4	Description of Construction Activities	2-10
2.4.1	Reclamation:.....	2-10
2.4.2	Temporary protective Rock Berm	2-10
2.4.3	Drilling and Blasting.....	2-11
2.4.4	Dredging	2-16
2.4.5	Construction of the Quay wall Foundations	2-17
2.4.6	Mobilisation and Construction Compound and Facilities	2-19
2.4.7	Concrete Batching Plant	2-20
2.4.8	Material Quantities for Construction	2-22
2.4.9	Construction Working Hours	2-22
2.4.10	Construction Personnel	2-22
2.4.11	Construction Vehicles	2-23
2.4.12	Monitoring and Control	2-23
2.4.12.1	Construction Environmental Management Plan (CEMP).....	2-23
2.4.12.2	Waste Management	2-24
2.4.12.3	Health and Safety	2-24
2.5	Decommissioning.....	2-26
2.6	The Use of Natural Resources	2-27
2.6.1	Aggregate.....	2-27
2.6.2	Water	2-27
2.7	The Production of Waste.....	2-27
2.7.1	Domestic Waste-Water Effluent	2-27
2.7.2	General Wastes	2-27
2.8	Emissions and Nuisances.....	2-28
2.9	Transboundary Effects.....	2-28
2.10	Risk of Major Accidents and Disasters.....	2-28
2.10.1.1	Fire/ Fuels	2-29

Chapter 3 Consideration of Need and Reasonable Alternatives

3.	Consideration of Need and Reasonable Alternatives	3-1
3.1	Introduction	3-1
3.2	Need and Objectives of the Project.....	3-1

3.3	Alternative Deep Water Quay Sites and Shapes	3-2
3.3.1	2002 Planning Application Alternatives Analysis	3-3
3.3.1.1	Site Selection	3-3
3.3.1.2	Quay Shape Alternatives	3-6
3.3.1.3	2002 Proposed Option	3-6
3.3.2	2017 Planning Application	3-7
3.4	Alternative Deep Water Quay Construction Methodologies (2023-2024)	3-8
3.4.1	Suspended Deck Option	3-8
3.4.2	Sheet-piled Wall Option	3-8
3.4.3	Caisson Construction	3-9
3.4.4	Preferred Quay Wall Construction Method and Environmental Assessment	3-9
3.5	Alternative Blasting and Dredging Options	3-9
3.5.1	Jack-Up Pontoon Method	3-10
3.5.2	Blasting Platforms Method	3-13
3.5.3	Environment Comparison of Blasting and Dredging Methods	3-13
3.6	Do Nothing Scenario	3-14
3.7	Conclusion	3-15
3.8	References	3-15

Chapter 4 Population & Human Health

4.	Population & Human Health	4-1
4.1	Introduction	4-1
4.2	Methodology	4-1
4.2.1	Scope of the Assessment	4-1
4.2.1.1	Human Health	4-2
4.2.1.2	Tourism and Amenities	4-3
4.2.1.3	Assessment of Effects and Significance	4-3
4.2.2	Desk Study	4-5
4.2.3	Study Area	4-5
4.3	Baseline Environment	4-6
4.3.1	Development Location and Description	4-6
4.3.2	Population Trends and Density	4-6

4.3.3	Settlement Patterns	4-7
4.3.4	Land Use	4-7
4.3.5	Public Health.....	4-8
4.3.6	Economic Activity/ Employment	4-9
4.3.7	Tourism and Amenities	4-10
4.4	Assessment of Effects	4-10
4.4.1	Construction Activities Overview	4-10
4.4.2	Mitigation Measures for Construction Phase	4-11
4.4.3	Assessment of the Significance of Effects.....	4-11
4.4.3.1	Population and Settlement.....	4-11
4.4.3.2	Land Use	4-12
4.4.3.3	Human Health	4-13
4.4.3.4	Employment and Economic Activity	4-14
4.4.3.5	Tourism and Amenity.....	4-15
4.5	Remedial Mitigation and Residual Effects	4-15
4.6	Cumulative Effects	4-16
4.7	Conclusion.....	4-16
	References.....	4-16

Chapter 5 Terrestrial Ecology

5.	Terrestrial Ecology	5-1
5.1	Introduction	5-1
5.1.1	Methodology	5-1
5.1.2	Legislation and Best Practice Guidance	5-2
5.1.3	Definition of Zone of Influence (ZOI).....	5-2
5.1.4	Desktop Study.....	5-2
5.1.4.1	Database Searches and Data Requests.....	5-3
5.1.5	Consultation	5-3
5.1.6	Definition of Study Area.....	5-4
5.1.7	Field Surveys.....	5-4
5.1.7.1	Habitat and Flora Survey	5-4
5.1.7.2	Non-Volant Mammals Survey.....	5-5

5.1.7.3	Bats	5-6
5.1.7.4	Bird Survey.....	5-6
5.1.7.5	Invertebrates and Herpetofauna Survey	5-6
5.1.8	Ecological Evaluation Criteria	5-7
5.1.9	Impact Assessment Criteria	5-7
5.2	Appropriate Assessment Screening and Natura 2000 Impact Statement.....	5-8
5.3	Baseline Environment.....	5-8
5.3.1	Site Location	5-8
5.3.2	Development Site	5-9
5.3.3	Local Hydrology	5-10
5.3.4	Designated Sites	5-13
5.3.4.1	Sites of International Importance	5-13
5.3.4.2	Sites of National Importance	5-17
5.3.4.3	Additional Sites.....	5-17
5.3.5	Habitat Survey	5-18
5.3.5.1	Buildings and Artificial Surfaces (BL3)	5-18
5.3.5.2	Sea Walls, Piers and Jetties (CC1).....	5-19
5.3.5.3	Recolonising Bare Ground (ED3)	5-19
5.3.5.4	Scrub (WS1)	5-19
5.3.5.5	Dry-Humid Acid Grassland (GS3).....	5-19
5.3.5.6	Open Marine Water (MW1)	5-19
5.3.5.7	Coastal Lagoon and Saline Water (CW1)	5-19
5.3.5.8	Exposed Siliceous Rock (ER1)	5-20
5.3.5.9	Dry Siliceous Heath (HH1)	5-20
5.3.6	Rare and Protected Flora	5-20
5.3.6.1	Desktop Study and Field Survey	5-20
5.3.7	Invasive Alien Species (IAS)	5-25
5.3.7.1	Desk Study	5-25
5.3.7.2	Field Study	5-25
5.3.8	Mammals (excluding bats).....	5-25
5.3.8.1	Desk Study	5-25
5.3.8.2	Field Surveys.....	5-26
5.3.9	Bats	5-26

5.3.9.1	Desk Study	5-26
5.3.9.2	Field Surveys.....	5-27
5.3.10	Birds	5-27
5.3.10.1	Desk Study	5-27
5.3.10.2	Field Survey	5-28
5.3.11	Reptiles & Amphibians	5-29
5.3.11.1	Desk Study	5-29
5.3.11.2	Field Surveys.....	5-29
5.3.12	Terrestrial Macro-invertebrates.....	5-29
5.3.12.1	Desk Study	5-29
5.3.13	Identification of IEFs.....	5-29
5.3.13.1	Selection of Designated Sites as IEFs	5-29
5.3.13.2	Selection of Habitats as IEFs	5-30
5.3.13.3	Selection of Flora and Fauna Species as IEFs.....	5-31
5.4	Description of Likely Effects	5-35
5.4.1	Construction Phase Activities Overview	5-35
5.4.2	Construction Phase Mitigation Measures.....	5-35
5.4.2.1	Construction Phase Mitigation Measures	5-35
5.4.2.2	Current Phase Mitigation Measures	5-36
5.4.3	Construction Phase Effects	5-37
5.4.3.1	Noise	5-37
5.4.3.2	Habitat Destruction.....	5-38
5.4.3.3	Pollution.....	5-39
5.4.3.4	Introduction of Non-native Invasive Species	5-40
5.4.3.5	Mammals (excluding Bats)	5-40
5.4.3.6	Birds	5-41
5.4.3.7	Reptiles and Amphibians	5-43
5.4.3.8	Terrestrial Macro-Invertebrates.....	5-44
5.4.3.9	Water Quality	5-44
5.4.4	Current Effects from Incomplete Works	5-45
5.5	Residual Effects	5-46
5.6	Cumulative Effects	5-48
5.6.1.1	Plans.....	5-48

5.6.1.2	Permitted and Developments in the Locality	5-49
5.6.1.3	EPA Licenced/Registered Facilities.....	5-49
5.6.1.4	Existing Land-use and On-going Activities	5-49
5.6.1.5	Potential for Significant In-combination Effects.....	5-50
5.7	Conclusion	5-50
5.8	References	5-51

Chapter 6 Land and Soils

6.	Land and Soils	6-1
6.1	Introduction	6-1
6.2	Methodology.....	6-1
6.2.1	Desktop Review	6-1
6.2.2	Site Investigation Methodology	6-2
6.2.3	Geophysical Survey	6-4
6.3	Site Location.....	6-5
6.4	Baseline Environment.....	6-6
6.4.1	Land Use	6-6
6.4.2	Regional & Quaternary Geology.....	6-7
6.4.3	Local Geology	6-9
6.4.4	Seabed Geology.....	6-9
6.4.5	Geological Heritage	6-10
6.4.6	Soils and Subsoils	6-11
6.4.7	Groundwater	6-13
6.4.8	Geohazards.....	6-14
6.5	Description of Likely Effects	6-14
6.5.1	Construction Activities	6-14
6.5.2	Mitigation Measures for Construction Works	6-15
6.5.3	Construction Phase Effects	6-15
6.5.3.1	Change of Land Use	6-15
6.5.3.2	Effects on Soils and Geology from Drilling, Blasting, Dredging and Reclamation	6-16
6.5.3.3	Deep Water Quay Foundations.....	6-17
6.5.4	Effects associated with the current status of the site	6-17

6.6	Residual Effects	6-18
6.7	Cumulative Effects	6-18
6.8	Conclusion	6-18
6.9	References	6-18

Chapter 7 Land and Soils

7.	Water	7-1
7.1	Introduction	7-1
7.2	Methodology	7-1
7.2.1	Legislation and Best Practice	7-1
7.2.1.1	Water Framework Directive (WFD) (2000/60/EC)	7-1
7.2.1.2	Water Framework Directive – Protected Area	7-3
7.3	Site Location	7-3
7.4	Baseline Environment	7-5
7.4.1	Hydrology	7-5
7.4.2	Hydrogeology	7-8
7.4.2.1	Bedrock	7-8
7.4.2.2	Groundwater Body and Vulnerability	7-8
7.4.2.3	Aquifer Classification	7-8
7.4.2.4	Abstractions (Wells and Springs)	7-11
7.4.3	Flood Risk	7-11
7.5	Description of Likely Effects	7-12
7.5.1	Construction Phase Activities Overview	7-12
7.5.2	Construction Phase Mitigation Measures	7-12
7.5.3	Construction Phase Effects Assessment	7-12
7.5.3.1	Drilling, Blasting, Dredging	7-13
7.5.3.2	Land reclamation	7-14
7.5.3.3	Surface Water Run-off	7-15
7.5.3.4	Oils and Fuel Usage and Storage	7-15
7.5.3.5	Use of Concrete	7-16
7.5.3.6	Flooding	7-16
7.5.4	Current Phase Effects	7-17
7.6	Remedial Mitigation and Residual Effects	7-17

7.7	Conclusion	7-18
7.8	References	7-19

Chapter 8 Marine

8.	Marine	8-1
8.1	Introduction	8-1
8.2	Competency of Assessor	8-1
8.3	Methodology.....	8-1
8.3.1	Legislation and Best Practice Guidelines	8-1
8.3.2	Definition of Study Area.....	8-5
8.3.3	Desktop Study.....	8-8
8.3.4	Field Surveys	8-8
8.3.4.1	Benthic Grab Survey	8-8
8.3.4.2	Drop Down Video Survey.....	8-10
8.3.4.3	Sediment Sampling	8-12
8.4	Baseline Characterisation.....	8-13
8.4.1	Benthic Communities.....	8-13
8.4.1.1	Benthic Fauna.....	8-13
8.4.2	Sediment Characteristics	8-15
8.4.3	Sediment Physio-chemistry	8-17
8.4.4	Sediment Radiological Analysis	8-23
8.4.5	Marine Mammals and Marine Megafauna.....	8-23
8.4.6	Fish and Shellfish	8-27
8.4.6.1	Anadromous and Catadromous Species.....	8-27
8.4.6.2	Marine Species	8-27
8.4.6.3	Commercial and Recreational Fisheries.....	8-28
8.4.7	Important Ecological Features.....	8-28
8.5	Criteria for Assessment of Likely Effects	8-29
8.6	Construction Phase Activities Overview	8-32
8.7	Construction Phase Mitigation Measures	8-32
8.7.1	Pollution Control	8-32
8.7.2	Invasive Alien Species	8-33

8.7.3	Marine Mammal Mitigation	8-33
8.7.3.1	Dredging	8-33
8.7.3.2	Drilling.....	8-33
8.7.3.3	Blasting	8-34
8.7.4	Compliance with Marine Mammal Mitigation Measures	8-34
8.8	Current Site Status Mitigation.....	8-36
8.9	Assessment of Construction Phase Post-Mitigation Effects.....	8-37
8.9.1	Habitat Disturbance or Structure Change.....	8-37
8.9.1.1	Sensitivity of IEFs.....	8-37
8.9.1.2	Magnitude of Impact	8-39
8.9.1.3	Significance of Habitat Disturbance/Change Effect	8-39
8.9.2	Suspended Sediments, Smothering and Siltation Rate Changes	8-40
8.9.2.1	Sensitivity of IEFs.....	8-40
8.9.2.2	Magnitude of Smothering Effect.....	8-43
8.9.2.3	Significance of Smothering Effect	8-43
8.9.3	Underwater Noise Effects from Reclamation and Dredging.....	8-45
8.9.3.1	Sensitivity of IEFs to underwater noise from land reclamation and dredging	8-46
8.9.3.2	Magnitude of Impact	8-51
8.9.3.3	Significance of Likely Underwater Noise Effect from land reclamation and dredging.....	8-52
8.9.4	Underwater Noise Effects from Drilling	8-54
8.9.4.1	Sensitivity of IEFs to Drilling	8-55
8.9.4.2	Magnitude of Impact	8-56
8.9.4.3	Significance of Likely Underwater Noise Effects from Drilling	8-57
8.9.5	Underwater Noise Effects from Blasting.....	8-59
8.9.5.1	Sensitivity of IEFs to Blasting	8-60
8.9.5.2	Magnitude of Impact	8-61
8.9.5.3	Significance of Likely Effects from Underwater Noise Effect from Blasting	8-63
8.9.6	Likely Significant Noise Effect of Non-Compliance with Mitigation Measures	8-65
8.9.6.1	Likely Significant Noise Effect of Non-Compliance with Marine Mammal Mitigation Measures 8-65	
8.9.6.2	Likely Significant Noise Effects of Non-Compliance on Atlantic Salmon and Sea Trout	8-66
8.9.7	Death or Injury by Collision.....	8-67
8.10	Assessment of Current Site Status Effects	8-68
8.10.1	Permanent Loss of Habitat or Change of Habitat Type Due to Presence of Infrastructure	8-68

8.10.1.1	Sensitivity of IEFs to Operational Effects	8-69
8.10.1.2	Magnitude of Impact	8-69
8.10.1.3	Significance of Likely Effect	8-69
8.11	Residual Effects and Remediation Measures	8-70
8.11.1	Marine Mammals	8-71
8.11.2	Atlantic Salmon and Sea Trout	8-71
8.12	Cumulative Effects (rEIAR)	8-76
8.13	Conclusion	8-77
	References.....	9-78

Chapter 9 Material Assets – Built Infrastructure

9.	Material Assets – Built Infrastructure	9-1
9.1	Introduction	9-1
9.2	Assessment Methodology	9-1
9.2.1	Scope of Assessment.....	9-1
9.2.2	Desk Study	9-2
9.2.3	Legislation, Policy and Guidance	9-2
9.2.4	Study Area	9-3
9.2.5	Assessment Criteria.....	9-4
9.2.6	Statement on Limitations and Difficulties Encountered	9-4
9.3	Baseline Environment.....	9-5
9.3.1	Baseline Assessment Prior to January 2023	9-5
9.3.1.1	Grid Capacity and Electricity Infrastructure	9-5
9.3.1.2	Wastewater Infrastructure	9-5
9.3.1.3	Water Supply	9-6
9.3.1.4	Surface Water Drainage.....	9-6
9.3.1.5	Telecommunications.....	9-7
9.3.1.6	Gas	9-7
9.3.1.7	Waste Management	9-7
9.4	Description of Likely Effects	9-7
9.4.1	Construction Phase Activities Overview	9-7
9.4.2	Construction Phase Mitigation Measures.....	9-8

9.4.3	Construction Phase Effects Assessment	9-8
9.4.3.1	Grid Capacity and Electricity Infrastructure	9-8
9.4.3.2	Wastewater Infrastructure	9-9
9.4.3.3	Water Supply	9-9
9.4.3.4	Surface Water Drainage.....	9-10
9.4.3.5	Telecommunications.....	9-10
9.4.3.6	Gas	9-10
9.4.3.7	Waste Management	9-11
9.4.4	Current Phase Effects.....	9-11
9.5	Remedial Mitigation and Residual Effects	9-11
9.6	Cumulative Effects	9-12
9.7	Conclusion	9-12
	References.....	9-13

Chapter 10 Archaeological and Cultural Heritage Assessment

10.	Archaeological and Cultural Heritage Assessment	10-1
10.1	Introduction	10-1
10.2	Methodology.....	10-1
10.2.1	Desktop Study.....	10-1
10.2.2	Study Area	10-2
10.2.3	Field Inspection	10-2
10.2.3.1	Terrestrial Field Inspection	10-2
10.2.3.2	Marine Field Inspection	10-2
10.2.4	Legislation and Best Practice	10-3
10.2.4.1	National Monuments.....	10-3
10.2.4.2	Preservation Orders/Temporary Preservation Orders.....	10-3
10.2.4.3	Register of Historic Monuments	10-3
10.2.4.4	The Record of Monuments and Places	10-4
10.2.4.5	Protection under the Architectural Heritage (National Inventory) and Historic Monuments (Miscellaneous Provisions) Act 1999	10-4
10.2.4.6	Record of Protected Structures (RPS) and Architectural Conservation Areas (ACA)	10-4
10.3	Baseline Environment.....	10-4
10.3.1	Site Context	10-4

10.3.2	Historical Background and Townland	10-5
10.3.3	Cartographic Information	10-5
10.3.4	Excavation Evidence	10-7
10.4	Archaeological Environment	10-7
10.4.1	Prehistoric Period	10-7
10.4.2	Neolithic Period	10-8
10.4.3	Chalcolithic Period	10-8
10.4.4	Bronze Age Period	10-8
10.4.5	Iron Age Period	10-8
10.4.6	Historic Period	10-8
10.4.7	Development Area	10-12
10.5	Description of Likely Effects	10-13
10.5.1	Construction Activities	10-13
10.5.2	Mitigation Measures Applied	10-13
10.5.3	Construction Phase Impacts	10-14
10.5.4	Current Status Effects	10-15
10.6	Remedial Mitigation and Residual Effects	10-15
10.7	Cumulative Effects	10-15
10.8	Conclusion	10-16

Chapter 11 Noise and Vibration

11.	Noise & Vibration	11-1
11.1	Introduction	11-1
11.1.1	Fundamentals of Noise	11-1
11.2	Methodology	11-1
11.2.1	Guidelines and Best Practice	11-2
11.2.2	Study Area and Noise Sensitive Locations	11-2
11.2.3	Baseline Noise Survey	11-3
11.2.4	Noise Survey Equipment and Instrumentation	11-4
11.2.5	Weather Conditions	11-5
11.2.6	Assessment Criteria	11-5
11.2.6.1	Significance of Effects	11-5

11.2.6.2	Sensitivity.....	11-5
11.2.6.3	Magnitude of Impacts.....	11-6
11.2.6.4	Construction Phase – Vibration Impacts.....	11-8
11.2.6.5	Operational Phase – Noise and Vibration Impacts.....	11-9
11.2.7	Statement on Limitation and Difficulties Encountered.....	11-9
11.3	2016 Baseline Noise Survey Results and Discussion.....	11-9
11.4	Description of Likely Effects	11-11
11.4.1	Construction Phase Activities Overview	11-11
11.4.2	Construction Phase Mitigation Measures and Monitoring.....	11-11
11.4.3	Construction Phase Effects Assessment	11-12
11.4.3.1	Construction Noise.....	11-12
11.4.3.2	Construction Road Traffic Noise.....	11-12
11.4.3.3	Construction Vibration.....	11-13
11.4.4	Current Phase Effects.....	11-15
11.5	Remedial Mitigation and Residual Effects.....	11-15
11.6	Cumulative Effects	11-16
11.7	Conclusion.....	11-16
	References.....	11-17

Chapter 12 Air Quality and Climate

12.	Air and Climate.....	12-1
12.1	Introduction	12-1
12.1.1	Guidelines and Legislation	12-1
12.1.1.1	Air Quality.....	12-1
12.1.1.2	Climate.....	12-3
12.1.1.3	National Climate Action Plan 2023	12-3
12.1.1.4	Local Policy and Guidelines	12-4
12.2	Methodology.....	12-5
12.2.1	Scope of Assessment.....	12-6
12.2.2	Assessment of Dust sensitivity of Receptors	12-6
12.2.3	Assessment Criteria.....	12-9
12.2.3.1	Air Quality.....	12-9

12.2.3.2	Climate.....	12-11
12.2.4	Statement on Limitations and Difficulties Encountered	12-12
12.3	Existing Environment.....	12-13
12.3.1	Air Quality	12-13
12.3.2	Climate.....	12-14
12.3.2.1	Global Climate Trends.....	12-14
12.3.2.2	National Greenhouse Gas Emissions	12-15
12.3.2.3	Local Climate	12-15
12.4	Construction Activities.....	12-17
12.5	Mitigation Measures Applied	12-18
12.5.1	Dust and Air Quality	12-18
12.5.2	Odour	12-18
12.5.3	Traffic Emissions.....	12-18
12.5.4	Greenhouse Gas Emissions.....	12-18
12.6	Assessment of the Effects of the Development.....	12-19
12.6.1	Air Quality and Dust Effects	12-19
12.6.2	Odour	12-24
12.6.3	Greenhouse Gas Assessment (GHHA)	12-25
12.7	Remedial Mitigation and Residual Effects	12-26
12.8	Cumulative Effects	12-27
12.9	Conclusions	12-27
12.10	References	12-28

Chapter 13 Landscape & Visual Impact Assessment

13.	Landscape & Visual Impact Assessment.....	13-1
13.1	Introduction	13-1
13.2	Methodology.....	13-1
13.2.1	Guidelines and Best Practice	13-1
13.2.2	Study Area	13-2
13.2.3	Desk Study	13-2
13.2.4	Assessment Criteria.....	13-2
13.2.4.1	Landscape/Seascape Effects.....	13-2

13.2.4.2	Visual Effects	13-4
13.3	Baseline Environment.....	13-7
13.3.1	Landscape/Seascape Baseline	13-7
13.3.1.1	Coastline Characteristics	13-7
13.3.1.2	Centres of Population and Houses.....	13-7
13.3.1.3	Transport Routes.....	13-8
13.3.1.4	Public Amenities and Facilities	13-9
13.3.2	Landscape Policy Context and Designations.....	13-9
13.3.2.1	Galway County Development Plan (2022-2028)	13-9
13.3.2.2	Landscape/Seascape Value and Sensitivity	13-10
13.3.2.3	Designated Views and Prospects	13-12
13.3.3	Visual Baseline	13-14
13.3.3.1	Zone of Theoretical Visibility (ZTV)	13-15
13.4	Description of Effects	13-18
13.4.1	Construction Activities	13-18
13.4.2	Mitigation Measures	13-19
13.4.3	Landscape/Seascape Effect Assessment.....	13-19
13.4.3.1	Magnitude of Landscape/Seascape Effects	13-19
13.4.3.2	Significance of Landscape/Seascape Effects.....	13-20
13.4.4	Visual Effect Assessment	13-20
13.4.5	Effect Summary	13-22
13.5	Remedial Mitigation and Residual Effects	13-22
13.6	Cumulative Effects	13-23
13.7	Conclusion	13-23

Chapter 14 Material Assets – Traffic & Transport

14.	Material Assets – Traffic & Transport	1
14.1	Introduction	1
14.2	Methodology.....	1
14.2.1	Legislation, Policy and Guidance References.....	1
14.2.2	Assessment Criteria.....	1
14.2.2.1	Forecasting Methods	1
14.3	Baseline Environment.....	2

14.3.1	Baseline Environment prior to January 2023	2
14.3.1.1	Roads and Transport Network	2
14.3.1.2	Traffic Volumes	4
14.3.2	Baseline Environment 26 th January 2023 to 20 th May 2024	8
14.3.2.1	Roads and Transport Network	8
14.3.2.2	Traffic Volumes	8
14.4	Description of Likely Effects	11
14.4.1	Construction Phase Activities	11
14.4.2	Mitigation Measures Applied	12
14.4.3	Traffic for previous works undertaken between 26 th January 2023 and 10 th July 2023	12
14.4.3.1	Traffic Effect Rating.....	15
14.4.4	Traffic for Previous Works between 11 th July 2023 and 20 th May 2024	16
14.4.4.1	Traffic Effect Rating.....	21
14.5	Current Status (Post-Construction) TrafficEffects.....	21
14.6	Remedial Mitigation and Residual Effects	21
14.7	Cumulative Effects	21
14.8	Risk of Major Accidents and Disasters.....	22

Chapter 15 Interaction of the Foregoing

15.	Interaction of the Foregoing	15-1
15.1	Introduction	15-1
15.2	Identification of Environmental Effects	15-1
15.2.1	Population and Human Health	15-1
15.2.2	Traffic and Transportation	15-2
15.2.3	Terrestrial Ecology.....	15-2
15.2.4	Water	15-3
15.2.5	Marine.....	15-3
15.2.6	Land and Soils	15-3
15.2.7	Air and Climate	15-4
15.2.8	Noise and Vibration.....	15-4
15.2.9	Landscape and Visual	15-5
15.2.10	Archaeology and Cultural Heritage	15-5

15.2.11	Material Assets	15-5
15.3	Conclusion	15-7

Chapter 16 Schedule of Mitigation

16.	Schedule of Mitigation	16-1
16.1	Introduction	16-1
16.2	Mitigation Measures Undertaken During the Works	16-1
16.2.1	Blasting and Dredging	16-1
16.2.2	Chemical management	16-1
16.2.3	Concrete Management	16-2
16.2.4	Refuelling Facilities	16-2
16.2.5	Waste Management	16-2
16.2.6	Traffic and Transport management	16-3
16.2.7	Plant and Machinery management	16-3
16.2.8	Staff Training	16-4
16.2.9	Public Relations	16-4
16.2.10	Protection of Archaeological and Cultural Heritage	16-4
16.2.11	Noise	16-5
16.2.12	Vibration Management	16-5
16.2.13	Population and Human Health	16-6
16.2.14	Terrestrial Ecology	16-6
16.2.15	Land and Soils	16-7
16.2.16	Water	16-8
16.2.17	Marine	16-9
16.2.17.1	Pollution Control	16-9
16.2.17.2	Invasive (Marine) Alien Species Management	16-9
16.2.17.3	Marine Mammal Mitigation	16-9
16.2.18	Material Assets	16-10
16.2.19	Air Quality and Climate	16-11
16.2.19.1	Dust and Air Quality	16-11
16.2.19.2	Odour	16-11
16.2.19.3	Traffic Emissions	16-11

16.2.19.4	Greenhouse Gas Emissions.....	16-12
16.2.20	Landscape and Visual Mitigations	16-12
16.3	Monitoring during the Previous Works	16-12
16.3.1	Alien Invasive Plant Species (IAPS)	16-12
16.3.2	Turbidity Monitoring.....	16-12
16.3.3	Vibration Monitoring	16-14
16.3.4	Marine Mammal Observation and Monitoring	16-15
16.3.5	Archaeological monitoring.....	16-15
16.4	Remedial Mitigation Measures	16-16