



Appendix 14.1

Sites in the Record of Monuments and Places

CW006-001---- Ringfort - rath : CLOGRENAN

Circular area (diam. c. 23m) enclosed by earthen bank and external fosse which may have been deepened when used as haggard. Entrance not identifiable. On sloping ground.

CW007-039001- : Church : CLOGRENAN

In the NE sector of a rectangular graveyard (CW007-039003-). Undifferentiated late medieval parish church of Cloydagh. According to ITA Survey (1945), church attached to Augustinian Monastery of Great Connall, Co. Kildare. Remains consist of rectangular church (ext dims. 19.3m x 7.10m), of limestone rubble with granite quoins. Church has opposed N and S doorways and late medieval window with pointed arch of chamfered granite. Plain window in S wall of chancel. May incorporate parts of earlier structure, suggested by blocked narrow lintelled ope in N wall close to W end. Door in S wall formerly included face mask with bulbous features (possibly modern) on W jamb; arch and jamb now removed. Piscina with moulded granite surround at E end of S wall. Incorporated in W gable is stone with incised cross, of pre-Norman date.

CW007-039002- : Cross-inscribed stone : CLOGRENAN

Incorporated into W gable of church (CW007-039001-) is a stone with incised cross, of pre-Norman date.

CW007-039003- : Graveyard : CLOGRENAN

A roughly rectangular graveyard (map dims. c. 32m N-S; c. 73m E-W) with the late medieval parish church (CW007-039001-) of Cloydagh in the NE sector. According to ITA Survey (1945) the church was attached to Augustinian Monastery of Great Connall, Co. Kildare.

LA037-004---- : Ringfort - unclassified : CLOGRENAN

Situated in an upland area. Marked on the 1841 edition of the OS 6-inch map; a circular 'fort' (max. diam. c. 20m). No visible surface remains.

LA037-007---- : Ringfort - rath : CLOGRENAN

Not marked on the 1841 edition of the OS 6-inch map. A circular area (diam. c. 47.3m) defined by an earthen bank (Wth c. 2.3m; int. H c. 0.5m, ext. H c. 1.8m) and external fosse (Wth c. 3.4m) from SE-NE. Possible original entrance at E.



Appendix 14-2

Sites in the Sites and Monuments Record

WX027-050---- Ballyconnigar Upper Redundant record

Scheduled for inclusion in the next revision of the RMP: No

Situated on the N-facing slope of an esker ridge. An aerial photograph (GSIAP BDR 21) shows no evidence of any ancient monuments.